

July 27, 2023

Darius Lisowski, Matthew Jasica, Qiuping Lv, Zhiee Ooi, Rui Hu, Mitch Farmer
Argonne National Laboratory

Water-Cooled Natural Convection Shutdown Heat Removal Test Facility (NSTF) Status and Recent Data Results

DOE ART Gas-Cooled Reactor (GCR) Review Meeting

Virtual Meeting


July 25 – 27, 2023



Introduction: NSTF at Argonne

Natural Convection Shutdown Heat Removal Test Facility (NSTF) was initiated in support of DOE programs: NGNP, SMR, and ART

- Air-based testing program (completed, FY13 - FY16)
- Water-based testing program (on-going, FY18 to present)
- Top level objectives of NSTF program at Argonne:
 - passive safety and decay heat removal for advanced concepts
 - generate NQA-1 qualified licensing data for industry
 - provide benchmark data for code V&V
- Concurrent with a broader scope and multiple collaborators
 - Experimental facilities at scales ($\frac{1}{2}$, $\frac{1}{4}$, etc.) for both air and water
 - Complimenting CFD modeling and 1D system level analysis
 - Collaborating towards development of a central data bank



Full Scale



UW-Madison



Argonne



1/2-concept



Idaho National Laboratory

FY23 Work Packages & Deliverables

Work Package	Activity	Months	Funding
AT-22AN060201	Program Administration & NQA-1	12	\$100K
RD-22AN050201	Experimental Testing & Computational Analysis	12	\$880K

- Funding from Gas-Cooled Reactor Campaigns in ART and ARRD
 - Separate packages for program management and testing/analysis
 - Reduction from previous years, currently funded at minimum level to cover staff / overhead
- Computational analysis, partially unfunded in previous years, returned to FY23
 - Limited to only RELAP5 two-phase development (no CFD)
- Completion of year-end deliverables is on schedule

Level	Work Package / Deliverable	Due Date	Status
L3	M3RD-23AN0502014 Progress report on RELAP5 modeling of NSTF two-phase	09/08/2023	<i>On Schedule</i>
L2	M2RD-23AN0502013 Test report detailing experimental results from FY23 parametric	09/08/2023	<i>On Schedule</i>

Program Quality Assurance

- Regular audits, or assessments, maintain compliance to NQA-1
 - Following requirements of ASME NQA-1 2008 with 2009 addendum
 - Small team of dedicated individuals with strong management support
 - Primary purpose is generating and packaging high-quality data

<u>Date</u>	<u>Audit Type</u>			<u>Lead Auditor</u>
Spring 2014, 03/18 – 20/2014	<input type="checkbox"/> MA	<input type="checkbox"/> Internal	<input checked="" type="checkbox"/> External	Kirk Bailey (INL)
Winter 2014, 02/16 – 18/2015	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Summer 2015, 07/20 – 23/2015	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Fall 2015, 11/3 – 5/2015	<input type="checkbox"/> MA	<input type="checkbox"/> Internal	<input checked="" type="checkbox"/> External	Alan Trost (INL)
Winter 2016, 01/21/2016	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Summer 2016, 06/29 – 30/2016	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Fall 2016, 11/29 – 30/2016	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Fall 2017, 11/07 – 09/2017	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Spring 2018, 02/06 – 08/2018	<input type="checkbox"/> MA	<input type="checkbox"/> Internal	<input checked="" type="checkbox"/> External	Michelle Sharp (INL)
Summer 2018, 05/30/2018	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Winter 2019, 01/29 – 30/2019	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Winter 2020, 02/18 – 19/2020	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Spring 2020, 03/17 – 19/2020	<input type="checkbox"/> MA	<input type="checkbox"/> Internal	<input checked="" type="checkbox"/> External	R. Dieter (Kairos)
Fall 2020, 08/25 – 27/2020	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Summer 2021, 09/07 – 09/2021	<input type="checkbox"/> MA	<input checked="" type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Spring 2022, 04/25 – 28/2022	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)
Spring 2023, 02/21 – 23/2023	<input type="checkbox"/> MA	<input type="checkbox"/> Internal	<input checked="" type="checkbox"/> External	Michelle Sharp (INL)
Spring 2023, 05/30 – 31/2023	<input checked="" type="checkbox"/> MA	<input type="checkbox"/> Internal	<input type="checkbox"/> External	Roberta Riel (ANL)

NQA-1 2008/2009a compliant

Summary of FY23 Accomplishments To-Date


- Hosted program review meeting, December 2022
 - Held every 1 – 2 years since 2010 with the purpose to gather feedback from external groups on progress, direction, and accomplishments of the NSTF program
 - This years meeting included participation from Federal (DOE, INL, NRC), Industry (Framatome, Kairos, X-Energy), US Univ. (TAMU, UW-Madison)
- Formal external audit for NQA-1 compliance, February 2023 (✓ *compliant*)
- Continuation of two-phase matrix testing
 - Off-normal test conditions with expansion of blocked riser conditions; Expansion of depleted inventory condition with focus on refill methods
 - Introduced flow restriction at tank inlet for parametric loss testing
- Data packaging and exchange with active US vendors
 - Comprehensive packaging of previously collected data including both air & water cases dating to 2013
 - Exchanged with multiple US companies in recent months
- Regular use of RELAP5 for predictive capability; supporting tests



FY23 Testing Results



Blocked riser channels (#3 & 6)

- Two-phase baseline test was repeated with riser channels #3 & 6 full blocked
 - Blockage was initiated ~2-hr prior to onset of boiling
 - Tubes were vented to prevent pressure build-up and allow liquid boil-off
- Dry-out conditions reached 1.6-hr after starting of boiling





	<u>Baseline</u>	<u>Blocked</u>	<i>diff</i>
Primary flow rate, kg/s	1.79	1.51	-15.5%
Riser flow rate, kg/s	0.227	0.258	13.4%
Heated section ΔT, °C	3.83	4.22	10.1%
Water tube, hot side °C	112.6	214.9	91.0%
Water tube, cold side °C	106.4	201.34	89.3%
Panel fins, hot side °C	133.5	177.1	32.6%
Panel fins, cold side °C	133.2	175.9	32.1%
Heated plate surface °C	340.16	343.69	1.0%
Side walls °C	181.7	179.1	-1.4%
Cold wall °C	105.8	108.8	2.8%



Depleted inventory scenario




Depleted inventory scenario




Depleted inventory scenario



Depleted inventory scenario





Depleted inventory scenario





Stagnation & instability

Stagnation of loop flow \rightarrow Quiescent fluid in risers \rightarrow Geysering





Stagnation & instability

Stagnation of loop flow \rightarrow Quiescent fluid in risers \rightarrow Geysering



Boiling delay time for geysering



Test No.	Refill Location	Refill Rate	Time to re-establish natural circulation	No. geysering events
DataQuality069	Inlet header	1.5 GPM	160 min	8+
DataQuality074	Primary tank	3.2 GPM	90 min	~6
DataQuality081	Primary tank	14.8 GPM	28 min	2-3



RELAP5 Modeling

Computational Modeling

- “Symbiotic” relationship between experimental and computational work
 - **Mutually beneficial** to both campaigns
 - Good communication between both teams
- Experimental data helps to benchmark computational modeling approaches
 - System-level measurements (e.g. mass flow rate) beneficial for RELAP5
 - Fine-grained measurements (e.g. numerous thermocouples) beneficial for CFD
 - Provides more confidence in using analysis tools for future work
- Computational studies help elucidate some physical mechanisms
 - Also provide a “sanity check” for the experimental data

Component-level CFD analysis


- Detailed cavity air flow simulations
- Header design on flow distribution
- Mixing behavior in tank
- Porosity of insulation in heated region

Integral System RELAP5 model


- Loop benchmarking
- Full length transient scenarios
- Instability analysis
- Predictive capability for test guidance

RELAP5 - Model Development


- RELAP5-3D v4.3.4
- Primary loop model:
 - Consists of pipes, branches, junction components
 - Simplified tank model
 - No secondary cooling: steam is vented to the environment
- Cavity model:
 - Natural convection modeled by pipes and branches
 - Fluid flow in the cavity is coupled to heat structures
 - 'Enclosure' system to model thermal radiation




Inlet Throttle Benchmark



Depleted Inventory Benchmark



Cavity schematic (top view)





Test Summary & Path Forward

Completed Matrix Test Case

	Test Name	Date	Duration	Purpose	Classification			
FY18	BakeOut003	06/01/2018	010h06m	Heater & insulation bake out	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input checked="" type="checkbox"/> n/a
	BakeOut004	06/07/2018	007h26m	Heater & insulation bake out	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input checked="" type="checkbox"/> n/a
	Shakedown001	07/05 – 06/2018	024h22m	Single-phase demonstration, 60% tank vol.	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input checked="" type="checkbox"/> n/a
FY19	DataQuality050	08/03/2019	008h57m	Single-phase, 1.4 MW, baseline, 80a%	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input checked="" type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality051	11/28 - 29/2018	026h53m	Single-phase, 1.4 MW, baseline, 80%, 15°ΔT	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality052	01/16 - 17/2019	029h4m	Single-phase, 2.1 MW, baseline, 80%	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality053	03/26 – 27/2019	026h52m	Single-phase, 2.1 MW, baseline, 80%, riser throttle	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality054	04/25 – 05/01	177h37m	Transient characterization; Single-phase, 700 kW, add'l	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality055	6/13 – 14/2019	026h01m	Single-phase, 2.8 MW, baseline, 80%; 42kW, add'l	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
FY20	DataQuality056	10/08 – 10/2019	054h14m	Single-phase and two-phase 2.1 MW, baseline	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality057	11/07 – 08/2019	020h24m	Two -phase 2.1 MW, baseline	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality058	12/12– 13/2019	021hm34	Two -phase 2.1 MW, baseline (repeatability)	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input checked="" type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality059	03/04 – 04/2020	019h05m	Two -phase 2.1 MW, baseline (repeatability)	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality060	06/25 – 26/2020	019h28m	Two -phase 2.1 MW, baseline, 70% inventory	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality061	09/23 – 24/2020	016h55m	Two-phase 2.1 MW, baseline; 60% inventory	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality062	11/12 – 13/2020	018h58m	Two-phase 2.1 MW, baseline; Reduced pressure	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality063	12/10 – 11/2020	022h57m	Two-phase 2.1 MW, baseline, Steady-state refill	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
FY21	DataQuality064	01/12 – 13/2021	020h34m	Two-phase 2.1 MW, baseline; Header inlet throttle	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality065	02/03 – 04/2020	017h48m	Two-phase 2.8 MW, High power	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality066	03/10 – 11/2021	021h56m	Two-phase 2.1 MW, baseline, Moderate pressure	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality067	04/07 – 08/2021	021h11m	Two-phase 2.1 MW, baseline, Moderate pressure	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality068	05/06 – 07/2021	019h12m	Two-phase 2.1 MW, baseline, High pressure	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality069	06/10 – 11/2021	022h15m	Two -phase 2.1 MW, baseline, 55% inventory	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality070	07/07 – 08/2021	025h13m	Two-phase 1.4 MW, Low power	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality071	08/11 – 12/2021	022h07m	Two-phase 2.1 MW, baseline; Header inlet throttle	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality072	02/10 - 11/2022	027h21m	Single-phase, 1.4 MW, baseline, 70% ARPA-E fault #1,2,&3	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
FY22	DataQuality073	03/16 - 17/2022	021h02m	Two-phase 2.1 MW, baseline 70% tank; Refill; Riser throttle	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality074	04/18 - 21/2022	071h45m	Framatome accident scenario, V.2 scaled x5.2, 80% initial tank	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality075	07/13 - 14/2022	019h04m	Two-phase 2.8 MW, high power, 70% tank, Transient	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality076	07/28/2022	025h47m	Static boiling, 36kWe, refill up	<input type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input checked="" type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality077	08/10/2022	014h53m	Static boiling, 36kWe, drain down	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality078	09/08 - 09/2022	023h58m	Two-phase 1.4 MW, 70%; tank, Transient, Blocked #3	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality079	10/04 - 05/2022	021h23m	Two-phase 1.75 MW, medium power, 70%; tank, Transient	<input type="checkbox"/> Accepted	<input checked="" type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
FY23	DataQuality080	11/02 - 03/2022	021h08m	Two-phase 1.75 MW, medium power, 70%; tank, Transient	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality081	11/30 – 12/01/22	019h37m	Two -phase 2.1 MW, 50% invent.; Depletion; High flow refill	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality082	01/19/2023	011h25m	Static boiling, 48kWe, drain down	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality083	03/08 – 09/2023	025h53m	Low power throttle test	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality084	04/05 – 06/2023	021h55m	High power throttle test	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
	DataQuality085	06/27 – 28/2023	019h57m	70% baseline repeatability; tank valve scoping trials	<input checked="" type="checkbox"/> Accepted	<input type="checkbox"/> Trending	<input type="checkbox"/> failed	<input type="checkbox"/> n/a
				




Activities Remaining & FY24

Continuation for remainder of FY23




- Continuation of loss coefficient / blockages for off-normal scenarios
 - Recently added throttle valve at chimney (two-phase) outlet
- Ramp-up analysis of performance and stability
 - Deep dive into two-phase phenomena and system parameters at tested conditions
 - Global identification of stable and unstable operating windows
 - Continued development of this computational modeling tools

Data packaging and exchange with active US vendors

- Comprehensive packaging of new and previously collected data



- Create short-circuit with high vapor carry over





Current & Future Role of NSTF

Outreach Effort – Industry Needs & Future of NSTF

- Because of continued support from the DOE, the NSTF program has been able to provide relevant and timely support to US vendors for development of their passive decay heat removal systems
- There is a strong interest in maximizing the DOE investment to allow continuation of this support for the evolving landscape of current and active industry technologies
- Led by the program federal manager, and in coordination with technical leads, a white paper was released in early 2023:
 - summarizes past, ongoing, and future work
 - evaluates industry gaps and inputs, identifies risks
 - considerations, options, risks, and recommendations related to disposition of the NSTF
 - recommendations for continued future use of the facility

Outreach Effort – Industry Needs & Future of NSTF

- An outreach campaign was initiated to identify future roles, purpose, and needs of the NSTF program at Argonne
 - 19 US companies were contacted requested information on their gaps and needs for passive decay heat removal in the design and development of their advanced reactor(s)
 - We received detailed communication and/or written responses from 15 companies
 - Identified strong interest in specific technologies pertaining to RCCS and RVACS
- Based on the feedback, we identified the following:
 - All reactor vendors are including *some* form of passive decay heat removal in their designs
 - Majority utilize existing technologies in a traditional form; some have incorporated hybrid concepts
 - RVACS (traditional & hybrid)
 - RCCS (air & water)
 - DRACS
 - There was curiosity in use of heat pipes for large scale heat removal, but feasibility is yet to be determined
- At the current time, the traditional RVACS and water-cooled RCCS stand out as main contenders



Vendor	Reference Reactor	Passive Heat Removal System	
		Concept Design	Working Fluid
ARC Clean Technology	ARC-100		
Boston Atomics	HC-HTGR		
BWX Technologies	BANR		
BWX Technologies	PELE		
Framatome	SC-HTGR		
GE - Hitachi	PRISM		
GE - Hitachi	BWRX-300		
General Atomics	FMR		
General Atomics	EM ²		
Holtec Intl.	SMR-160		
Kairos Power	KP-FHR		
NNSA	Generic		
Oklo	Aurora		
Southern Co.	MCFR		
TerraPower	Sodium		
Terrestrial Energy	ISMR		
Ultra Safe Nuclear	MMR		
US NRC	Generic		
Westinghouse	LFR		
Westinghouse	eVinci		
X-Energy	Xe-100		

redacted

Breadth & Impact of NSTF Program

- Facility infrastructure reflects a generic containment and reactor vessel, able to generate decay heat load representative of nearly *any* reactor design by US vendors (LWR, SFR, GFR, MSR, SMR, etc.)
 - 6.7 m (22 ft.) heated section
 - 23 kW/m² / 500°C peak RPV power
- Overall program has been on-going since 2013
 - Industry collaboration with Kairos, Framatome, Boston Atomics and Westinghouse
 - Provided JAEA and US vendors with validation data
- Testing matrix covers broad range of expected, design-basis accident, and off-normal scenarios

	<u>Water</u>	<u>Air</u>
Duration	61-month	33-month
Active Hours	1,288-hr	2,250-hr
Data-Quality	32	27
<i>Accepted</i>	26	16
<i>Trending</i>	8	7
<i>Failed</i>	3	4
Total Runs	54	40




Short circuit air by-pass scenario


Chugging during inventory depletion scenario



Stabilization of two-phase oscillations



Program Timeline



Acknowledgements

This work was supported by the U.S. Department of Energy Office of Nuclear Energy, Office of Advanced Reactor Concepts under contract number DE-AC02-06CH11357.

Argonne Project Personnel	
Project Manager	Mitch Farmer
Principal Investigator	Darius Lisowski
Lead Experimenter	Qiuping Lv
Test & Instrumentation	Matthew Jasica
Quality Assurance	John Woodford
Facility Designer	Dennis Kilsdonk
Laboratory Technical	Art Vik Nathan Bremer

Argonne Analysis Support Team	
Computer Modeling	Rui Hu Adam Kraus Zhiee Ooi

Program Sponsors	
Federal	Matthew Hahn
Technical	Gerhard Strydom Mike Davenport Paolo Balestra

Guidance / Consultation	
External Guidance	Jim Kinsey Lew Lommers Sud Basu Mike Salay Brian Woods Farshid Shahrokhi Michael Corradini Yassin Hassan

Notable Mentions, Past Involvement	
Modeling	David Pointer Elia Merzari Matt Bucknor Constantine Tzanos
Program Support	Tom Wei Craig Gerardi Diana Croson Steve Reeves Diana Li Hans Gougar
Laboratory Support	Bruce Herdt Tony Tayofa Steve Lomperski



THANK YOU