



PC-000586  
Revision 0

# ENGINEERING SERVICES FOR THE NEXT GENERATION NUCLEAR PLANT (NGNP) WITH HYDROGEN PRODUCTION

## Technology Development Road Mapping Report for NGNP with 750°C Reactor Outlet Helium Temperature

Prepared by General Atomics  
For the Battelle Energy Alliance, LLC

Subcontract No. 00075309  
Uniform Filing Code UFC:8201.3.1.2

GA Project 30302









**PROJECT CONTROL ISSUE SUMMARY**

GA 2175 (1199E)

DOC. CODE RGN	PROJECT 30302	DOCUMENT NO. PC-000586	REV. 0
------------------	------------------	---------------------------	-----------

**TITLE:**

Technology Development Road Mapping Report for NGNP with 750°C Reactor Outlet Helium Temperature

CM APPROVAL/ DATE	REV.	PREPARED BY	APPROVALS		REVISION DESCRIPTION/ W.O. NO.
			RESOURCE/ SUPPORT	PROJECT	
 <b>MAY 11 2009</b>	0	NGNP Project Staff	 A. Shenoy   V. Nicolayeff	 J. Saurwein	Initial issue WO No. A30302-0310

**GA PROPRIETARY INFORMATION**

THIS DOCUMENT IS THE PROPERTY OF GENERAL ATOMICS. ANY TRANSMITTAL OF THIS DOCUMENT OUTSIDE GA WILL BE IN CONFIDENCE. EXCEPT WITH THE WRITTEN CONSENT OF GA, (1) THIS DOCUMENT MAY NOT BE COPIED IN WHOLE OR IN PART AND WILL BE RETURNED UPON REQUEST OR WHEN NO LONGER NEEDED BY RECIPIENT AND (2) INFORMATION CONTAINED HEREIN MAY NOT BE COMMUNICATED TO OTHERS AND MAY BE USED BY RECIPIENT ONLY FOR THE PURPOSE FOR WHICH IT WAS TRANSMITTED.

X NO GA PROPRIETARY INFORMATION

PAGE ii OF \*

### LIST OF CONTRIBUTORS

<b>Name</b>	<b>Organization</b>
John Saurwein	General Atomics
Matt Richards	General Atomics
David Carosella	General Atomics
Amy Bozek	General Atomics
Jessie Crozier	General Atomics
Puja Gupta	General Atomics
Carol Moseley	General Atomics
John Bolin	General Atomics
Stephen Gibson	General Atomics
Russ Vollman	General Atomics
Hankwon Choi	Washington Division of URS Corp.
Bill McTigue	Washington Division of URS Corp.
David Carroccia	Washington Division of URS Corp
Greg Walz	Washington Division of URS Corp
Gary Stark	Washington Division of URS Corp
Cody Connell	Washington Division of URS Corp

### EXECUTIVE SUMMARY

A decision was made by the NGNP Project in October 2008 to reduce the nominal reactor outlet helium temperature for the NGNP from 950°C into the range of 750°C to 800°C. This decision to reduce the reactor outlet helium temperature has a significant impact on the technology development effort required to support the NGNP. Specifically, much of the technology development required for an NGNP operating with a reactor outlet helium temperature of 950°C will no longer be needed (for example, development and qualification of high-temperature metal alloys for the IHX and ceramic composites for several reactor internals components, design and verification of a reactor vessel cooling system, etc.).

This report presents the work that the General Atomics (GA) NGNP team has performed to revise the NGNP Technology Readiness Level (TRL) assessment presented in GA Report PC-000580 to reflect a reduction in the nominal reactor outlet helium temperature from 950°C to 750°C. The Technology Development Road Maps (TDRMs) in PC-000580 and the corresponding Test Plans were developed in 2008 for the NGNP configuration shown in Figure E-1. Based on the decision by the NGNP Project to lower the reactor outlet helium temperature into the range 750°C - 800°C, GA has selected the configuration shown in Figure E-2 as its reference NGNP configuration, which will be the point of departure for NGNP conceptual design.




Figure E-1. NGNP Configuration for Technology Development Roadmapping in 2008




Figure E-2. Current NGNP Configuration for Technology Development Roadmapping

It is currently anticipated that the NGNP will be used to co-generate electricity and process heat in the form of steam, and that the steam will be provided to the end-user's facility via a tertiary loop. Heat will be transferred from an appropriate location (or locations) in the power conversion loop to the tertiary loop via a steam-to-steam heat exchanger. A steam-to-steam heat exchanger may also be needed in the power conversion loop to reheat the steam exiting the high pressure turbine as a means of improving power conversion cycle efficiency and reducing steam wetness at the back end of the cycle.

The purpose of the technology development roadmapping effort is to systematically define the current technology readiness level (TRL) for the critical systems, structures, and components (SSCs) and to define the activities necessary to advance the TRLs to the level required for installation and operation of the critical SSCs in the NGNP. The scope of the work to revise the TRL assessment presented in PC-000580 included the following subtasks:

- Revise the list of critical SSCs to reflect the lower reactor outlet helium temperature and revised reference NGNP configuration

- Revise the technology development road map (TDRM) and the supporting TRL rating sheets for each critical SSC for which the technology development requirements have changed due to the reduction in the reactor outlet helium temperature
- Assign an initial TRL rating for any newly identified critical SSCs and prepare TDRMs and the supporting TRL rating sheets
- For any SSCs for which the technology development requirements have changed due to the reduction in the reactor outlet helium temperature, modify the previously prepared Test Plan for the critical SSC that identifies the activities necessary to advance the TRL from the initial (baseline) level to TRL 8 and that provides ROM cost estimates and a schedule for these activities
- Prepare an integrated technology development schedule that supports NGNP startup in 2021
- Prepare a final report that includes the TDRMs, the supporting TRL ratings sheets, and the integrated SSC test schedule

For the purposes of the technology road mapping task, critical SSCs are defined as SSCs that are not commercially available or that do not have proven industry experience. For the plant configuration shown in Figure E-2, GA has identified the following critical SSCs:

- Reactor control equipment
- Control rods
- Upper core restraint
- High temperature ducting (hot duct)
- Reactor core assembly
- Reactor graphite elements
- Reactor pressure vessel
- Helium circulators (PHTS and SCS)
- Shutdown cooling heat exchanger (SCHE)
- Reactor cavity cooling system (RCCS)
- Steam generator (SG)
- High temperature valves
- Fuel handling and storage system
- Primary circuit and balance of plant instrumentation
- RPS, IPS, and PCDIS
- Fuel

Table E-1 lists the initial TRL rating<sup>1</sup> that GA has assigned to each critical SSC and shows how the critical SSCs and TRL ratings have changed relative to those in PC-000580.

**Table E-1. Initial TRL Ratings for NGNP Critical SSC**

SSC #	Critical SSC	Initial TRL Rating	
		Figure E-1	Figure E-2
1	Reactor control equipment	4	4
2	Reactor internals		
	a1. Control rods – composite	2	2
	a2. Control rods – metallic	NA*	4
	b. Control rod and RSM guide tubes	2	4
	c. Metallic core support structure (insulation)	3	3
	d1. Upper core restraint - composite	2	2
	d2. Upper core restraint - metallic	NA	4
	e. Upper plenum shroud (thermal barrier)	2	4
3	Hot duct	2	2
4	Reactor core and graphite		
	a. Reactor core	5	5
	b. Graphite	6	6
5	Reactor pressure vessel	5	5
6	Helium circulator	6	6
7	Intermediate heat exchanger	2	NA
8	Shutdown cooling system heat exchanger	4	4
9	Reactor cavity cooling system	4	4
10	Steam Generator	3	4
11	Turbomachinery (for combined cycle PCS)	4	NA
12	High temp. isolation valves and pressure relief valves	3	4
13	S-I hydrogen production system	3	NA
14	Fuel handling and storage system	4	4
15	Primary circuit and BOP protection inst.	3	3
16	RPS, IPS, PCDIS	4	4
N/A	Fuel	4	4
*NA = Not applicable			

As indicated in Table E-1, three of the critical SSCs for the previous NGNP configuration shown in Figure E-1 are not critical SSCs for the new reference configuration shown in Figure E-2. These include the intermediate heat exchanger, the S-I hydrogen production system, and the turbomachine, none of which are needed for the new plant configuration. On the other hand, variations of two of the critical SSCs have been added. These include metallic control rods and

<sup>1</sup> See Table 2-1 for TRL definitions

metallic upper core restraint elements. These SSC variations were added because GA considers it likely that these components will have to be made initially from high-temperature metals while ceramic composite components are being developed and qualified as a future design improvement. This approach is considered necessary because it is considered unlikely that the ceramic composite components can be developed and qualified on a schedule that would make them available for an NGNP startup in 2021. However, It is anticipated that the parallel effort to develop ceramic composite control rods and upper core restraint elements will eventually lead to replacement of their metallic counterparts. Reflecting the need for less technology development for the metallic components, the initial TRL assigned to the metallic control rods and upper core restraint elements is 4 compared to 2 for the corresponding ceramic composite components.

With respect to changes in the initial TRL ratings, the initial TRL rating of the steam generator (3 to 4), the control rod and RSM guide tubes (2 to 4), and the upper plenum shroud (2 to 4) have been increased due to elimination of the need to develop and qualify high-temperature materials for these components. This is a direct benefit of the reduction in the reactor outlet helium temperature. Another component that is greatly impacted by the reduction in the reactor outlet helium temperature is the reactor pressure vessel because the lower reactor outlet temperature eliminates the need for a direct vessel cooling of the vessel. Although the initial TRL level assigned to the reactor pressure vessel was 5 for both the old and new reference NGNP configurations, the level of effort and cost associated with increasing the TRL from 5 to 8 is substantially reduced as a result of the reduction in the reactor outlet helium temperature.

As previously noted in PC-000580, because the NGNP design process is at a very early stage, adequate design details to precisely define design data needs (DDNs) and the testing required to satisfy the DDNs are not currently available. Consequently, the TDRMs, TRL rating sheets, and test plans reflect GA's engineering judgment at this time based on the results of the NGNP preconceptual and conceptual design studies performed by the GA NGNP team and the design data needs (DDNs) and engineering development plans developed for other GA MHR designs, including the MHTGR, the NP-MHTGR, the GT-MHR, and the PC-MHR, none of which have the same reactor operating conditions as proposed in the current reference NGNP configuration. Consequently, GA views the TDRMs, TRL rating sheets, and test plans as preliminary documents that will need to be continually updated as the design and technology development efforts progress. Further, it is assumed that DDNs specific to the NGNP design will be prepared during NGNP conceptual design and that the specific requirements for the tests needed to satisfy the DDNs will be defined in Test Specifications, which will also be prepared by GA during conceptual design. The details of the tests will be provided in test plans and test procedures to be prepared by the testing organizations.



## TABLE OF CONTENTS

<b>EXECUTIVE SUMMARY .....</b>	<b>iv</b>
<b>ACRONYMS .....</b>	<b>xi</b>
<b>1 INTRODUCTION.....</b>	<b>1</b>
1.1 Scope.....	1
1.2 Reference NGNP Configuration.....	3
1.3 Critical SSCs.....	5
<b>2 METHODOLOGY.....</b>	<b>8</b>
2.1 Establish Baseline TRLs .....	8
2.2 Preparation of TDRMs and TRL Rating Sheets .....	10
<b>3 BASELINE TRL RATINGS .....</b>	<b>13</b>
<b>4 TDRMs, TRL RATING SHEETS, AND TEST PLANS .....</b>	<b>15</b>
4.1 RC2-SSC-1 Reactor Control Equipment.....	17
4.2 RC2-SSC-2a Control Rods and RC2-SSC-2d Upper Core Restraint .....	35
4.3 RC2-SSC-3 Hot Duct TRL .....	73
4.4 RC2-SSC-4a Reactor Core Assembly and RC2-SSC-4b Reactor Graphite Elements.....	87
4.5 RC2-SSC-5 Reactor Pressure Vessel .....	98
4.6 RC2-SSC-6 Helium Circulator .....	106
4.7 RC2-SSC-8 Shutdown Cooling Heat Exchanger .....	113
4.8 RC2-SSC-9 Reactor Cavity Cooling System .....	121
4.9 RC2-SSC-10 Steam Generator.....	128
4.10 RC2-SSC-12 High Temperature Valves.....	135
4.11 RC2-SSC-14 Fuel Handling and Storage System.....	145
4.12 RC2-SSC-15 Primary Circuit and Balance of Plant Instrumentation .....	156
4.13 RC2-SSC-16 RPS, IPS, and PCDIS .....	172
<b>5 TECHNOLOGY DEVELOPMENT SCHEDULES.....</b>	<b>183</b>
<b>6 REFERENCES.....</b>	<b>196</b>

### LIST OF FIGURES

Figure 1-1. Approach for Integration of Design with Technology Development.....	3
Figure 1-2. NGNP Configuration for Technology Development Roadmapping in 2008.....	4
Figure 1-3. Current NGNP Configuration for Technology Development Roadmapping.....	4
Figure 2-1. Comparison between TRL number, integration, and testing .....	8
Figure 5-1. Overall Schedule for NGNP Technology Development .....	184
Figure 5-2. Schedule for Potential Testing in CTF .....	195

### LIST OF TABLES

Table E-1. Initial TRL Ratings for NGNP Critical SSC .....	vii
Table 2-1. Technology Readiness Level (TRL) Definitions.....	9
Table 2-2. Technology Options for NGNP .....	11
Table 3-1. Initial TRL Ratings for NGNP Critical SSC .....	13
Table 4-1. Test Plans for NGNP Critical SSC .....	16

**ACRONYMS**

AGR	Advanced Gas Reactor
ASME	American Society of Mechanical Engineers
ASTM	American Society of Testing and Materials
BEA	Battelle Energy Alliance
BOP	Balance of Plant
BWXT	Babcock & Wilcox Company
CCD	Conduction Cool Down (event)
CR	Control Rod
CTF	Component Test Facility
DDN	Design Data Need
DOE	U.S. Department of Energy
EHGA	Element Hoist and Grapple Assembly
EPRI	Electric Power Research Institute
F&ORs	Functional and Operational Requirements
FHEP	Fuel Handling Equipment Positioner
FHESS	Fuel Handling Equipment Support Structure
FHM	Fuel Handling Machine
FHSS	Fuel Handling and Storage System
FSIF	Fuel Sealing and Inspection Facility
FSV	Fort Saint Vrain
FTC	Fuel Transfer Cask
GA	General Atomics
GT-MHR	Gas Turbine Modular Helium Reactor
HTE	High Temperature Electrolysis
HTGR	High-Temperature, Gas-Cooled Reactor
HTTR	High Temperature Test Reactor
IHX	Intermediate Heat Exchanger
INL	Idaho National Laboratory
IFMU	In-core Flux Monitor
IPS	Investment Protection System
JAEA	Japan Atomic Energy Agency
KAERI	Korea Atomic Energy Research Institute
LWR	Light Water Reactor
MHR	Modular Helium Reactor
MHTGR	Modular HTGR
NCA	Neutron Control Assembly

NGNP	Next Generation Nuclear Plant
NP-MHTGR	New Production Modular HTGR
ORNL	Oak Ridge National Laboratory
PASSC	Plant, Areas, Systems, Subsystems, and Components
PCDIS	Plant Control, Data, and Instrumentation System
PCHE	Printed Circuit Heat Exchanger
PC-MHR	Plutonium Consumption – Modular Helium Reactor
PCS	Power Conversion System
PHTS	Primary Heat Transport System
PIE	Post-Irradiation Examination
PPM	Performance Prediction Methodology
PRD	Power Range Detector
RC2-SSC	Reference Configuration 2 - System, Structure, and Components
RCE	Reactor Control Equipment
RCCS	Reactor Cavity Cooling System
ROM	Rough Order of Magnitude
RPS	Reactor Protection System
RPV	Reactor Pressure Vessel
RSM	Reserve Shutdown Material
SCHE	Shutdown Cooling Heat Exchanger
SG	Steam Generator
SCS	Shutdown Cooling System
SHTS	Secondary Heat Transport System
SOW	Statement of Work
SRD	Source Range Detector
S-I	Sulfur-Iodine
SSC	System, Structure, and Components
TDRM	Technology Development Road Map
TRISO	TRI-material, ISOtropic (with the materials being low-density pyrocarbon, high-density pyrocarbon, and silicon carbide)
TRL	Technology Readiness Level
UCO	Uranium Oxycarbide (fuel)
UCR	Upper Core Restraint
VCS	Vessel Cooling System

## 1 INTRODUCTION

### 1.1 Scope

A decision was made by the NGNP Project in October 2008 to reduce the nominal reactor outlet helium temperature for the NGNP from 950°C into the range of 750°C to 800°C. This decision to reduce the reactor outlet helium temperature has a significant impact on the technology development effort required to support the NGNP. Specifically, much of the technology development required for an NGNP operating with a reactor outlet helium temperature of 950°C will no longer be needed (for example, development and qualification of high-temperature metal alloys for the IHX and ceramic composites for several reactor internals components, design and verification of a reactor vessel cooling system, etc.).

This report presents the work that the General Atomics (GA) NGNP team has performed to revise the NGNP Technology Readiness Level (TRL) assessment presented in GA Report PC-000580 [GA TDRM 2008] to reflect a reduction in the nominal reactor outlet helium temperature from 950°C to 750°C. The members of the GA NGNP team that participated in this task included GA and URS Washington Division (URS-WD). The work was performed under Amendment 1 to Release 4 of Subcontract 75309 with the Battelle Energy Alliance (BEA).

The purpose of the technology development roadmapping effort is to systematically define the current technology readiness level (TRL) for the critical NGNP systems, structures, and components (SSCs) and to define the activities necessary to advance the TRLs to the level required for installation and operation of the critical SSCs in the NGNP [TDRM 2009]. The scope of the work to revise the TRL assessment presented in [GA TDRM 2008] included the following subtasks:

- Revise the list of critical SSCs to reflect the lower reactor outlet helium temperature and revised reference NGNP configuration
- Revise the technology development road map (TDRM) and the supporting TRL rating sheets for each critical SSC for which the technology development requirements have changed due to the reduction in the reactor outlet helium temperature
- Assign an initial TRL rating for any newly identified critical SSCs and prepare TDRMs and the supporting TRL rating sheets
- For any SSCs for which the technology development requirements have changed due to the reduction in the reactor outlet helium temperature, modify the previously prepared Test Plan for the critical SSC that identifies the activities necessary to advance the TRL from the initial (baseline) level to TRL 8 and that provides ROM cost estimates and a schedule for these activities

- Prepare an integrated technology development schedule that supports NGNP startup in 2021
- Prepare a final report that includes the TDRMs, the supporting TRL ratings sheets, and the integrated SSC test schedule

Sections 1.2 and 1.3 present the reference NGNP configuration and the SSCs that were considered in this technology development road mapping task. Section 2 discusses the methodology used to develop the TDRMs. Section 3 provides the baseline TRL levels assigned to the SSC. Section 4 includes the TDRMs and supporting TRL rating sheets for each of the critical SSC. Section 4 also provides references to the test plans, which have been issued as separate documents (with the exception of two test plans prepared by GA team member URS – Washington division, which are included as appendices). Section 5 provides both an integrated schedule for all of the technology maturation testing identified in the TRL rating sheets, TDRMs, and the test plans. Section 5 also includes a schedule just for the testing that can potentially be performed in the HTGR Component Test Facility (CTF) that is currently planned to be built at the INL [INL 2008a] [INL 2007] to support the NGNP Project.

Because the NGNP design process is at a very early stage, adequate design details to precisely define design data needs (DDN) and the testing required to satisfy the DDNs are not currently available. Consequently, the TDRMs, TRL rating sheets, and test plans reflect GA's engineering judgment at this time based on the results of the NGNP preconceptual and conceptual design studies performed by the GA NGNP team and the design data needs and engineering development plans developed for other GA MHR designs including the MHTGR, the NP-MHTGR, the GT-MHR, and the PC-MHR, none of which have the same reactor operating conditions as the reference NGNP configuration. Consequently, GA views the TDRMs, TRL rating sheets, and test plans as preliminary documents that will need to be continually updated as the design and technology development efforts progress.

Further, it is assumed that DDNs specific to the NGNP design will be prepared during NGNP conceptual design and that the specific requirements for the tests needed to satisfy the DDNs will be defined in Test Specifications, which will also be prepared by GA during conceptual design. The details of the tests will be provided in test plans and test procedures to be prepared by the testing organizations. This approach is consistent with the approach shown in Figure 1-1, which GA has used historically to integrate design and technology development to maximize the benefit of the technology development programs in terms of supporting a plant design and minimizing the technical risk of the design. This model is based on successful Engineering Development and Demonstration (ED&D) programs conducted and managed by GA for DOE projects, including Accelerator Production of Tritium, the Salt Waste Processing Facility, the commercial GT-MHR, and the New Production Reactor.




Figure 1-1. Approach for Integration of Design with Technology Development

## 1.2 Reference NGNP Configuration

The Technology Development Road Maps (TDRMs) in [GA TDRM 2008] and the corresponding Test Plans were developed in 2008 for the NGNP configuration shown in Figure 1-2. Based on the decision by the NGNP Project to lower the reactor outlet helium temperature into the range 750°C - 800°C, GA has selected the configuration shown in Figure 1-3 as its reference NGNP configuration, which will be the point of departure for NGNP conceptual design.




Figure 1-2. NGNP Configuration for Technology Development Roadmapping in 2008




Figure 1-3. Current NGNP Configuration for Technology Development Roadmapping



This NGNP technology development road mapping effort covered in this report is based on the NGNP configuration shown in Figure 1-3. GA has selected this configuration as best meeting the process heat needs of potential end users of the HTGR technology based on the market survey performed by MPR Associates [MPR 2008]. As reflected by Figure 1-3, it is currently anticipated that the NGNP will be used to co-generate electricity and process heat in the form of steam, and that the steam will be provided to the end-user's facility via a tertiary loop. Heat will be transferred from an appropriate location (or locations) in the power conversion loop to the tertiary loop via a steam-to-steam heat exchanger. A steam-to-steam heat exchanger may also be needed in the power conversion loop to reheat the steam exiting the high pressure turbine as a means of improving power conversion cycle efficiency and reducing steam wetness at the back end of the cycle. This plant configuration is consistent with the high-level requirements specified in the latest revision of the NGNP Systems Requirements Manual [SRM 2009].

In the absence of a conceptual design, the following assumptions were made with respect to the NGNP design to provide a basis for this technology development road mapping effort. These assumptions are based on the various NGNP conceptual design studies that have been performed to date by the GA team.

- The working fluid for the primary heat transport loops will be helium, and for the secondary heat transport loop it will be steam.
- All vessels will be made out of LWR steel (i.e., SA-508/533). A vessel cooling system will not be necessary to control the reactor pressure vessel maximum temperatures below ASME code limits for SA-508/533

The SSCs and the current technology readiness levels for the SSCs are based on the NGNP configuration shown in Figure 1-3 and on the above assumptions, and the TDRMs reflect this NGNP configuration and these assumptions.

### **1.3 Critical SSCs**

For the purposes of the technology road mapping task, critical SSCs have been defined by BEA as components that are not commercially available or that do not have proven industry experience. Based primarily on the DDNs listed in Table 5 of the NGNP Technology Development Plan prepared by GA during the NGNP preconceptual design phase [GA TDP 2007], GA identified the following critical SSCs to be considered in the initial technology development roadmapping task reported in [GA TDRM 2008].

- Reactor control equipment
- Reactor internals (control rods)
- High temperature ducting (hot duct)
- Reactor core assembly
- Reactor graphite elements
- Reactor pressure vessel/reactor vessel cooling system
- Helium circulators (PHTS, SCS, SHTS)
- Intermediate heat exchanger (IHX)
- Shutdown cooling heat exchanger (SCHE)
- Reactor cavity cooling system (RCCS)
- Steam generator (SG)
- Turbomachinery (for direct combined-cycle PCS)
- High temperature valves
- S-I hydrogen production system
- Fuel handling and storage system
- Primary circuit and balance of plant instrumentation
- RPS, IPS, and PCDIS

Three of the above SSCs are not included in the new NGNP configuration shown in Figure 1-3. These include the IHX, the turbomachinery (for a combined-cycle PCS), and the S-I hydrogen production system. No new SSCs have been identified, but a technology development road map and the supporting TRL rating sheets have been prepared for the upper core restraint as part of the current work<sup>2</sup>. The new list of critical SSCs that have been addressed in this report is as follows.

- Reactor control equipment
- Reactor internals (control rods, upper core restraint)
- High temperature ducting (hot duct)
- Reactor core assembly
- Reactor graphite elements
- Reactor pressure vessel/reactor vessel cooling system
- Helium circulators (PHTS, SCS, SHTS)
- Shutdown cooling heat exchanger (SCHE)
- Reactor cavity cooling system (RCCS)
- Steam generator (SG)

---

<sup>2</sup> The UCR was also a critical SSC for the previous NGNP configuration, but preparation of a technology development roadmap for this component was not within the scope of the 2008 technology development road mapping task.

- High temperature valves
- Fuel handling and storage system
- Primary circuit and balance of plant instrumentation
- RPS, IPS, and PCDIS

Fuel, which is clearly a critical SSC for GA's NGNP design, was not addressed in the 2008 technology readiness assessment nor in the current assessment. This is because the NGNP/AGR Fuel Development and Qualification Program already has a detailed technical program plan [INL 2008d] (that GA helped prepare as a participant in this Program) that defines the necessary technology development for fuel and fission products.

## 2 METHODOLOGY

### 2.1 Establish Baseline TRLs

The TRLs are an input to inform NGNP project decision makers of the readiness of a particular technology or component. TRLs are associated with the entire NGNP or the applicable plant area, system, subsystem (structure), and components (PASSC). For TRLs 1 through 5, assessment typically occurs on a technology or component basis with a roll-up TRL for the areas, systems, and subsystems. TRLs 6 through 8 generally involve integrated subsystem or system testing, which allows TRL assessments directly against subsystems and systems.

Table 2-1 provides the TRL definitions that GA used as the basis for assigning a baseline TRL to each critical SSC. These TRL definitions are basically the same as in [INL 2008c], but GA has made some minor modifications for clarification purposes. These changes were reviewed and accepted by BEA.

As an aid to understanding the context under which TRLs are applied, Figure 2-1 depicts the interrelationship among the TRLs, their abbreviated definitions, and the increasing amount of integration as the TRL levels advance.




Figure 2-1. Comparison between TRL number, integration, and testing

**Table 2-1. Technology Readiness Level (TRL) Definitions**

TRL	Technology Readiness Level Definition	Abbreviated Definition
1	<b>Basic principles observed</b> and reported in white papers, industry literature, lab reports, etc. Scientific research without well-defined application.	Basic principles observed
2	<b>Technology concept and application formulated.</b> Issues related to performance identified. Issues related to technology concept have been identified. Issues related to materials of construction have been identified. Paper studies indicate potentially viable system operation	Application Formulated
3	<b>Proof-of concept:</b> Related industrial experience and/or technology, component, and/or material testing at laboratory scale provide proof of potential viability in anticipated service. Although analysis of performance of SSC gives favorable results, testing is required to provide the data needed to support design of key features. Materials property data may be incomplete, but sufficient traceable material properties data are available for material selection.	Proof of Concept
4	<b>Technology or Component bench-scale testing has been performed to</b> demonstrate technical feasibility and functionality. Alternately, equivalent relevant operating or test data from similar applications of the technology or component are available to demonstrate technical feasibility and functionality. For analytical modeling, use generally recognized benchmarked computational methods and traceable material properties.	Component Verified at Bench Scale
5	<b>Component demonstrated at less-than-full scale (experimental scale) in relevant environment.</b> Experimental scale testing provides the necessary design data or component demonstration, but the test article may not be a model of the final component design. Experimental-scale demonstration may also be satisfied by equivalent operating or test data from similar applications of the component. At this TRL, sufficient data is available to completely define the component and identify any technology issues that must be resolved before the component can be integrated into a system or subsystem for pilot scale testing. Demonstration methods include analyses, verification, tests, and inspection.	Component Verified at Experimental Scale
6	<b>Components have been integrated into a subsystem</b> and demonstrated at a pilot scale in a relevant environment. The test article used in pilot-scale testing will likely not be identical to the final version, but should be sufficiently representative to serve as a basis for performance demonstration. Pilot-scale demonstration may also be satisfied by equivalent operating or test data from similar applications, but a high degree of component/subsystem similarity is necessary to achieve this TRL based on such data.	Subsystem Verified at Pilot Scale
7	<b>Subsystem integrated into a system</b> for integrated engineering scale demonstration in a relevant environment.	System Verified at Engineering Scale
8	<b>Integrated prototype of the system is demonstrated</b> in its operational environment with the appropriate number and duration of tests and at the required levels of test rigor and quality assurance. Analyses, if used support extension of demonstration to all design conditions. Analysis methods verified and validated. Technology issues resolved pending qualification (for nuclear application, if required). Demonstrated readiness for hot startup.	System Tested and Qualified
9	<b>The project is in final configuration</b> tested and demonstrated in operational environment.	Plant Operational
10	<b>Commercial-scale demonstration</b> is achieved. Technological risks minimized by multiple units built and running through several years of service cycles – Multiple Units	Commercial Scale – Multiple Units

## **2.2 Preparation of TDRMs and TRL Rating Sheets**

### **2.2.1 Technology Development Road Maps (TDRMs)**

Based on the BEA statement of work (SOW) and discussions held with BEA, the information needed for each TDRM (much of which is to be provided in the TRL rating sheets) is as follows:

- Description of the SSC under consideration
- Current TRL for the SSC
- Identification of technology options, if any, for the SSC
- The decision discriminators to be used in technology down selection, if applicable
- The tasks (e.g., studies, tests, modeling, and analyses) required to obtain the discriminating information for technology down selection, if applicable
- The tasks necessary to achieve the next TRL level
- The tasks necessary to achieve all TRL levels up to TRL 8
- The validation requirements for each TRL level – parameters and, to the extent possible, acceptance values

Most technology option selections have already been made for the steam-cycle MHR and the GT-MHR based on past trade studies. Key design and technology selection issues for the NGNP include, but are not limited to those summarized in Table 2-2. In most cases, GA has already made a preliminary selection with respect to these issues based on the results of preconceptual and conceptual design studies for the NGNP and trade studies performed for previous MHR reactor designs. The TDRMs and test plans prepared under this NGNP technology road mapping task reflect these selections. These selections will need to be confirmed during NGNP conceptual design.

**Table 2-2. Technology Options for NGNP**

<b>Critical System, Structure, or Component</b>	<b>Technology Options</b>
Reactor pressure vessel	- Material of construction
Helium circulators	- Bearing type - Impeller type - Motor type - Motor cavity seal type
High temperature valves	- Type of valve - Material of construction
Graphite	- Graphite grade(s) for fuel elements - Graphite grade(s) for reflector and core support elements
Reactor cavity cooling system	- Air or water cooled system
Reactor internals	- Material of construction (composites or metals)
High temperature ducting and insulation	- Material of construction for ducts - Type of insulation - Material of construction for cover plates

### 2.2.2 TRL Rating Sheets

TRL rating sheets were developed for each TRL from the baseline TRL to TRL 8 for each critical SSC using the TRL rating sheet form provided by BEA (and slightly modified by GA). GA prepared TRL rating sheets for the yet-to-be-achieved TRLs as requested by BEA although it is clearly difficult to define a basis for the yet-to-be-achieved TRLs and the actions needed to reach the next level before reaching the previous rating level. The primary purpose of the TRL rating sheets for the higher-than-baseline TRL levels is therefore to provide an outline of the actions needed to advance to the next level. To reach a given TRL, all of the actions identified (to reach the next TRL level) in the TRL rating sheet for the previous TRL level must be successfully completed. Clearly, it will be necessary to update these TRL rating sheets as the technology development effort progresses and new information becomes available.

### **2.2.3 Test Plans**

Test Plans were prepared for each of the SSCs identified in Section 1.3 as part of the original NGNP road mapping task. These Test Plans are SSC specific and define and describe the activities required to advance the TRL from the baseline TRL to TRL 8. For the most part, the activities described are tests, but design and computer modeling activities are also identified and described in several of the Test Plans. As requested by BEA, the descriptions of the tests are generally organized under the following headings:

- Test objective
- Test description
- Test conditions
- Test configuration
- Required data
- Test location
- Data requirements
- Test evaluation criteria
- Test deliverables
- Cost, schedule, and risk

Also, as required by BEA, the Test Plans are organized by TRL level, with a section for each TRL step (i.e., 3 to 4, 4 to 5, etc.).

Several of the Test Plans identified in Table 4-1 of [GA TDRM 2008] remain applicable in their entirety to the new NGNP configuration, but some Test Plans required modification to delete technology development related to the higher reactor outlet helium temperature of the previous reference configuration. These Test Plans were modified as part of the current task.



### 3 BASELINE TRL RATINGS

Table 3-1 lists the initial TRL rating that GA has assigned to each critical SSC and shows how the critical SSCs and TRL ratings have changed relative to those in [GA TDRM 2008].

**Table 3-1. Initial TRL Ratings for NGNP Critical SSC**

SSC #	Critical SSC	Initial TRL Rating	
		Figure 1-2	Figure 1-3
1	Reactor control equipment	4	4
2	Reactor internals		
	a1. Control rods – composite	2	2
	a2. Control rods – metallic	NA	4
	b. Control rod and RSM guide tubes	2	4
	c. Metallic core support structure (insulation)	3	3
	d1. Upper core restraint - composite	2	2
	d2. Upper core restraint - metallic	NA	4
	e. Upper plenum shroud (thermal barrier)	2	4
3	Hot duct	2	2
4	Reactor core and graphite		
	a. Reactor core	5	5
	b. Graphite	6	6
5	Reactor pressure vessel	5	5
6	Helium circulator	6	6
7	Intermediate heat exchanger	2	NA
8	Shutdown cooling system heat exchanger	4	4
9	Reactor cavity cooling system	4	4
10	Steam Generator	3	4
11	Turbomachinery (for combined cycle PCS)	4	NA
12	High temp. isolation valves and pressure relief valves	3	4
13	S-I hydrogen production system	3	NA
14	Fuel handling and storage system	4	4
15	Primary circuit and BOP protection inst.	3	3
16	RPS, IPS, PCDIS	4	4
N/A	Fuel	4	4

As indicated in Table 3-1, three of the critical SSCs for the previous NGNP configuration shown in Figure 1-2 are not critical SSCs for the new reference configuration shown in Figure 1-3. These include the intermediate heat exchanger, the S-I hydrogen production system, and the turbomachine, none of which are needed for the new plant configuration. On the other hand, variations of two of the critical SSCs have been added. These include metallic control rods and

metallic upper core restraint elements. These SSC variations were added because GA considers it likely that these components will have to be made initially from high-temperature metals while ceramic composite components are being developed and qualified as a future design improvement [GA 2009]. This approach is considered necessary because it is considered unlikely that the ceramic composite components can be developed and qualified on a schedule that would make them available for an NGNP startup in 2021. However, it is anticipated that the parallel effort to develop ceramic composite control rods and upper core restraint elements will eventually lead to replacement of their metallic counterparts. Reflecting the need for less technology development for the metallic components, the initial TRL assigned to the metallic control rods and upper core restraint elements is 4 compared to 2 for the corresponding ceramic composite components.

With respect to changes in the initial TRL ratings, the initial TRL rating of the steam generator (3 to 4), the control rod and RSM guide tubes (2 to 4), and the upper plenum shroud (2 to 4) have been increased due to elimination of the need to develop and qualify high-temperature materials for these components. This is a direct benefit of the reduction in the reactor outlet helium temperature. Another component that is greatly impacted by the reduction in the reactor outlet helium temperature is the reactor pressure vessel because the lower reactor outlet temperature eliminates the need for a direct vessel cooling of the vessel. Although the initial TRL level assigned to the reactor pressure vessel was 5 for both the old and new reference NGNP configurations, the level of effort and cost associated with increasing the TRL from 5 to 8 is substantially reduced as a result of the reduction in the reactor outlet helium temperature.

As previously noted in Section 1.3, fuel, which is clearly a critical SSC for GA's NGNP design, was not addressed in this study because the NGNP/AGR Fuel Development and Qualification Program already has a detailed technical program plan [INL 2008d] that defines the necessary technology development for fuel. However, it is GA's view that the current TRL for TRISO-coated UCO fuel is 4. This TRL rating is based on the excellent performance to date of experimental-scale fuel made at BWXT (UCO kernels) and ORNL (TRISO-coated particles and compacts) in irradiation test AGR-1, as indicated by the very-low fission-gas release from all six capsules in the test train. The AGR-1 test is scheduled to complete irradiation in the June – September 2009 time frame and post-irradiation examination (PIE) and safety-testing of the irradiated fuel will start shortly thereafter. A TRL rating of 5 will be achieved for the fuel when PIE results confirm satisfactory performance of the fuel during irradiation (i.e., with respect to retention of metallic fission products) and the results of safety-testing demonstrate acceptable fuel performance during simulated accident conditions (i.e., conduction cool down events).

#### **4 TDRMS, TRL RATING SHEETS, AND TEST PLANS**

The TDRMs and TRL rating sheets developed for each critical SSC for the previous NGNP reference configuration were prepared using the methodology discussed in Section 2. For the SSC that remain critical SSC for the new NGNP reference configuration shown in Figure 1-3, the TDRMs and TRL rating sheets have been modified, as necessary, using the same methodology to reflect the new NGNP configuration. The critical SSC for the new reference configuration are identified as RC2-SSC-X (where RC2 stands for reference configuration 2 and X is the SSC number) to distinguish the TRL rating sheets and TDRMs for the new reference configuration from the TRL ratings sheets and TDRMs for the previous reference configuration. The SSC numbering for the previous configuration has been retained to avoid confusion.

A complete set of TRL rating sheets and TDRMs for the critical SSC in the new reference NGNP configuration are presented below. The TRL rating sheets provide a brief description of the SSC and the basis for the TRL rating assigned to the SSC. They also outline the actions required to advance the TRL to the next level. More detailed descriptions of the SSCs can be found in [PCDSR 2007] and in the Test Plans.

The Test Plans for the critical SSCs have been issued as separate documents. Several of the Test Plans prepared for the SSC in the old reference configuration in 2008 remain applicable in their entirety to the new NGNP configuration, but some Test Plans required modification to delete technology development related to the higher reactor outlet helium temperature of the previous reference configuration. These Test Plans were modified as part of the current task.

Table 4-1 identifies the Test Plans applicable to the new reference NGNP configuration shown in Figure 1-3. As indicated in Table 4-1, new Test Plans were prepared for the upper core restraint, the reactor pressure vessel, the steam generator, the hot duct, and the high-temperature valves.

**Table 4-1. Test Plans for NGNP Critical SSC**

RC2-SSC #	SSC Description	Originating Org.	Report #
1	Reactor control equipment	GA	911133
2a	Control rods (composites)	GA	911134
2d	Upper Core Restraint (composites)	GA	911172*
3	Hot duct	URS-WD	911177*
4a	Reactor core assembly	GA	911135
4b	Graphite elements	GA	911136
5	Reactor pressure vessel	GA	911173*
6	Helium circulator	GA	911138
8	Shutdown cooling heat exchanger	GA	911140
9	Reactor cavity cooling system	GA	911141
10	Steam generator	GA	911174*
12	High-temperature valves	URS-WD	911178*
14	Fuel handling and storage system	GA	911145
15	Primary circuit and BOP instrumentation	GA	911146
16	RPS, IPS, and PCDIS	GA	911147
* New Test Plans prepared for NGNP configuration having a reactor outlet helium temperature of 750°C			

#### **4.1 RC2-SSC-1 Reactor Control Equipment**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-1.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Reactor Control Equipment</b>			
<b>Description:</b> This SSC contains equipment associated with control and measurement of reactor processes. This includes the Neutron Control Assembly (NCA), which contains control rod drive equipment and instrumentation. Reserve Shutdown Control Equipment (RSCE) is contained in the NCAs that operate the outer control rods. It also includes other nuclear instrumentation – the in-core Flux Mapping Units (IFMU), the Source Range Neutron Detectors (SRD), and the Power Range neutron detectors. The Power Range neutron detectors are located in six wells, equally spaced around the Reactor Vessel, in the Reactor Building concrete structure behind the RCCS. (Cont.)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Components verified at bench scale	Components verified at experimental scale
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The initial level 4 technical rating relies on experience gained at Fort St. Vrain and considerable conceptual design effort in both the commercial MHR program and the NPR program. Later, the GT-MHR program at General Atomics continued this work, all of which is applicable to the NGNP design and justifies a level 4 rating and continuation of the NGNP Conceptual Design (CD) at this technical rating. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>
1. Complete preliminary NHSS conceptual design of SRD, Power Range ex-vessel neutron detector, IFMU, NCA, and NCA with Reserve Shutdown equipment. Provide assembly views of each system. Document design issues. (Cont.)		GA	CD 0-36mo
<b>DDN(s) Supported:</b> C.11.10.01, C.11.01.03, C.11.01.04, C.11.01.05, C.11.01.06, C.11.02.01		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/24/08	<b>Originating Organization:</b> General Atomics		

### Additional Description Sheet(s)

Description:

Component level development testing parallels Reactor Internals testing to develop control rod materials, guide tubes, and other Reactor Internals components. Likewise, the nuclear instrumentation design requires considerable interaction with Reactor System, Reactor Internals, and Vessel System development efforts. The testing at the component level requires interaction with all these development efforts. Further testing of the installed NCA, SRD, and IFMU systems will be needed to confirm hot startup readiness. These tests involve operation of the equipment from the control room, utilizing the Plant Control, Data and Instrumentation System (PCDIS). Reactor Control and Protection development testing therefore includes testing of NCA, SRD, and IFMU operational functions for hot startup readiness, as well as testing at the component design level.

### Additional Basis Sheet(s)

Basis:

Design issues remain from these efforts, but these require conceptual design analysis in order to make equipment selections and proceed with the technical development. For instance, the location of the SRDs in the lower reactor requires conduction cooldown temperature analysis, as well as calculation of the neutron flux levels at the SRDs following a reactor trip. These in turn are affected by vessel design considerations. In earlier designs, it was concluded that reflector material temperatures adjacent to the SRDs were too high for fission chamber detectors available at the time. There were solutions, such as the use of pyrolytic liners to protect the SRDs. This might require bench scale material testing if the design issue remains in the NNGP design. However, both the NNGP conceptual design temperature analysis and available fission chamber detector design improvements must be considered first. A level 5 TRL rating requires completion of conceptual design calculations, completion of component selections and mechanism designs, and review of the effects of all bench scale component data (obtained from manufacturers) on critical design issues. Inability to operate the SRDs at the required temperatures would be one of these issues.

Component data for the SRDs includes; neutron detection range, maximum operating temperature and pressure, duty-cycle and lifetime, etc. SRD neutron detectors are withdrawn through the lower vessel to prevent premature burnup, and remain withdrawn during all but startup, normal shutdown or reactor trip, and refueling operations. They must also remain inserted and operating in the event of a conduction cooldown event. They require drive mechanisms and controls, as well as supporting structures, pressure seals, insulation, etc. Range, maximum operating temperature and pressure, duty-cycle and lifetime data is also required for the Power Range neutron detectors. However, the Power Range detectors have different temperature requirements and remain in place for all operations except maintenance. The Reactor Building design must assure that the neutron detectors and instrumentation cabling are not exposed to undesirable temperature transients during a conduction cooldown event. The IFMUs are also movable neutron detection devices. They include neutron detector assemblies, drive mechanisms and controls, thermocouples, cabling, etc. They are lowered into the reactor by a weight and retracted by the drive mechanism, and include a support structure for the movable detector and guide tube equipment, gamma shielding to protect personnel during retrieval of the IFMU, pressure seals, insulation, and flow restrictions to suppress flow of hot core inlet gas into the vessel penetration and to minimize air in-leakage during handling operations. The Neutron Control Assembly (NCA) contains and operates the control rods. The NCAs also have drive mechanisms and controls, thermocouples, cabling, etc., but in addition will be instrumented to obtain the control rod position, rod full-in or full-out indication, control rod motor start stop indication, and control rod support cable tension for each control rod. The NCAs will also be instrumented to obtain temperatures in the lower portion of the NCA control rod drive mechanism area. These temperatures will be processed by the PCDIS to provide excess temperature operator alarms, indicating control rod location, and to provide graphic displays for the operator to observe during events such as conduction cooldown. Additionally, the RSCEs (which are included in the outer NCAs, but not the startup NCAs) are instrumented to provide measurement of fuse link continuity and hopper gate open close status for display on the Reactor Protection System (RPS) operator console.

Testing will be completed to verify manufacturers data for some of the components selected in the CD, and to confirm level 5 technical readiness.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
<p>2. Coordinate with interfacing design areas – SRD with Reactor System, Reactor Internals, and Vessel System; Power Range detectors with Reactor System and Reactor Building; IFMU and NCA with Reactor System, Reactor Internals, and Vessel System – to provide supporting design analysis of component operating conditions, to complete interrelated design efforts (e.g. NCA control rod, guide-tubes etc. development under Reactor Internals), and to assure compatibility of interrelated components, such as consideration that fluid flow through the guide tubes and around the control rods for cooling is also adequate to protect the control rod drive mechanism at a different location in the NCA. Resolve design issues which do not require component testing.</p>	GA	CD 0-36mo	500
<p>3. List all design issues which do require component testing and determine tests required. (NOTE: For design issues from pre-existing conceptual design work see DDN(s) Supported, on page 1.) For the components being used, or considered for use, in the SRD, IFMU, Power Range neutron detector, and NCA/RSCE designs, identify all data which is marginal or questionable, and requires verification testing at the Experimental Scale (ES). From the list of considerations below, applying experience gained during CD to modify the list, develop a verification process and prepare test facilities to resolve design issues at the component test level, and to verify or extend component data which was supplied by manufacturers.</p> <p><u>Neutron Detector Assemblies:</u> Fission chamber devices used in the SRD, IFMU, and Power Range neutron detectors require design specific range, response time, maximum operating temperature and pressure margins, duty-cycle and lifetime capabilities, etc. In addition, SRD and IFMU designs require movement to operate and movement during operation. Manufacturers may not supply this information, and ES testing will be needed to provide the data. All the detectors require handling operations for maintenance and inspection, as well. Instrument cabling and electronics, associated with each of the detectors, must also meet the handling and operating requirements of the detector itself. For example, IFMU instrumentation cabling (for neutron detectors and thermocouples located in the movable detector assemblies) must be extended and retracted while the detector assembly travels through the reactor.</p> <p><u>Drive Mechanisms and Controls:</u> The SRD, IFMU, and NCA motor driven operating mechanisms require design specific torque, speed, minimal stop start travel increments, maximum operating temperature and pressure margins, duty-cycle and lifetime</p>	GA	CD 12-36mo	300
	Vendor(s)	CD 12-24mo	500
	Facility	CD 12-24mo	700



<p>capabilities, etc. In addition, all may require testing of particular motor loading extremes associated with guide-tube misalignment, caused by temperature effects or vessel and core misalignment, including misalignment of individual core components under various conditions of reactor operation. Attached motor power and controller cabling and electronics, switches, etc. must meet the requirements of the motor itself. In addition, the NCA requires instrumentation to indicate motor start stop status, cable tension for each control rod, rod full-in or full-out indication, operating temperature, etc. Instrumentation placed near the motors may require testing to evaluate the effects of electrical noise. Most of the equipment is safety-related, and consideration of this should be included in all test planning. This requires Safe Shutdown Earthquake (SSE) seismic testing prior to installation of the systems. CD recommendations to verify some component reliability issues might be included in ES component testing; otherwise, reliability testing will occur at the pilot scale.</p> <p><u>Support Structures, Movement Guidance Structures, Pressure Seals, Insulation, and Shielding:</u> Some SRD, IFMU, Power Range detector, or NCA components, which fall into the above categories, may require additional test data to achieve a level 5 technical rating. However, it is assumed that most CD component selections will specify documentation assuring qualification of materials and small components, such as pressure seals, to operate in the neutron flux environment at the required operating conditions. In the pre-existing design work, mentioned above, only the IFMU appears to require gamma shielding to protect personnel. The other systems may need this requirement as well. Also, support cables, rods, tubing, pressure seals, structures, etc. which experience changes in temperature, pressure, alignment, etc. associated with movement of devices, during performance of the specific SRD, IFMU, and NCA functions, must be tested at the most extreme conditions, with consideration of the required operating lifetime.</p> <p>4. Complete experimental-scale testing as determined above, make design adjustment and repeat testing, if required. Also, repeat testing of other components where inter-dependencies might occur. Document results to confirm level 5 technical rating. Provide recommendations for testing at next technical rating level.</p>	<p>GA Vendor(s) Facility</p>	<p>CD 24-36mo CD 12-36mo CD 12-36mo</p>	<p>500 1,000 1,500</p>
--	--------------------------------------	---	--------------------------------

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-1.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Reactor Control Equipment</b>				
<b>Description:</b> For this SSC it contains equipment associated with control and measurement of reactor processes. This includes the Neutron Control Assembly (NCA), which contains control rod drive equipment and instrumentation. Reserve Shutdown Control Equipment (RSCE) is contained in the NCAs that operate the outer control rods. This SSC also includes other nuclear instrumentation - in-core Flux Mapping Units (IFMU), the Source Range Neutron Detectors (SRD), and the Power Range neutron detectors. The Power Range neutron detectors are located in six wells, equally spaced around the Reactor Vessel, in the Reactor Building concrete structure behind the RCCS. (Cont.)				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale	
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
The level 5 technical rating is based on completion of previous TRL activities required to achieve a level 5 technical rating. This work included testing of components in the SRD, IFMU, Power Range neutron detectors, NCA, and RSCE systems. These components are contained in Reactor Control and Protection systems which are included in the reactor control equipment design. Prominent subsystems are neutron detector assembly subsystems; drive mechanism, controls, instrumentation, and support structure subsystems; and movement guidance subsystems. (Cont)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Complete NHSS preliminary Final Design (FD) of SRD, Power Range ex-vessel neutron detector, IFMU, NCA, and NCA with Reserve Shutdown equipment. Provide subsystem and final assembly views and supporting analysis to determine operating conditions for each subsystem. Document design issues. (Cont)		GA	FD 0-42mo	3,000
<b>DDN(s) Supported:</b> C.11.10.01, C.11.01.02, C.11.01.07, C.11.01.03, C.11.01.04, C.11.01.05, C.11.01.06, C.11.02.01			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> Dale Pfremer				
<b>Date:</b> 10/24/08		<b>Originating Organization:</b> General Atomics		

### **Additional Description**

Description:

Component level development testing parallels Reactor Internals testing to develop control rod materials, guide tubes, and other Reactor Internals components. Likewise, the nuclear instrumentation design requires considerable interaction with Reactor System, Reactor Internals, and Vessel System development efforts. The testing at the subsystem level requires interaction with all these development efforts. Further testing of the installed NCA, SRD, and IFMU systems will be needed to confirm hot startup readiness. These tests involve operation of the equipment from the control room, utilizing the Plant Control, Data and Instrumentation System (PCDIS). Reactor Control and Protection development testing therefore includes testing of NCA, SRD, and IFMU operational functions for hot startup readiness, as well as testing at the subsystem design level.

### Additional Basis Sheet(s)

Basis:

Component testing was done in conjunction with interfacing system groups, including Reactor System, Reactor Internals, Vessel System, and the Reactor Building System. Design issues which could not be resolved at the component testing level may require testing of pilot scale configurations to resolve issues of operability, reliability, and failure effects to achieve a level 6 technical rating.

Operability, reliability, and failure effects issues for the SRD, IFMU, and NCA-RSCE subsystems are resolved during preliminary Final Design (PFD), and if necessary include pilot scale testing. System by system test planning considerations are mentioned below;

The SRDs operate through the lower vessel and must be mounted in a fashion which allows removal and replacement of the entire assembly. SRD neutron detectors are withdrawn through the lower vessel to prevent premature burn-up of fissile material contained in the detector, and remain withdrawn during all but startup, normal shutdown or reactor trip, and refueling operations. They require drive mechanisms and controls to operate, and these rely on alignment considerations affecting both the vessel design and lower reflector. They are required to operate during conduction cooldown events. Normal life expectancy is approximately 5 years. Both operability and reliability should be verified at the subsystem level and effects of various drive mechanism failure on overall reactor operability should be considered as well.

The Power Range neutron detectors are permanently mounted, and may not require pilot scale subsystem testing.

The IFMUs are also movable neutron detection devices (but also contain temperature instrumentation, whereas the SRDs do not) and contain a drive mechanism subsystem which lowers the detector assemblies into the reactor. However, these operate through the top-head, as do the NCAs. The IFMUs operate only periodically, but the NCAs operate the control rods, and have a more severe duty-cycle. Both the IFMU and NCA systems have drive mechanisms. The NCA contains instrumentation in the drive mechanism enclosure. This includes temperature instrumentation and possibly contact switches or other devices to determine and verify full out or full in positioning of individual control rods. The IFMU has instrumentation cabling attached through the drive mechanism enclosure to the detector assembly, which travels axially through the guide system in the reactor. This, in turn, requires extension/retraction of instrumentation cabling. RSCEs are included in the outer NCAs, but not the startup NCAs, so these NCAs contain a different subsystem. The mounting structure for these subsystems interfaces with the vessel top-head. Associated instrumentation and power cabling, entering the enclosure into the drive motor area is also a consideration in the vessel top-head design. Both drive mechanisms require suppression of hot core inlet gas heating effects, and this is a concern to other parts of the system (such as the guide-tubes) as well. Subsystem operability must be verified. Sub-assembly drawings and accompanying analysis from the preliminary Final Design provide operating conditions and the arrangement of each subsystem. Component testing and analysis contribute, but subsystem testing may also be required to verify certain operability considerations such as the requirement that drive mechanisms must maintain movement of the control rods, or the IFMU detector assembly, by gravity force through guide-tubes under abnormal, as well as normal, conditions of reactor operation. (Loss of flow, over-temperature, conduction cooldown scenarios, etc.) Accelerated life testing may also be needed to verify reliability. Failure effects also may be needed for NCA and IFMU drive subsystems.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
<p>2. Coordinate with interfacing design areas – SRD with Reactor System, Reactor Internals, and Vessel System; Power Range detectors with Reactor System and Reactor Building; IFMU and NCA with Reactor System, Reactor Internals, and Vessel System – to provide supporting data and stress analysis to verify drive mechanism and detector assembly operating integrity. Complete interrelated subsystem development efforts. Resolve design issues which do not require specific subsystem testing, using analysis or test data from qualified similar applications. (For example, some aspects of NCA movement guidance structure analysis/testing might be applicable to IFMUs as well.)</p>	GA	FD 0-12mo	500
<p>3. List all design issues which do require subsystem testing and determine tests required. Coordinate with Reactor Internals, Vessel System, and Reactor System interrelated design areas. (NCA development, under Reactor Internals, includes control rod guide-tubes and the control rods.) Identify the SRD, IFMU, and NCA/RSCE subsystems which require reliability verification testing at the Pilot Scale. Prepare test facilities for drive mechanisms, detector subsystems, etc. using representative versions of final design. The following consideration should be included in preparing facilities for testing operability, reliability, and failure modes.</p> <p><u>Detector Assembly Subsystems:</u> SRD, IFMU, and Power Range neutron detectors which require design specific range, response time, maximum operating temperature and pressure margins, duty-cycle and lifetime capabilities, etc. will have been tested, or verified, at the component level and should not require subsystem testing to verify these capabilities. However, SRD and IFMU detector subsystems require movement to operate and movement during operation. These features can be confirmed at the subsystem level to assure subsystem reliability, within design lifetime, operating conditions, etc. Failure modes affecting plant operation or which cause effects in interfacing design areas (Vessel, Reactor Internals, etc.) should also be considered.</p> <p><u>Drive Mechanisms Subsystems:</u> The SRD, IFMU, and NCA motor driven operating mechanisms, at the subsystem level, require a representative version of the final design including gearing, cables and pulleys, pushrods, motor and instrumentation support structures, etc sufficient to test torque, speed, minimal stop start travel increments, etc. under maximum operating temperature and pressure conditions, with cables, etc. attached. Duty-cycle and lifetime capabilities, etc. may incorporate additional testing of particular motor loading extremes associated with guide-tube misalignment, core</p>	GA	FD 12-30mo	300
	Vendor(s)	FD 24-30mo	500
	Facility	FD 12-30mo	700

<p>misalignment, etc. Testing should include attached motor power and controller cabling and electronics, switches, etc., as well as instrumentation included in the NCA to measure control rod and motor enclosure parameters. It is expected that testing to evaluate the effects of electrical noise on instrumentation can be done better at the subsystem level. Test documentation should support safety-related qualification of this equipment.</p> <p><u>Support Structures, Movement Guidance Structures, Pressure Seals, Insulation, and Shielding:</u></p> <p>Most, if not all, SRD, IFMU, or NCA components, which fall into the above category, may require no additional testing at the subsystem level, since it is assumed that most small components will achieve a level 6 rating by inclusion in subsystem testing. Movement guidance structures may be one exception. It may be necessary to separate testing of this portion of the NCA or IFMU from drive mechanism testing, for example. In this case, that portion of the subsystem must be tested at the most extreme conditions, with consideration of the required operating lifetime, etc. just as would be the case were it included as part of the drive mechanism subsystem testing. Also considered at the subsystem level, are various equipment handling systems. While other features of the handling systems probably don't require testing below level 7, it may be desirable to verify attachment/pick-up features of handling systems at the subsystem level.</p> <p>4. Complete Pilot Scale testing as determined above. Make design adjustment and repeat testing, if required. Document results to confirm level 6 technical rating. Provide recommendations for pre-installation integrated system level testing of SRD, Power Range ex-vessel neutron detector, IFMU, NCA, and NCA with Reserve Shutdown equipment.</p>	<p>GA Vendor(s) Fabricators Facility</p>	<p>FD 30-42mo FD 30-36mo FD 30-36mo FD 30-42mo</p>	<p>500 300 1,400 1,800</p>
--	--	--	--

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-1.3	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Reactor Control Equipment</b>			
<b>Description:</b> For this SSC it contains equipment associated with control and measurement of reactor processes. This includes the Neutron Control Assembly (NCA), which contains control rod drive equipment and instrumentation. Reserve Shutdown Control Equipment (RSCE) is contained in the NCAs that operate the outer control rods. It also includes other nuclear instrumentation - in-core Flux Mapping Units (IFMU), the Source Range Neutron Detectors (SRD), and the Power Range neutron detectors. The Power Range neutron detectors are located in six wells, equally spaced around the Reactor Vessel, in the Reactor Building concrete structure behind the RCCS. (Cont.)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The level 6 technical rating for this SSC is based on the completion of activities required to achieve a level 6 technical rating. This work included testing of subsystems in the SRD, IFMU, Power Range neutron detectors, NCA, and RSCE systems. These subsystems are contained in Reactor Control and Protection systems which are included in the reactor control equipment design. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>
<b>Cost (\$K)</b>			
1. Complete NHSS Final Design (FD) of SRD, Power Range ex-vessel neutron detector, IFMU, NCA, and NCA with Reserve Shutdown equipment. Fabricate equipment and provide as-built drawings showing final assembly views, sub-assembly views, control and instrumentation diagrams, etc. and supporting documentation to allow assembly, installation, test-point hookup procedures for test instruments, etc. Document pre-installation issues. (Cont.)		GA Fabricators	FD 43-84mo FD 48-54mo
		2,500	33,000
<b>DDN(s) Supported:</b> C.11.01.02, C.11.01.09, C.11.02.01		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/24/08	<b>Originating Organization:</b> General Atomics		

### **Additional Description**

Description:

Component level development testing parallels Reactor Internals testing to develop control rod materials, guide tubes, and other Reactor Internals components. Likewise, the nuclear instrumentation design requires considerable interaction with Reactor System, Reactor Internals, and Vessel System development efforts. The testing at the subsystem level requires interaction with all these development efforts. Further testing of the installed NCA, SRD, and IFMU systems will be needed to confirm hot startup readiness. These tests involve operation of the equipment from the control room, utilizing the Plant Control, Data and Instrumentation System (PCDIS). Reactor Control and Protection development testing therefore includes testing of NCA, SRD, and IFMU operational functions for hot startup readiness, as well as testing at the subsystem design level.



### Additional Basis Sheet(s)

**Basis:**

Prominent subsystems are neutron detector assembly subsystems, drive mechanism subsystems, and movement guidance subsystems. Subsystem testing was done in conjunction with interfacing system groups, including Reactor System, Reactor Internals, Vessel System, and the Reactor Building System. Issues such as reliability, failure effects, etc. have been resolved by pilot scale testing using representative configurations to test operability, perform accelerated life testing, and determine failure modes at a level 6 technical rating. The final design is completed under the level 6 technical rating, but demonstration of installation readiness requires further testing. For example, an integrated engineering scale demonstration of specific features such as SRD, IFMU or NCA extension and retraction operations requires facilities and procedures to perform the testing. The actions below address design efforts and testing to achieve a level 7 technical rating for this SSC. Related handling equipment will also be evaluated at level 7. Seismic testing for safety-related qualification of the equipment is also completed at level 7.

Specific test planning considerations are mentioned below:

Since the SRDs operate the SRD neutron detectors through the lower vessel, an integrated test configuration must be devised to assure alignment, retrieval, etc. The vessel and lower reflector are involved. It may be desirable to coordinate test activities with these design areas to verify the alignment aspects prior to installation. The IFMUs and NCAs also require alignment verification. This can probably be accomplished with checkout of the handling machines. The SRDs, IFMUs, and NCAs all interface with the vessel and therefore must maintain all requirements for vessel integrity, including leakage tightness. Testing to verify this may previously exist under the vessel design scope, but this should be verified and documented as part of the installation readiness process.

All systems, including the Power Range neutron detectors, have power and instrumentation wiring. Test procedures to verify power cable and instrumentation readiness are needed as well. These would include testing to verify subsystem power-up, at the integrated system level. (Including operation from the actual or representative control consoles.) In particular, the NCA equipment has rigorous safety-related design requirements. Verification of rod runout limitation features, power cable and channel separation features, drive mechanism failure-detection features, etc. must be provided. Tests requiring end-to-end power cable and control access to simulate NCA operational and failure protection features, which cannot or should not be tested prior to installation of NCA equipment, must be completed beforehand. Examples of this include testing the control rod trip operation (under simulated controller failures resulting in a rod runout, reactor exit over-temperature, etc.), and RSCE release of the boron balls. An above-reactor test rig (possibly on the refueling floor) may be required to accomplish this testing.

The IFMUs also contain movable equipment and may require testing similar to the NCAs. However, the IFMU may require only minimal verification of operation functions. It may be reasonable to verify IFMU operation more fully after installation, prior to hot startup. Verification of IFMU handling equipment functions will be required before installation.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Coordinate with interfacing design areas – SRD with Reactor System, Reactor Internals, and Vessel System; Power Range detectors with Reactor System and Reactor Building; IFMU and NCA with Reactor System, Reactor Internals, and Vessel System – to provide an all-design-area test requirement summary for pre-installation checkout of each system, with design area responsibility included.	GA	FD 43-84mo	1,000
3. Resolve issues which do not require testing, using all available information. Document resolution of issues for advancement to level 7.	GA	FD 43-54mo	500
4. List all issues which do require testing and determine tests required, with participation from Reactor Internals, Vessel System, Reactor Building, Reactor System and BOP engineering design areas.	GA	FD 54-60mo	200
5. Prepare test facilities for SRD, IFMU, and NCA equipment, and Power Range neutron detector equipment, if necessary. All associated handling equipment should be checked. The following primary areas of verification and testing are expected in preparing the systems for installation:	GA Facility	FD 54-60mo FD 54-72mo	300 1,000
<p><u>System Interconnection and Alignment:</u>                      Since the SRD neutron detectors operate through the lower vessel, a test configuration must be devised to verify proper alignment during installation. This may require observation of the SRD insertion/withdrawal process with the lower vessel and internals partially assembled. This might be accomplished during checkout of SRD removal and handling equipment, to verify that no binding or bending of the overall SRD assembly could impair the operating function. The IFMU and NCA assemblies have similar considerations, but pre-installation testing may not be required. However, checkout of the handling equipment is required, as well as checkout of maintenance equipment associated with the Power Range neutron detector assemblies. The SRD, IFMU and NCA systems each seal their respective vessel penetrations to prevent primary coolant leakage during operation. It is assumed that this requirement will be verified during Vessel System checkout. The Vessel System, Reactor Building, and AE (Architect Engineer) checkout of electric power wiring must verify cable harnesses, cable tray attachments, etc for each of these systems. This also includes verification of proper cable separation procedures for the reliability design of the equipment.</p>			
<p><u>Integrated System Operability:</u>                      The SRD, IFMU, and NCA operating mechanisms, powered instrumentation, etc. which were tested at the subsystem level, will require additional testing at the integrated system level to assure operability features which could not be demonstrated fully at the subsystem level. Integrated system level testing is better suited to fully check power and power</p>			

<p>transfer/control mechanisms, instrumentation and power cabling, etc. Also, systems can be connected to allow activation of system functions from the actual command consoles. It is assumed that simple point-of-fabrication procedures will have been completed to verify proper manufacturing of the SRD, IFMU, Power Range neutron detectors, and NCA systems. These will include equipment power-on tests, continuity checks, etc. However, minimal, special purpose testing equipment may be required for these tests as well. After delivery of prototype units, more testing is required. The SRDs require alignment and insertion/withdrawal tests (see above). The NCAs require verification of rod runout limitation features, speed and positioning accuracy, control rod trip features, and RSCE backup features (release of boron balls). An above-reactor test rig (possibly on the refueling floor) will be required to accomplish this testing. The normal features of control rod withdrawal and insertion should be demonstrated also. IFMU testing may be required as well, but some IFMU prototype testing could be accomplished with checkout of IFMU handling equipment (assuming IFMU placement in and removal from the reactor will be included), or this testing could be deferred to level 8. NCA testing is, however, limited after installation and prior to hot startup, so the above testing is required outside the reactor. Test documentation should be provided to support safety-related qualification of the equipment.</p> <p><u>Seismic Testing:</u> Seismic testing of the systems is required to achieve a level 7 technical rating. These tests will be accomplished in a nuclear qualified facility. Special test structures to attach equipment and produce as-installed seismic effects, or amplification of the seismic effects to represent the as-installed effects, will be required. Operability at Safe Shutdown Earthquake (SSE) seismic levels must be demonstrated for safety-related equipment. The SSE magnitude is twice the Operational Basis Earthquake (OBE) magnitude, but the OBE requirement applies to all equipment, and requires that all equipment needed to operate the reactor must continue to operate. Therefore, temporary relocation of supporting test equipment to seismic test facilities will be necessary. Test documentation from seismic testing must be provided to support SSE and OBE qualification of the equipment.</p> <p>6. Determine the Engineering Scale testing, prepare test facilities, and complete testing. If equipment adjustments are necessary, repeat testing after adjustments are completed. Provide equipment change information to manufacturing, modify as-built drawings, and assure that all levels of Quality Assurance are repeated in the process. Document results to confirm level 7 technical rating. Provide recommendations for after-installation-testing of SRD, Power Range ex-vessel neutron detector, IFMU, NCA, or NCA with Reserve Shutdown equipment, which should be completed prior to hot startup.</p>	<p>GA Facility Fabricators Seismic</p>	<p>FD 54-84mo FD 54-78mo FD 54-78mo FD 78-84mo</p>	<p>500 4,000 1,000 3,000</p>
--	--	--	--

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-1.4	<b>Revision:</b> 1		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Reactor Control Equipment</b>				
<b>Description:</b> For this SSC it contains equipment associated with control and measurement of reactor processes. This includes the Neutron Control Assembly (NCA), which contains control rod drive equipment and instrumentation. Reserve Shutdown Control Equipment (RSCE) is contained in the NCAs that operate the outer control rods. It also includes other nuclear instrumentation -- In-core Flux Mapping Units (IFMU), the Source Range Neutron Detectors (SRD), and the Power Range neutron detectors. The Power Range neutron detectors are located in six wells, equally spaced around the Reactor Vessel, in the Reactor Building concrete structure behind the RCCS. (Cont.)				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
The level 7 technical rating for this SSC is based on the completion of activities required to achieve a level 7 technical rating. This work included testing of SRD, IFMU, Power Range neutron detectors, NCA, and NCA/RSCE prototype systems. These systems are contained in Reactor Control and Protection systems equipment design. (Cont)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b> 1. Install NCA and NCA/RSCE equipment and perform hot-startup readiness tests at sub-power conditions. All testing, which is done after fuel installation, must be completed within minimum negative reactivity limitations at cold reactor conditions. (Cont.)		<b>Actionee</b> GA	<b>Schedule</b> FD 85-108mo	<b>Cost (\$K)</b> 1,500
<b>DDN(s) Supported:</b> none			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			Dale Pfremmer	
<b>Date:</b> 10/24/08	<b>Originating Organization:</b>		General Atomics	

**Additional Description**

Description:

Component level development testing parallels Reactor Internals testing to develop control rod materials, guide tubes, and other Reactor Internals components. Likewise, the nuclear instrumentation design requires considerable interaction with Reactor System, Reactor Internals, and Vessel System development efforts. The testing at the subsystem level requires interaction with all these development efforts. Further testing of the installed NCA, SRD, and IFMU systems will be needed to confirm hot startup readiness. These tests involve operation of the equipment from the control room, utilizing the Plant Control, Data and Instrumentation System (PCDIS). Reactor Control and Protection development testing therefore includes testing of NCA, SRD, and IFMU operational functions for hot startup readiness, as well as testing at the subsystem design level.

**Additional Basis Sheet(s)**

Basis:

Verification of NCA rod runout limitation features, control rod trip features, power cable and channel separation features. etc. were tested at the prototype level, and the required equipment adjustments were completed, documented, and incorporated into the equipment. Prominent subsystems -- neutron detector assembly subsystems, drive mechanism subsystems, and movement guidance subsystems -- were also checked. The SRD neutron detectors, which operate through the lower vessel, were checked for alignment, retrieval features, etc. The IFMUs also contain movable equipment, and were checked at the prototype level. The handling equipment for all systems was checked. Seismic testing for safety-related qualification of the equipment was also completed at level 7.


**Additional Action Sheet(s)**

<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Install Source Range Detector equipment and repeat pre-installation test procedure, including power-up and instrumentation checkouts, using PCDIS.	GA	FD 85-108mo	800
	Fabricators	FD 85-108mo	200
3. Install Power Range detectors and cabling. Complete power-up checkout using PCDIS.	GA	FD 85-108mo	800
	Fabricators	FD 85-108mo	200
4. Install IFMU equipment and repeat pre-installation checkout. Add operational testing deferred to level 8. Perform checkout testing with PCDIS.	GA	FD 85-108mo	800
	Fabricators	FD 85-108mo	200
5. Confirm all sub-power nuclear instrumentation testing completion for hot startup readiness. Confirm source-level range and accuracy of SRD equipment, as part of checkout. Document.	GA	FD 96-102mo	500

4/21/2009 10:37 AM

Revision 0

RC2-SSC01 Reactor Control Equipment Technology Roadmap



#### **4.2 RC2-SSC-2a Control Rods and RC2-SSC-2d Upper Core Restraint**

**Control Rods (Composite), TRL Rating Sheets, TRL 2 through 7**

**Control Rods (Metallic), TRL Rating Sheets, TRL 4 through 7**

**Upper Core Restraint (Composite), TRL Rating Sheets, TRL 2 through 7**

**Upper Core Restraint (Metallic), TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Maps**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.1-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>			
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Basic principles observed	Application formulated	Proof of concept
<b>TRL</b>	<b>1</b>	<b>2</b>	<b>3</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
The CR design will be essentially the same as in Ft St Vrain but the higher temperatures to which the CR will be subjected during conduction cooldown events in the NNGP require use of a ceramic composite as the material of construction for the structural components. Ceramic composite materials are widely used in aerospace but little data is available on irradiation effects and corrosion in an impure He environment, so a substantial materials development program is needed (see HTR2008 conference paper HTR2008-58050 and GA Report 911125/0). Composite architectures specific to the geometries of the various CR structural components must be developed.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>
1. Perform engineering analyses to establish control rod operating conditions (e.g., temperatures, flow conditions, helium impurities, etc.) and develop control rod requirements		General Atoms (GA)	6 months starting near beginning of CD
<b>DDN(s) Supported:</b> N.11.03.53, N.11.03.54, N.11.03.55, N.11.03.56, C.11.03.24		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> John Saurwein, Russ Vollman			
<b>Date:</b> 11-27-08	<b>Originating Organization:</b> General Atomics		



<b>Additional Actions Sheets(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Develop control rod conceptual design. Perform FEA and seismic analyses to calculate the expected mechanical and seismic loads. Initiate development of CR composite material performance models	GA	3 months starting after completion of action 1	200
3. Review ceramic composite materials knowledge base and composite materials supply network to select potential composite materials and parts manufacturers	GA/Rolls-Royce	6 months starting after completion of action 1	350
4. Develop composite architectures and manufacturing processes for the CR parts. Fabricate shapes having the selected composite architectures and cut out specimens for the tests in actions 5, 6, and 7	GA/Rolls-Royce and part manufacturers	1 year, complete by ~middle of PD	3000
5. Conduct baseline physical and mechanical properties tests on test specimens from action 4.	ORNL, INL, and/or commercial laboratories	1 year, complete by end of PD	1000
6. Conduct screening irradiation tests on test specimens from action 4 to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties (from action 5)	INL and/or ORNL	3 years, complete 2 years into NGNP FD	TBD (A very rough estimate is ~\$20M)
7. Conduct screening corrosion tests on test specimens from action 4 in a reactor helium environment at reactor operating temperatures (up to ~1400°C) to determine the effects on the baseline physical and mechanical properties (from action 5)	INL and/or ORNL	2 years starting in parallel with action 6	1000
8. Select composite materials and architectures	GA/Rolls-Royce and parts manufacturers	3 months starting as soon as data are available from actions 6 & 7	200

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2a.2-c	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>				
<b>Description:</b>				
Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods.) The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Application formulation	Proof of concept	Verified at bench scale	
<b>TRL</b>	<b>2</b>	<b>3</b>	<b>4</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 3 is achieved when the following conditions are met: (1) All of the engineering analyses and design activities and all of the testing activities required to advance the TRL from 2 to 3 have been completed; (2) Composite architectures have been selected based on the screening baseline physical and mechanical properties tests, irradiation tests, and corrosion tests on candidate composite architectures; and (3) The results of the tests on the selected composite architectures show that CRs fabricated from these materials have a high probability of satisfying CR design requirements.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Finalize the composite architectures for the CR structural parts. Fabricate prototype parts and cut samples from the parts for actions 2, 3, and 4 below.		GA/Rolls-Royce, and parts manufacturers	6 months starting as soon composite architectures are selected	2000
<b>DDN(s) Supported:</b> N.11.03.53, N.11.03.54, N.11.03.55, N.11.03.56, C.11.03.24			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			John Saurwein, Russ Vollman	
<b>Date:</b> 11-27-08	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s):</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct baseline physical and mechanical properties tests on test specimens from action 1. The number of tests performed shall be adequate to obtain the data required for the statistically significant engineering data base required for the composite material performance models	INL, ORNL, and/or commercial laboratories	1 year starting as soon as test specimens from action 1 are available	1000
3. Conduct irradiation tests on test specimens from action 1 to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties (from action 2). The testing shall be sufficient to establish a statistically significant engineering data base for the composite material performance models	INL and/or ORNL	2 years, must be completed by ~mid 2017 to support NNGP startup in 2021	TBD (a very rough estimate is ~\$20m)
4. Conduct corrosion tests on test specimens from action 1 in a reactor helium environment at reactor operating temperatures (up to ~1400°C) to determine the effects on the baseline physical and mechanical properties (from action 2)	INL and/or ORNL	2 years, must be completed by ~mid 2017 to support NNGP startup in 2021	2000
5. Complete composite material behavior and failure models based on the data from actions 2, 3, and 4	GA	6 months starting as soon as data from actions 2, 3, and 4 are available	400

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2a.3-c	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>				
<b>Description:</b>				
Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at engineering scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 4 is achieved when the following conditions are met: (1) The composite architectures for the CR structural parts have been finalized and prototype parts have been fabricated and cut up for testing; (2) Adequate physical and materials properties testing of unirradiated, irradiated, and corrosion specimens from the prototype parts have been performed to establish a statistically significant material properties engineering data base; and (3) Composite material behavior and failure models have been completed based on the composite properties engineering data base.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Conduct engineering analysis to verify that components meet design and safety requirements, including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability.		General Atomics	12 months starting about half-way through FD	1000
<b>DDN(s) Supported:</b> None			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			John Saurwein, Russ Vollman	
<b>Date:</b> 11-27-08		<b>Originating Organization:</b> General Atomics		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2a.4-c	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>				
<b>Description:</b>				
Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale	
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 5 is achieved once engineering analyses have been completed and show that the control rod design meets design and safety requirements including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability requirements.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (<i>list all</i>)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Conduct engineering analysis to show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods will be adequate for cooling.		GA	6 months. Must be complete about 1.5 years before end of final design	200
<b>DDN(s) Supported:</b> None			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman		
<b>Date:</b> 11-27-08	<b>Originating Organization:</b> General Atomics			

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.5-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>			
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
TRL 6 is achieved upon completion of engineering analyses that show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods will be adequate for cooling.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Conduct vibration testing of a single full-scale control rod inside a guide tube and inside a column of graphite control-rod fuel elements.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	1700
<b>DDN(s) Supported:</b> C.11.03.02, C.11.03.05, C11.03.06		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman	
<b>Date:</b> 11-27-08	<b>Originating Organization:</b> General Atomics		

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct CR shock absorber testing. A simulated CR will be dropped within a simulated column of CR fuel elements test various candidate shock absorber designs.	GA, Wyle Laboratories, Hazen Research, or other commercial laboratory	1 year, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	600
3. Conduct CR structural integrity testing. A full-size CR assembly will be subjected to operational and accident-condition loads and temperatures to quantify margins against structural failure. The tests will also determine ultimate load capacity and elongation at failure for these conditions.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	1900

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.6-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Composite</b>			
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and Qualified
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
TRL 7 is achieved when the following conditions are met: (1) CR flow-induced vibration testing has been completed and the results confirm that any potential damage to the CRs or graphite CR channels due to flow-induced vibrations will not inhibit impact the capability to insert or withdraw the CRs in the reactor; (2) CR shock absorber testing has been completed and the results have resulted in selection of a satisfactory shock absorber design; and (3) CR structural integrity testing has been completed and the results confirm that the CR design has adequate margin against operational failure.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
Perform testing at the NGNP to verify that the CRs can be inserted and withdrawn from the CR channels with the neutron control assembly (NCA) providing the motive force. This test will be performed as part of the integrated test of an NCA, CR guide tube, and CR as described in the GA Test Plan 911133.	GA and NGNP operator	Must be completed ~3 months prior to installation of NCAs and CRs in NGNP	200 (incremental cost for CR testing)
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman	
<b>Date:</b> 11-27-08	<b>Originating Organization:</b> General Atomics		



<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.1-m	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Metallic</b>			
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Basic principles observed	Application formulated	Proof of concept
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>
<b>Basis for Rating</b> (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
As discussed in GA report 911175, GA has concluded that Hastelloy XR should be used initially as the material of construction for the NNGP CR metallic parts (with a conversion to ceramic composites at a later time). Hastelloy XR steel has a limited database in the United States as the material has been extensively developed in Japan for the HTRR, and it has not been codified in Section III of the ASME code. It is anticipated that a small materials development program will be needed to supplement the data and fill in any gaps that are present.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>
1. Perform engineering analyses to establish control rod operating conditions (e.g., temperatures, flow conditions, helium impurities, etc.) and develop control rod requirements		General Atoms (GA)	6 months starting near beginning of CD
<b>DDN(s) Supported:</b> N.11.02.10, N.11.02.11, N.11.02.16		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier	
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics		

<b>Additional Actions Sheets(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Develop control rod conceptual design. Perform FEA and seismic analyses to calculate the expected mechanical and seismic loads.	GA	3 months starting after completion of action 1	200
3. Conduct baseline physical and mechanical properties tests on material test specimens. The number of tests performed shall be adequate to obtain the data required for the statistically significant engineering database or supplement an existing database required for the material performance models	INL, ORNL, JAEA, CEA, KAERI, and/or commercial laboratories	6 months	500
4. Conduct irradiation tests to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties (from action 3). The testing shall be sufficient to establish a statistically significant engineering data base or supplement an existing database for the material performance models	INL, JAEA, CEA, KAERI, and/or ORNL	2 years, must be completed by ~mid 2013	~2000
5. Conduct corrosion tests in a reactor helium environment at reactor operating temperatures (up to ~1400°C) to determine the effects on the baseline physical and mechanical properties, including emissivity data, (from action 3). The testing shall be sufficient to establish a statistically significant engineering data base or supplement an existing database for the material performance models	INL, JAEA, CEA, KAERI, and/or ORNL	1 year, must be completed by ~mid 2013	750
6. Complete updating material behavior and failure models based on the data from actions 3, 4, and 5	GA	6 months starting as soon as data from actions 3, 4, and 5 are available	400

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.2-m	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Metallic</b>				
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale	
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 5 is achieved when the following conditions are met: (1) Adequate physical and materials properties testing of unirradiated, irradiated, and corrosion of Hastelloy XR parts have been performed to establish a statistically significant material properties engineering data base; and (2) Material behavior and failure models have been updated based on the testing.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Conduct engineering analysis to verify that components meet design and safety requirements, including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability.		General Atomics	12 months starting about half-way through FD	1000
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics			

<b>Additional Actions Sheets(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct engineering analysis to show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods will be adequate for cooling.	GA	6 months. Must be complete about 1.5 years before end of final design	200

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2a.3-m	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Reactor Internals-Control Rods (CR) - Metallic</b>				
<b>Description:</b>				
Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 6 is achieved upon completion of 1) engineering analyses have been completed and show that the control rod design meets design and safety requirements including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability requirements, and 2) engineering analyses that show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods will be adequate for cooling.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Conduct vibration testing of a single full-scale control rod inside a guide tube and inside a column of graphite control-rod fuel elements.		GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by 2019 prior to fab. of CRs for NNGP	1700
<b>DDN(s) Supported:</b> C.11.03.02, C.11.03.05, C11.03.06			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			John Saurwein, Russ Vollman	
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct CR shock absorber testing. A simulated CR will be dropped within a simulated column of CR fuel elements test various candidate shock absorber designs.	GA, Wyle Laboratories, Hazen Research, or other commercial laboratory	1 year, must be completed by 2019 prior to fab. of CRs for NGNP	600
3. Conduct CR structural integrity testing. A full-size CR assembly will be subjected to operational and accident-condition loads and temperatures to quantify margins against structural failure. The tests will also determine ultimate load capacity and elongation at failure for these conditions.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by 2019 prior to fab. of CRs for NGNP	1900

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2a.4-m	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals-Control Rods (CR) - Metallic</b>			
<b>Description:</b> Control Rods (CR) are located in 2 areas of the reactor core: near the inner boundary of the fuel and central replaceable reflector elements (12 rods); and near the outer boundary between the fuel and outer replaceable reflector reflectors (18 rods). The outer CR are used to control the power in the core and are inserted during normal operation. The inner CR are withdrawn during normal operation and are only used to shut down the nuclear reaction. The rod is a linear assembly of rigid links filled with boronated graphite compacts within a cylindrical sleeve. The joints between rigid links allow flexibility in the rod assembly. The sleeves and joints are the structural elements that contain the nonstructural absorber compacts and transfer the operational loads to the control rod drive. All control rods are identical to accommodate interchangeability.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and Qualified
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
TRL 7 is achieved when the following conditions are met: (1) CR flow-induced vibration testing has been completed and the results confirm that any potential damage to the CRs or graphite CR channels due to flow-induced vibrations will not inhibit impact the capability to insert or withdraw the CRs in the reactor; (2) CR shock absorber testing has been completed and the results have resulted in selection of a satisfactory shock absorber design; and (3) CR structural integrity testing has been completed and the results confirm that the CR design has adequate margin against operational failure.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
Perform testing at the NGNP to verify that the CRs can be inserted and withdrawn from the CR channels with the neutron control assembly (NCA) providing the motive force. This test will be performed as part of the integrated test of an NCA, CR guide tube, and CR.	GA and NGNP operator	Must be completed ~3 months prior to installation of NCAs and CRs in NGNP	200 (incremental cost for CR testing)
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman	
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics		

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.1-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>			
<b>Description:</b> The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS
	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP	
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Basic principles observed	Application formulated	Proof of concept
<b>TRL</b>	<b>1</b>	<b>2</b>	<b>3</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
The UCR design will be essentially the same as the one designed in the NP-MHTGR, but the higher temperatures to which the UCR will be subjected during conduction cooldown events in the NNGP may require use of a ceramic composite as the material of construction. Ceramic composite materials are widely used in aerospace but little data is available on irradiation effects and corrosion in an impure He environment, so a substantial materials development program is needed (see HTR2008 conference paper HTR2008-58050 and GA Report 911125/0). Composite architectures specific to the geometries of the various UCR components must be developed.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Perform engineering analyses to establish upper core restraint operating conditions (e.g., temperatures, flow conditions, helium impurities, etc.) and develop upper core restraint requirements	General Atoms (GA)	6 months starting near beginning of CD	350
<b>DDN(s) Supported:</b> N.11.02.25, N.11.02.26, N.11.02.27, and N.11.02.28,		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> John Saurwein, Russ Vollman, Jessie Crozier			
<b>Date:</b> 04-20-09	<b>Originating Organization:</b> General Atomics		



<b>Additional Actions Sheets(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Develop upper core restraint conceptual design. Perform FEA and seismic analyses to calculate the expected mechanical and seismic loads. Initiate development of UCR composite material performance models	GA	3 months starting after completion of action 1	200
3. Review ceramic composite materials knowledge base and composite materials supply network to select potential composite materials and parts manufacturers	GA/Rolls-Royce	6 months starting after completion of action 1	350
4. Develop composite architectures and manufacturing processes for the UCR elements. Fabricate shapes having the selected composite architectures and cut out specimens for the tests in actions 5, 6, and 7	GA/Rolls-Royce and part manufacturers	1 year, complete by ~middle of PD	3000
5. Conduct baseline physical and mechanical properties tests on test specimens from action 4.	ORNL, INL, and/or commercial laboratories	1 year, complete by end of PD	1000
6. Conduct screening irradiation tests on test specimens from action 4 to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties (from action 5)	INL and/or ORNL	3 years, complete 2 years into NNGP FD	TBD (A very rough estimate is ~\$20M)
7. Conduct screening corrosion tests on test specimens from action 4 in a reactor helium environment at reactor operating temperatures (up to ~1000°C) to determine the effects on the baseline physical and mechanical properties (from action 5)	INL and/or ORNL	2 years starting in parallel with action 6	1000
8. Select composite materials and architectures	GA/Rolls-Royce and parts manufacturers	3 months starting as soon as data are available from actions 6 & 7	200

<b>TRL Rating Sheet</b>					
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2d.2-c	<b>Revision:</b>	0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology					
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>					
<b>Description:</b>					
The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.					
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS <input type="checkbox"/> HTS <input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP				
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>	
<b>Technology Readiness Level</b>					
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level		
Generic Definitions ( <i>abbreviated</i> )	Application formulation	Proof of concept	Verified at bench scale		
<b>TRL</b>	<b>2</b>	<b>3</b>	<b>4</b>		
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>					
TRL 3 is achieved when the following conditions are met: (1) All of the engineering analyses and design activities and all of the testing activities required to advance the TRL from 2 to 3 have been completed; (2) Composite architectures have been selected based on the screening baseline physical and mechanical properties tests, irradiation tests, and corrosion tests on candidate composite architectures; and (3) The results of the tests on the selected composite architectures show that UCR elements fabricated from these materials have a high probability of satisfying UCR design requirements.					
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>					
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>	
1. Finalize the composite architectures for the UCR elements. Fabricate prototype parts and cut samples from the parts for actions 2, 3, and 4 below.		GA/Rolls-Royce, and parts manufacturers	6 months starting as soon as composite architectures are selected	2000	
<b>DDN(s) Supported:</b> N.11.02.25, N.11.02.26, N.11.02.27, and N.11.02.28,			<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>			John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b> 04-20-09		<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s):</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct baseline physical and mechanical properties tests on test specimens from action 1. The number of tests performed shall be adequate to obtain the data required for the statistically significant engineering data base required for the composite material performance models	INL, ORNL, and/or commercial laboratories	1 year starting as soon as test specimens from action 1 are available	1000
3. Conduct irradiation tests on test specimens from action 1 to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties (from action 2). The testing shall be sufficient to establish a statistically significant engineering data base for the composite material performance models	INL and/or ORNL	2 years, must be completed by ~mid 2017 to support NNGP startup in 2021	TBD (a very rough estimate is ~\$20m)
4. Conduct corrosion tests on test specimens from action 1 in a reactor helium environment at reactor operating temperatures (up to ~1000°C) to determine the effects on the baseline physical and mechanical properties (from action 2)	INL and/or ORNL	2 years, must be completed by ~mid 2017 to support NNGP startup in 2021	2000
5. Complete composite material behavior and failure models based on the data from actions 2, 3, and 4	GA	6 months starting as soon as data from actions 2, 3, and 4 are available	400

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.3-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>			
<b>Description:</b> The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS
	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP	
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at engineering scale
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
TRL 4 is achieved when the following conditions are met: (1) The composite architectures for the UCR elements have been finalized and prototype parts have been fabricated and cut up for testing; (2) Adequate physical and materials properties testing of unirradiated, irradiated, and corrosion specimens from the prototype parts have been performed to establish a statistically significant material properties engineering data base; and (3) Composite material behavior and failure models have been completed based on the composite properties engineering data base.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
Conduct engineering analysis to verify that components meet design and safety requirements, including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability.	General Atomics	12 months starting about half-way through FD	1000
<b>DDN(s) Supported:</b>		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> John Saurwein, Russ Vollman, Jessie Crozier			
<b>Date:</b> 03-10-09	<b>Originating Organization:</b> General Atomics		

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.4-c	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>			
<b>Description:</b> The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
TRL 5 is achieved once engineering analyses have been completed and show that the upper core restraint design meets design and safety requirements including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability requirements.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Engineering analyses will be performed to show fluid flow, freedom of movement for different thermal expansions, and seismic load / movement requirements. This analysis will show analytically how the UCR elements perform during normal differential thermal expansion, dynamic fluid flow, seismic shaking, and movement from graphite columns.	GA	6 months. Must be complete about 1.5 years before end of final design	500
<b>DDN(s) Supported:</b>		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier	
<b>Date:</b> 04-20-09	<b>Originating Organization:</b> General Atomics		

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Engineering analyses will be performed to show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal. This analysis will show analytically how the CR and RSM guide tubes respond during normal differential thermal expansion, dynamic fluid flow, seismic shaking, and non-normal events.	GA,	6 months. Must be complete about 1.5 years before end of final design	200

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.5-c	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>				
<b>Description:</b> The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 6 is achieved upon completion of engineering analyses that shows that the composite UCR elements meet the design and safety requirements. In addition, the UCR elements should be demonstrated to be capable of having the control rods inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
1. Conduct vibration testing of a full-scale UCR array with guide tubes, and above columns of graphite control-rod fuel elements.		GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	1500
<b>DDN(s) Supported:</b> C.11.03.44			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> John Saurwein, Russ Vollman, Jessie Crozier				
<b>Date:</b> 04-20-09		<b>Originating Organization:</b> General Atomics		

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct UCR structural integrity testing. A full-size UCR array will be subjected to operational and accident-condition loads and temperatures to quantify margins against structural failure. The tests will also determine ultimate load capacity and elongation at failure for these conditions.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	1000
3. Conduct UCR flow distribution and pressure drop testing. A full-size UCR array will be subjected to operational and accident-condition loads and temperatures to quantify pressure drop coefficients and coolant hole flow distributions as function of the Reynolds number.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by first quarter of 2020 prior to fab. of CRs for NNGP	1000



<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.6-c	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Composite</b>				
<b>Description:</b> The UCR consists of interconnecting composite plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and Qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved when the following conditions are met: (1) UCR flow-induced and seismic vibration testing has been completed and the results confirm the position of the UCR elements and that there is no impact on the capability to insert or withdraw the CRs in the reactor, (2) UCR structural integrity testing has been completed and the results confirm that the UCR design has adequate margin against operational failure, and (3) UCR testing of pressure drop and flow distribution through the UCR elements confirms with limits.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
Perform testing at the NGNP to verify integration of the UCR interfaces with other components as part of the integrated testing of the NCA, RSM, RSM guide tubes, CR guide tube, and CR. The test should include both normal and off-normal events. Position measurements and visual inspection are required.		GA and NGNP operator	Must be completed ~3 months prior to installation of NCAs and CRs in NGNP	1500
<b>DDN(s) Supported:</b>		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b> 03-10-09	<b>Originating Organization:</b> General Atomics			

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.1-m	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Metallic</b>				
<b>Description:</b> The UCR consists of interconnecting metallic plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Application formulation	Proof of concept	Verified at bench scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
As discussed in GA report 911175, GA has concluded that Hastelloy XR should be used as the material of construction for the NNGP UCR elements (with a conversion to ceramic composites at a later time). Hastelloy XR steel has a limited database in the United States as the material has been extensively developed in Japan for the HTTR, and it has not been codified in Section III of the ASME code. It is anticipated that a small materials development program will be needed to supplement the data and fill in any gaps that are present.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions</b> ( <i>list all</i> )		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Perform engineering analyses to establish upper core restraint operating conditions (e.g., temperatures, flow conditions, helium impurities, etc.) and develop upper core restraint requirements		General Atomics (GA)	6 months starting near beginning of CD	350
<b>DDN(s) Supported:</b> N.11.02.10, N.11.02.11, and N.11.02.16		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s):</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Develop upper core restraint conceptual design. Perform FEA and seismic analyses to calculate the expected mechanical and seismic loads. Initiate development of UCR performance models	GA	3 months starting after completion of action 1	200
3. Conduct physical and mechanical properties testing on Hastelloy XR specimens. The number of tests performed shall be adequate to obtain the data required for the statistically significant engineering database or supplement an existing database required for the material performance models	INL, ORNL, JAEA, CEA, KAERI, and/or commercial laboratories	1 year	1000
4. Conduct irradiation tests to determine irradiation induced dimensional changes and creep and to determine the effect of irradiation on the baseline physical and mechanical properties on Hastelloy XR (from action 3). The testing shall be sufficient to establish a statistically significant engineering database or supplement an existing database required for the material performance models	INL, JAEA, CEA, KAERI, and/or ORNL	2 years, must be completed by ~mid 2013	~2000
5. Conduct corrosion tests in a reactor helium environment at reactor operating temperatures (up to ~1000°C) to determine the effects on the baseline physical and mechanical properties, including emissivity, on Hastelloy XR (from action 3) The testing shall be sufficient to establish a statistically significant engineering database or supplement an existing database required for the material performance models	INL, JAEA, CEA, KAERI, and/or ORNL	2 years, must be completed by ~mid 2013	500
6. Complete updating metal behavior and failure models based on the data from actions 3, 4, and 5	GA	6 months starting as soon as data from actions 3, 4, and 5 are available	200

<b>TRL Rating Sheet</b>					
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-2d.2-m	<b>Revision:</b>	0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology					
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Metallic</b>					
<b>Description:</b>					
The UCR consists of interconnecting metallic plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.					
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>	
<b>Technology Readiness Level</b>					
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level		
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at engineering scale		
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>		
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>					
TRL 5 is achieved when the following conditions are met for the Hastelloy XR UCR elements: (1) Adequate physical and materials properties testing of unirradiated, irradiated, and corrosion specimens from the prototype parts have been performed to establish a statistically significant material properties engineering data base, and (2) Material behavior and failure models have been completed based on the properties engineering data base.					
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>					
<b>Actions (<i>list all</i>)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>	
1. Conduct engineering analysis to verify that components meet design and safety requirements, including thermal-hydraulic, corrosion and stress, dynamic and seismic, life, reliability, and maintainability. This analysis will show analytically how the UCR elements perform during normal differential thermal expansion, dynamic fluid flow, seismic shaking, and movement from graphite columns.		General Atomics	12 months starting about half-way through FD	1000	
<b>DDN(s) Supported:</b>			<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>			John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b>	4-20-09	<b>Originating Organization:</b>		General Atomics	

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Engineering analyses will be performed to show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal. This analysis will show analytically how the CR and RSM guide tubes respond during normal differential thermal expansion, dynamic fluid flow, seismic shaking, and non-normal events.	GA,	6 months. Must be complete about 1.5 years before end of final design	500

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.3-m	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Metallic</b>				
<b>Description:</b> The UCR consists of interconnecting metallic plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 6 is achieved upon completion of engineering analyses that show that the control rods can be inserted into the guide tubes and core graphite elements without interference for all normal and off-normal events and that the design helium coolant flow through the guide tubes, core graphite elements, and around the control rods.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1. Conduct vibration testing of a full-scale UCR array with guide tubes and above columns of graphite control-rod fuel elements.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed 2019 prior to fab. of CRs for NGNP	1500	
<b>DDN(s) Supported:</b> C.11.03.44		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b> John Saurwein, Russ Vollman, Jessie Crozier				
<b>Date:</b> 4-20-09	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Conduct UCR structural integrity testing. A full-size UCR array will be subjected to operational and accident-condition loads and temperatures to quantify margins against structural failure. The tests will also determine ultimate load capacity and elongation at failure for these conditions.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed 2019 prior to fab. of CRs for NGNP	1000
3. Conduct UCR flow distribution and pressure drop testing. A full-size UCR array will be subjected to operational and accident-condition loads and temperatures to quantify pressure drop coefficients and coolant hole flow distributions as function of the Reynolds number.	GA, Wyle Laboratories, Hazen Research, or INL CTF	18 months, must be completed by 2019 prior to fab. of CRs for NGNP	1000


<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-2d.4-m	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Internals - Upper Core Restraint (UCR) - Metallic</b>				
<b>Description:</b> The UCR consists of interconnecting metallic plenum elements which are located on the top layer of the reflector and permanent side reflector graphite blocks. All elements have hexagonal shapes except for those above the permanent side reflectors, which match the configuration of the permanent side reflectors. The UCR provides lateral restraint and stability to the core array, provides neutron flux attenuation to the reactor internals and reactor vessel, channels helium primary coolant from the upper plenum to the entrance of the reactor core, and maintains the capability to refuel the reactor core. In addition, the UCR provides channels to insert control rods, reserve shutdown pellets, and the In-Core Flux Mapping Unit (IFMU). The UCR assembly provides core stability and limits core movements. The plenum elements are keyed together to limit relative lateral motion within the UCR assembly. Connections between the core barrel and the plenum elements over the permanent side reflectors limit the translation and rotation of the UCR assembly with respect to the core barrel.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and Qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved when the following conditions are met: (1) UCR flow-induced and seismic vibration testing has been completed and the results confirm the position of the UCR elements and that there is no impact on the capability to insert or withdraw the CRs in the reactor, (2) UCR structural integrity testing has been completed and the results confirm that the UCR design has adequate margin against operational failure, and (3) UCR testing for estimating pressure drop and flow distribution through the UCR elements.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Perform testing at the NGNP to verify integration of the UCR interfaces with other components as part of the integrated testing of the NCA, RSM, RSM guide tubes, CR guide tube, and CR. The test should include both normal and off-normal events. Position measurements and visual inspection are required.		GA and NGNP operator	Must be completed ~3 months prior to installation of NCAs and CRs in NGNP	1500
<b>DDN(s) Supported:</b>		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		John Saurwein, Russ Vollman, Jessie Crozier		
<b>Date:</b> 4-20-09	<b>Originating Organization:</b>		General Atomics	



4/27/2009 1:24:44 AM

Revision 0


RC2-SSC02-Reactor Internals - Composite Control Rods Technology Roadmap



5/9/2009 4:01 PM


# Revision 0

## RC2-SSCO2-Reacto Internals - Metallic Control Rods Technology Roadmap



5/5/2008, 3:12 PM


Revision 0



5/6/2009 3:23 PM

# Revision 0

## RC2-SSC02-Reacto Internals-Metallic Upper Core Restraint Technology Roadmap



#### **4.3 RC2-SSC-3 Hot Duct TRL**

**TRL Rating Sheets, TRL 2 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-3.1	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b>				
The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The "cold" helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Basic principles observed	Application formulated	Proof of principal	
<b>TRL</b>	<b>1</b>	<b>2</b>	<b>3</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
An initial TRL of 2 has been assigned to the hot duct on the grounds that a proposed configuration for the insulated duct has been formulated and the technical challenges associated with containment of the flow of high temperature helium gas are understood. Additionally, published data indicate that there are commercially available insulating materials and duct alloys that are viable candidates for the application. (Cont.)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1) Establish safety class		GA	6 months	\$87 (Not including GA scope of work)
2) Establish code applicability (ASME pressure vessel, nuclear, piping, QA)		GA/URS-WD		
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> Greg Walz				
<b>Date:</b> 4-27-09		<b>Originating Organization:</b> Washington Division of URS		

**Additional Basis Sheet(s)**

Basis (continued):

However, critical functions and/or characteristics for a duct/insulation system have not been proven for the service conditions for NGNP. Analytical or experimental data testing the proposed configuration is not known to exist. Additionally, the critical functions of the duct/insulating system have not been finalized with regard to the following:

- Safety Class and Code applicability – final determination for the safety classification for the hot leg helium duct is needed to address plant licensing. Is credit for leak before break needed to support plant licensing, e.g., to preclude a total cross vessel failure (hot and cold duct) from consideration?
- Leak detection criteria and capability including that required to support credit for before break if needed, are critical characteristics that need to be defined for the specific configuration.
- Inspectability of welds if necessary, and required weld examinations are critical characteristics that pose a challenge for the co-axial hot and cold leg configuration with internal and external insulation.
- Inspectability of insulation: determine critical thickness of insulation, which is subject to erosion, and effect on overall system performance
- Stress Analysis – detailed stress analysis of the specific configurations under consideration for NGNP have not been performed, including differential temperature expansion.
- Accident Conditions – Design basis excursion pressures and temperatures to which the ductwork may be subjected have not been defined.

**Additional Action Sheet(s)**

<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
3) Determine thermal and mechanical properties of duct material	GA/URS-WD		
4) Determine thermal and mechanical properties of insulation material	GA/URS-WD		
5) Duct material stress testing under design basis event conditions	GA/URS-WD		
6) Establish conditions of service	GA		
7) Material selection	GA/URS-WD		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-3.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b> The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The "cold" helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Application formulated	Proof of principal	Demonstrated at bench scale	
<b>TRL</b>	<b>2</b>	<b>3</b>	<b>4</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 3 will be achieved on the basis of completion of the action items identified in the TRL rating sheet for TRL 2.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
1) Erosion/corrosion accelerated wear testing		GA/URS-WD	1 year	\$180
2) Environmental qualification of duct and insulation		GA/URS-WD		
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Greg Walz		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			



<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
3) Upfront CFD Analysis	GA/URS-WD		
4) Upfront FEA Analysis	GA/URS-WD		
5) Hot to cold leg leak detection	GA/URS-WD		
6) Insulation connection method	GA/URS-WD		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-3.3	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b> The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The "cold" helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of principal	Demonstrated at bench scale	Demonstrated at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
A TRL of 4 will be achieved on the basis of completion of the action items identified in the TRL rating sheet for TRL 3.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1) Hot duct and insulation materials property tests including: Room temperature and high temperature material properties verification, Environmental qualifications, Irradiation (specification and interpretation), Weldability and weld strength, Stress corrosion cracking		GA/URS-WD	1 year	610 – 810 Excluding INL and HFEF Costs
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Greg Walz		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2) Component level test	GA/URS-WD		Included above
3) Life cycle cost analysis	GA/URS-WD		
4) RAMI analysis	GA/URS-WD		
5) Acoustic and Flow vibrations test	GA/URS-WD & SME		
6) Creep analysis	GA/URS-WD & SME		
7) Endurance limit analysis	GA/URS-WD & Becht NS		
8) ALARA analysis	GA/URS-WD		
9) Limit analysis	GA/URS-WD & Becht NS		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-3.4	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b> The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The "cold" helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at bench scale	Demonstrated at experimental scale	Demonstrated at pilot scale	
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 5 will be achieved on the basis of completion of the action items identified in the TRL rating sheet for TRL 4.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1) FEA analysis - Stress analysis to optimize physical configuration	GA/URS-WD	1 year	367 - 417	
2) CFD analysis to optimize physical configuration - including insulation performance and flow conditions in the hot and cold duct sections (Cont.)	GA/URS-WD			
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Greg Walz		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
3) Sub-system level test	URS-WD		Included Above
4) Final thermal expansion analysis	URS-WD		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-3.5	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b> The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The “cold” helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at experimental scale	Demonstrated at pilot scale	Demonstrated at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 6 will be achieved on the basis of completion of the action items identified in the TRL rating sheet for TRL 5.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1) Testing of integrated system using 1/10 scale model	GA/URS-WD	1 year	545 - 795	
a) Measure parameters needed to validate models and observe scale model performance	GA/URS-WD			
b) Terminal end (nozzle) attachment method/allowable nozzle loads	GA/URS-WD			
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Greg Walz		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost</b>
c) Evaluate methods to conduct in-service inspections	URS-WD		Included above
d) Establish and validate installation techniques	URS-WD		
2) Conduct risk assessment to determine extent of CTF testing requirements	URS-WD		


<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-3.6	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Hot Duct and Insulation Between Reactor and Steam Generator</b>				
<b>Description:</b> The hot duct is an assembly of insulation and ducting through which the helium coolant exiting the reactor core at 750-800°C is transported to the steam generator. The ducting is located within the cross vessel and has a co-axial configuration with the cross vessel. The "cold" helium at ~340°C exiting the steam generator is returned to the reactor vessel through the annular flow path between the hot duct and cross vessel. The nominal peak operating temperature of the hot duct is 800°C, but the hot duct could be exposed to somewhat higher temperatures due to hot streaking of the helium exiting the core. Considered insulation will be both internal and external to the duct, consistent with assumptions made in GA Report 911105/0.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b> 3310	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at pilot scale	Demonstrated at engineering scale	Tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 7 will be achieved on the basis of completion of the action items identified in the TRL rating sheet for TRL 6.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1) Integrated CTF testing (as a part of a larger test effort)	GA/URS-WD	2 Years (coordinate with others)	500 (GA, INL/BEA Scope not included)	
2) Validate concept of in-service inspection	GA/URS-WD			
3) Test uniformity of duct heating	GA/URS-WD			
<b>DDN(s) Supported:</b> C.11.02.02, C.11.02.12, C.11.02.13, C.11.02.14, C.11.02.15, N.11.02.12, N.11.02.13, N.11.02.14		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Greg Walz		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			



<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost</b>
4) Validate concept of cold to hot leg leak detection	GA/URS-WD		Included above
5) Validate analytical testing based on risk assessment - FEA simulations validation - CFD simulations validation	GA/URS-WD		

4/27/2009 6:15 PM

Revision 0



#### **4.4 RC2-SSC-4a Reactor Core Assembly and RC2-SSC-4b Reactor Graphite Elements**

**Reactor Core Assembly, TRL Rating Sheets, TRL 5 through 7**

**Reactor Graphite Elements, TRL Rating Sheets, TRL 6 and 7**

**Technology Development Road Maps**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-4a.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Core</b>			
<b>Description:</b> The primary functions of the Reactor Core are to generate high temperature heat using nuclear fission, transfer the heat to the helium coolant, and control radiation from the core. The Reactor Core consists of fuel elements, inner and outer reflector elements, upper reflector elements, and lower reflector elements (including flow distribution elements). All of these elements are hexagonal-shaped blocks manufactured from nuclear grade graphite. In terms of SSC categorization, the permanent side reflector is assumed to be part of Reactor Internals. (Cont. on additional description sheet)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Components verified at bench scale	Components verified at experimental scale	Subsystem verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The testing programs to support design of the Ft. St. Vrain (FSV) reactor and the operational data base from FSV justify a high TRL level for this system. However, FSV used grades H-327 and H-451 graphite that are no longer available and the NGNP prismatic core design will likely adopt one of the new grades of graphite that are under development (e.g., PCEA, NBG-17 or NBG-18), as described in the NGNP Graphite Technology Development Plan prepared by INL. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Perform thermal/flow testing of individual fuel and reflector elements.	DOE Labs	1 year after start of final design	3,000
2. Perform detailed CFD modeling of individual fuel and reflector elements.	Vendor	2 years after start of final design	400
<b>DDN(s) Supported:</b> C.11.03.03, C.11.03.04, C.11.03.41, C.11.03.42, C.11.03.43, C.11.03.44		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Matt Richards	
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics		

### Additional Description Sheet(s)

**Description:**

The principal fuel elements are in the form of a right hexagonal prism, 793 mm high and 360 mm across the flats. The two other types of fuel elements are those with control-rod channels and those with reserve-shutdown channels. The active core (fueled region) consists of 102 fuel columns with 10 blocks per column, comprising a 3-row annular region. The active core is surrounded by prismatic blocks that form the upper, lower, inner, and side reflectors. Some of the columns in the outer reflector and active core (and possibly the inner reflector, depending on the final core design) contain channels for controls rods. Some of the columns in the active core also contain channels for reserve shutdown material.

### Additional Basis Sheet(s)

**Basis:**

In addition, the NGNP core configuration is significantly different from FSV (annular core for NGNP vs. cylindrical core for FSV and 10-block high core for NGNP vs. 6-block high core for FSV). For these reasons, the starting TRL level is judged to be 5 for this system.

A TRL level of 6 is achieved after test programs to satisfy the following DDNS are successfully completed: C.11.03.03 (Core Element Dynamic Strength Data), C.11.03.04 (Core Element Failure Mode Data), C.11.03.41 (Fuel Element Channel Flow Data), C.11.03.42 (Control Rod Flow Channel Data).

### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
3. Perform mechanical testing of individual fuel and reflector elements.	DOE Labs	1 year after start of final design	7,000
4. Perform detailed finite-element stress analyses of individual fuel and reflector elements.	Vendor	2 years after start of final design	400

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-4a.2	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Core</b>			
<b>Description:</b> The primary functions of the Reactor Core are to generate high temperature heat using nuclear fission, transfer the heat to the helium coolant, and control radiation from the core. The Reactor Core consists of fuel elements, inner and outer reflector elements, upper reflector elements, and lower reflector elements (including flow distribution elements). All of these elements are hexagonal-shaped blocks manufactured from nuclear grade graphite. In terms of SSC categorization, the permanent side reflector is assumed to be part of Reactor Internals. (Cont. on additional description sheet)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Components verified at experimental scale	Subsystem verified at pilot scale	System verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
TRL 6 is achieved for this system after all test data have been obtained and detailed modeling has been performed for the individual fuel and reflector elements to satisfy DDNs C.11.03.03, C.11.03.04, C.11.03.41, C.11.03.42, C.11.03.43, C.11.03.44. To advance to TRL 7, testing programs must be completed to satisfy the following DDNs: C.11.03.01 (Core Column Vibration Data), C.11.03.45 (Core Crossflow Test Data), C.11.03.46 (Core Fluctuation Test Data), C.11.03.43 (Bottom Reflector/Core Support Pressure Drop and Flow Mixing Data), C.11.03.44 (Metallic Plenum Element and Top Reflector Pressure Drop and Flow Distribution).			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Perform multiple-block testing and to obtain core column vibration data.	DOE Labs	2 years after start of final design	4,000
2. Perform detailed modeling of core vibrations.	Vendor	3 years after start of final design	400
<b>DDN(s) Supported:</b> C.11.03.01, C.11.03.45, C.11.03.46		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Matt Richards	
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics		

**Additional Description Sheet(s)**

Description:

The principal fuel elements are in the form of a right hexagonal prism, 793 mm high and 360 mm across the flats. The two other types of fuel elements are those with control-rod channels and those with reserve-shutdown channels. The active core (fueled region) consists of 102 fuel columns with 10 blocks per column, comprising a 3-row annular region. The active core is surrounded by prismatic blocks that form the upper, lower, inner, and side reflectors. Some of the columns in the outer reflector and active core (and possibly the inner reflector, depending on the final core design) contain channels for controls rods. Some of the columns in the active core also contain channels for reserve shutdown material.

**Additional Action Sheet(s)**

<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
3. Perform mock-up testing to obtain data for horizontal cross flow.	DOE Labs	2 years after start of final design	3,000
4. Perform detailed CFD analyses of cross flow.	Vendor	3 years after start of final design	200
5. Perform mock-up testing to obtain data for core flow fluctuations and hot streaks.	DOE Labs	2 years after start of final design	5,000
6. Perform CFD analyses of core flow fluctuations and hot streaks.	Vendor	3 years after start of final design	400

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-4a.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Core</b>				
<b>Description:</b> The Reactor Core consists of fuel elements, inner and outer reflector elements, upper reflector elements, and lower reflector elements (including flow distribution elements). All of these elements are hexagonal-shaped blocks manufactured from nuclear grade graphite. In terms of SSC categorization, the permanent side reflector is assumed to be part of Reactor Internals. The principal fuel elements are in the form of a right hexagonal prism, 793 mm high and 360 mm across the flats. The two other types of fuel elements are those with control-rod channels and those with reserve-shutdown channels. The active core (fueled region) consists of 102 fuel columns with 10 blocks per column, comprising a 3-row annular region. The active core is surrounded by prismatic blocks that form the upper, lower, inner, and side reflectors. Some of the columns in the outer reflector and active core (and possibly the inner reflector, depending on the final core design) contain channels for controls rods. Some of the columns in the active core also contain channels for reserve shutdown material.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	System tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved for this system after all integral test data have been obtained and detailed modeling has been performed to satisfy DDNs C.11.03.01, C.11.03.45, and C.11.03.46.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1. Perform instrumented tests as part of NGNP startup testing to confirm flow distributions, temperature distributions, and mechanical loadings are within design specifications.	GA/NGNP operator	TBD	TBD	
<b>DDN(s) Supported:</b> C11.03.01, C11.03.45, C.11.03.46		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Matt Richards		
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics			



<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-4b.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Graphite</b>			
<b>Description:</b> The graphite components of the reactor system are the core (fuel elements and replaceable reflector elements), the permanent side reflector, and the core support structure.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Component verified at experimental scale	Component verified at pilot scale	Component verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Nuclear-grade graphite is a mature technology and has been used previously in several HTGRS, including Ft. St. Vrain, which used block graphite elements manufactured from H-451 graphite. However, H-451 graphite is no longer commercially available and a graphite to replace H-451 is needed for a block-type NGNP core. The 30 MWt HTTR reactor in Oarai, Japan uses block graphite fuel and reflector elements manufactured from IG-110 graphite. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Perform test programs to obtain the requisite design data to advance to TRL 7	DOE Labs	3 years before completion of final design.	84,000
2. Obtain necessary ASME/ASTM code approvals.	Vendor / DOE Labs	2 years before completion of final design	2,000
3. Perform detailed modeling of in-core and accident-condition performance of graphite elements to establish design margins.	Vendor	1 year before completion of final design	1,500
<b>DDN(s) Supported:</b> C.11.03.11 through C.11.03.21 and C.11.03.23.		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Matt Richards	
<b>Date:</b> 10/30/08	<b>Originating Organization:</b> General Atomics		

### **Additional Basis Sheet(s)**

**Basis:**

For NGNP, new nuclear-grade graphites are being developed and qualified, including grades PCEA, NBG-17 and NBG-18 that can be used for a block-type core. Because of the extensive experience base with the manufacture and irradiation of nuclear-grade graphite, a TRL level of 6 is judged to be appropriate for this component.

A TRL level of 7 is achieved after the requisite design data have been obtained for the new graphite. These data are specified in the following Design Data Needs (DDNs): C.11.03.11 (Graphite Multiaxial Strength Data), C.11.03.12 (Graphite Fatigue Data), C.11.03.13 (Graphite Mechanical Properties Data), C.11.03.14 (Graphite Irradiation Induced Dimensional Change Data), C.11.03.15 (Graphite Irradiation Induced Creep Data), C.11.03.16 (Graphite Thermal Properties Data), C.11.03.17 (Graphite Fracture Mechanics Data), C.11.03.18 (Graphite Corrosion Data), C.11.03.19 (Graphite Corrosion Data for Methods Validation), C.11.03.20 (Graphite Destructive and Nondestructive Examination Data), C.11.03.21 (Graphite Coke Source Qualification), and C.11.03.23 (Graphite Oxidation Data for Postulated Accidents). These DDNs will be satisfied by completion of the graphite technology development plan described in INL document PLN-2497, Rev. 0.


Note: Another possible strategy is to startup the NGNP without having obtained the complete data base as defined by the above DDNs and use data obtained during the startup phase (either from NGNP operation or ongoing testing at DOE laboratories) to satisfy some elements of these DDNs.

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-4b.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Graphite</b>				
<b>Description:</b> The graphite components of the reactor system are the core (fuel elements and replaceable reflector elements), the permanent side reflector, and the core support structure.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at pilot scale	Component verified at engineering scale	System tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved for this system after design data have been obtained for a replacement to H-451 graphite. The required design data are described in the following Design Data Needs (DDNs): C.11.03.11 through C.11.03.21 and C.11.02.23. These DDNs will be satisfied by completion of the graphite technology development plan described in INL document PLN-2497, Rev. 0.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1. Perform instrumented tests as part of NGNP startup testing to confirm physical, mechanical, thermal, and chemical properties. Perform inspections of selected fuel and reflector elements at the end of startup testing.	Vendor/ Operator	NGNP Startup Phase	15,000	
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Matt Richards		
<b>Date:</b> 10/30/08	<b>Originating Organization:</b> General Atomics			

4/21/2009 11:01 AM

Revision 0

RC2-SSC04a- Reactor Core Technology Roadmap





#### **4.5 RC2-SSC-5 Reactor Pressure Vessel**

**TRL Rating Sheets, TRL 5 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-5.1
		<b>Revision:</b>	0
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component
<input type="checkbox"/> Technology			
<b>Title: Reactor Pressure Vessel (RPV)</b>			
<b>Description:</b> The RPV houses the reactor, the reactor internals, and the reactor support structure. The RPV consists of a main cylindrical section with hemispherical upper and lower heads. The upper head, which is bolted to the cylindrical section, has penetrations for the neutron control assemblies and in-vessel flux monitoring unit. The lower section, which is welded to the cylindrical section, has penetrations for the Shutdown Cooling System, the In-Service Inspection access, and source range neutron detectors. For a 600 MWt prismatic NNGP, the RPV would be larger in diameter (about 7.2 m I.D) than most LWR vessels, but the wall thickness would be comparable.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS
	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP	
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Component verified at bench scale	Component verified at engineering scale	Subsystem verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
As discussed in GA report PC-000566, GA has concluded that SA-508/533 steel should be used as the material of construction for the NNGP RPV. SA-508/533 steel has an extensive experience base as the material used for current generation LWR RPVs, and it has been codified in Section III of the ASME code. The RPV for a 600-MWt prismatic NNGP would be larger in diameter than most LWR vessels, but the wall thickness would be comparable, and it has been determined that forgings of the (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Develop RPV design requirements. This activity will include thermal-hydraulic analyses to calculate RPV temperatures and to assess the sensitivity of RPV temperatures to key parameters such as emissivity. Analyses will also be performed to define the design and expected helium impurity levels specific to (Cont.)	GA	9 months starting early in CD	750
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein	
<b>Date:</b> 4-2-09	<b>Originating Organization:</b> General Atomics		

### **Additional Basis Sheet(s)**

Basis:

required size are within the capabilities of a major forging supplier (Japan Steel Works).

GA has also concluded that it will not be necessary to include an active vessel cooling system (VCS) in the NNGP design with a reactor outlet helium temperature of 750°C. The vessel operating temperature is only a concern if the temperatures are pushing against the 371°C ASME code limit for SA508/533 steel and the design lifetime of the RPV is very long (e.g., 60 years). With a reactor outlet helium temperature of 750°C, the reactor inlet helium temperature will be limited to 350°C, which will result in maximum vessel temperatures of about 320°C. Vessel temperatures at this level should be sufficiently low to eliminate any concerns with regard to vessel creep damage.

Although there is a sufficient mechanical properties database for SA508/533, there is limited data available on the thermal aging effects on the mechanical properties, so additional information is needed on long-term aging effects. In particular, no data is available on the effects of impure helium on the long-term corrosion and mechanical properties of this material. Consequently, additional data on thermal aging and environmental effects are considered to be needed to support licensing. Also, as discussed in INL document PLN-2803, INL and ORNL have identified creep deformation as a potential concern for the NNGP SA-508/533 RPV and have recommended an extensive program of stress-rupture testing to address this concern. This concern derives from the 60-year design lifetime for the RPV and the environmental conditions within the RPV will be under during normal reactor operation.

In summary, GA has assigned a technology readiness level (TRL) of 5 to the RPV based on the extensive experience base for SA508/SA533 as the material of construction for current generation LWR RPVs and codification of this material in Section III of the ASME code. GA does not consider long-term creep effects to be a potential problem for the NNGP RPV based on the assumption that the RPV temperature is below 350°C during normal reactor operations. Further, although some testing will be needed for confirmation and licensing purposes, GA does not believe that there are likely to be any significant deleterious effects of impure helium on the mechanical properties of the SA-508/533 vessel based on the experience with 2.25Cr-1Mo steel in the HTTR.





<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-5.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Pressure Vessel (RPV)</b>				
<b>Description:</b> The RPV houses the reactor, the reactor internals, and the reactor support structure. The RPV consists of a main cylindrical section with hemispherical upper and lower heads. The upper head, which is bolted to the cylindrical section, has penetrations for the neutron control assemblies and in-vessel flux monitoring unit. The lower section, which is welded to the cylindrical section, has penetrations for the Shutdown Cooling System, the In-Service Inspection access, and source range neutron detectors. For a 600 MWt prismatic NGNP, the RPV would be larger in diameter (about 7.2 m I.D) than most LWR vessels, but the wall thickness would be comparable.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at experimental scale	Component verified at pilot scale	Component verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 6 is achieved when the following conditions are met: (1) The design requirements for the RPV system have been defined, and (2) the necessary testing program for SA-508/533 has been defined and performed, and the data needed to support final design of the RPV and to support NGNP licensing has been obtained.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Develop the final design of the RPV, and prepare and issue the procurement specifications for the RPV		GA	6 months starting early in FD	250
<b>DDN(s) Supported:</b> None			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein		
<b>Date:</b> 4-2-09	<b>Originating Organization:</b> General Atomics			


<b>Additional Action Sheet(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Develop the detailed design of the RPV and confirm that the design satisfies all ASME code rules for the RPV. Perform analyses to verify with high confidence that the maximum RPV temperatures will be within ASME code limits for SA-508/533 with adequate margin to eliminate concerns about creep effects over a 60-year lifetime.	GA	1 year starting about 1.5 years into NNGP FD	500

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-5.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Pressure Vessel (RPV)</b>				
<b>Description:</b> The RPV houses the reactor, the reactor internals, and the reactor support structure. The RPV consists of a main cylindrical section with hemispherical upper and lower heads. The upper head, which is bolted to the cylindrical section, has penetrations for the neutron control assemblies and in-vessel flux monitoring unit. The lower section, which is welded to the cylindrical section, has penetrations for the Shutdown Cooling System, the In-Service Inspection access, and source range neutron detectors. For a 600 MWt prismatic NNGP, the RPV would be larger in diameter (about 7.2 m I.D) than most LWR vessels, but the wall thickness would be comparable.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at pilot scale	Component verified at engineering scale	Component tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 7 is achieved when the RPV analyses have been completed and verify with high confidence that the maximum RPV temperatures will be within ASME code limits for SA-508/533 with adequate margin to eliminate concerns about creep effects over a 60-year lifetime.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
Conduct testing of the RPV in the actual operating environment (i.e., in the NNGP during start-up testing) to verify vessel temperatures are within the limits defined in the NNGP technical specifications. The first part of this activity will be to prepare the Test Specification (or alternately to define the test in the NNGP start-up plan).		GA, NNGP operator	During NNGP start-up testing	Cost to be covered under NNGP start-up testing
<b>DDN(s) Supported:</b> None			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein		
<b>Date:</b> 4-2-09	<b>Originating Organization:</b> General Atomics			

4/21/2009 11:01 AM

# Revision 0

## RC2-SSC05-Reactor Pressure Vessel Technology Roadmap



#### **4.6 RC2-SSC-6 Helium Circulator**

**TRL Rating Sheets, TRL 6 and 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-6.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input checked="" type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Helium Circulators (PHTS, SCS, SHTS)</b>			
<b>Description:</b> Main Circulator: The NGNP circulator is a variable speed, electric motor-driven axial flow helium compressor that facilitates thermal energy transfer from the reactor core to the steam generator and, hence, to the external turbo-generator set.			
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Item verified at experimental scale	Item verified at pilot scale	Item verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The NGNP helium circulator development builds on earlier studies carried out by circulator vendors for GA. The design proposed by Howden for the MHTGR program in 1989 was a two-stage axial flow machine running at 4500 rpm, with a maximum power rating of 4 MWe. It featured an induction motor and an AMB system. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
<b>1. Bearing Design Verification:</b>  a. Determine static and dynamic axial thrust load capacities, stiffness, and damping coefficients over the operating speed range. b. Determine sensitivity of the associated electronic control system to external disturbances c. Rotor dynamic response to externally induced unbalance loads occurring in the impeller plane of rotation d. Magnitude of drag losses	Vendor, INL CTF or PBMR HTF	2012-2013	2,900
<b>DDN(s) Supported:</b> C.14.01.01, M.21.01.01, M.21.01.03		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Puja Gupta	
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics		

### **Additional Basis Sheet(s)**

**Basis:**

Further to this, in 1993, Howden also designed the helium circulator for the New Production-Modular High Temperature Gas-cooled Reactor (NP-MHTGR) program. The selected design had radial flow impeller, oil-bath lubricated bearings, submerged motor drive, rotational speed of about 3000 rpm and a maximum power level of approximately 6 MWe. The James Howden Company has designed and built 112 machines for the commercial Advanced Gas Reactor (AGR) plants. Howden has designed a 4 MWe helium circulator to the concept stage for GA. Data on helium circulators are primarily available from component testing performed for Fort St. Vrain and the proposed Delmarva plant. The database has applicability limited to the design of axial compressors and shutoff valves. Considerable operating experience with magnetic bearings in various industrial applications has been accumulated, and covers the size and load range of a circulator of 4 to 5 MWe. Societe de Mecanique Magnetique (S2M), the world's leading manufacturer of magnetic bearings, has some proprietary data under various non-representative conditions. There is also experience with magnetic bearings for use in centrifuge enrichment equipment as part of some classified government programs. Part of this work has recently been declassified.

Data on characteristics and performance of AMBs operating in conditions representative of the NNGP MC environment have not been established. There is a lack of data on the reliability of backup "catcher" bearings for vertical rotors to repeatedly support the turning rotor for a limited time when the active magnetic field supporting the rotor is lost.




<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
e. Development testing of alternate bearings, operating procedures, lubricants, and/or materials, if the reference design is unsatisfactory f. Evaluation of aerodynamic load simulation, including decay, in the test rig g. Demonstrate capability of catcher bearings to support the full scale vertical circulator rotor with failed AMBs during the coast down at all steady state, transient pressurized and depressurized operating conditions in helium			
<b>2. Scale Model Circulator Aerodynamic Flow Testing:</b>  a. Determine pressure rise across the compressor as a function of speed and helium flow through the compressor b. Determine overall efficiency including impeller and diffuser efficiency	Vendor, INL CTF or PBMR HTF	2012-2013	1,100
<b>3. Motor Cooling Design and Insulation Dielectric Strength Verification:</b>  a. Measure necessary buffer gas flow to prevent the leakage of radioactive helium into the motor cavity b. Perform flashover tests in air at atmospheric pressure and in helium at three pressures: atmospheric, operating pressure, and an intermediate pressure to obtain flashover data as a function of helium pressure for the various insulation and rectifier components c. Obtain corona start data for the stator insulation versus helium pressure. d. Confirm the satisfactory performance of insulation and diode by test.	Vendor, INL CTF or PBMR HTF	2014	550

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-6.2	<b>Revision:</b> 0
<input type="checkbox"/> Area <input type="checkbox"/> System <input checked="" type="checkbox"/> Subsystem/Structure <input type="checkbox"/> Component <input type="checkbox"/> Technology				
<b>Title: Helium Circulators (PHTS, SCS, SHTS)</b>				
<b>Description:</b> Main Circulator: The NGNP circulator is a variable speed, electric motor-driven axial flow helium compressor that facilitates thermal energy transfer from the reactor core to the steam generator and, hence, to the external turbo-generator set.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Item verified at pilot scale	Item verified at engineering scale	Item tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved upon successful completion of the testing outlined in the TRL rating sheet for TRL 6 (and Section 3 of Test Plan 911138). Successful completion of these tests would demonstrate reliability/availability goals for the components such as insulation, diodes, motor cooling heat exchanger, shaft mounted motor cooling fans, journal and thrust AMB, catcher bearings, as well as full size labyrinth shaft seal have demonstrated reliability/availability goals under relevant environment.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
1. Prototype Circulator Design Verification  a. Buffer Helium Transient Tests b. Shaft Brake Test c. Low Speed Test d. Hot Restart Test e. Rapid Depressurization Test f. Endurance Test g. Acoustic and Vibration Test h. Spin Test		INL CTF or NGNP Prototype Location	2014-2016	25,000
<b>DDN(s) Supported:</b> C.14.01.03, M.21.01.02, M.57.01.02			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			Puja Gupta	
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Extended Duration Testing	INL CTF or NNGP Prototype Location	2017 (qt 1,2)	
3. Modified Main Circulator Testing (if necessary)	INL CTF or NNGP Prototype Location	2017 (qt 3,4)	
4. Addition Circulators Proof Testing in Support of First Plant Operation	INL CTF or NNGP Prototype Location	2018-2020	

4/21/2009 11:04 AM

Revision 0



**4.7 RC2-SSC-8 Shutdown Cooling Heat Exchanger**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-8.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component
<b>Title: Shutdown Cooling Heat Exchanger (SCHE)</b>			
<b>Description:</b> The Shutdown Cooling Heat Exchanger (SCHE) is a multi-tube helical coil heat exchanger. It is similar in design to the evaporator/economizer portion of the FSV steam generator. Its function is to cool the reactor whenever the primary cooling system is not available. It is a vertical cross-counter flow heat exchanger. The tubes are made of 2-1/4 Croloy (ASTM A213, T22). The heat is removed by 60°C-pressurized (4.8MPa) water. The SCHE does not have a safety function.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS
	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP	
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at experimental scale
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
The Shutdown Cooling Heat Exchanger (SCHE) will be a helical coil tube heat exchanger similar in design to successfully operating heat exchangers in other gas cooled reactor plants including FSV and THTR. The previous experience with helical coiled heat exchangers has shown that the heat transfer correlations for flow across tube bundles match the predicted values (ASME Paper 79-WA/NE-1) thus providing a starting point for heat exchanger sizing. The selected tube material is 2-1/4 Croloy (ASTM A213, T22).			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Computer models will be used to evaluate the following: 1) The heat exchanger thermal sizing which is based on pressurized cooldown from 100% power operation. 2) The heat exchanger gas side pressure drop evaluation, which is based on depressurized cooldown from 100% power operation. 3) The structural evaluation of the tubes, which is based on the maximum tube temperature in a hot streak location. (Cont.)	GA	2 years starting at beginning of conceptual design	2000
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dave Carosella, Bob Schleicher	
<b>Date:</b> 12-9-08	<b>Originating Organization:</b> General Atomics		

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
<p>Actions:</p> <p>The shroud material, the shroud insulation and the shroud insulation cover sheet must be selected based on evaluation of the effect of the environment on the shroud its insulation and the insulation cover sheet. Analysis can be used to determine the shroud, the insulation and the insulation cover sheet temperature levels. Temperature levels must be determined for the following operating conditions: steady state operation at full power, conduction cooldown and shutdown on the SCHE. The possible shroud and cover sheet material choices include Alloy 800H, Inconel 617, Haynes 230 or Hastelloy XR. The possible shroud insulation choices include: Kaowool, Alltemp Insulation and porous carbon Insulation.</p>			

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-8.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Shutdown Cooling Heat Exchanger (SCHE)</b>				
<b>Description:</b> The Shutdown Cooling Heat Exchanger (SCHE) is a multi-tube helical coil heat exchanger. It is similar in design to the evaporator/economizer portion of the FSV steam generator. Its function is to cool the reactor whenever the primary cooling system is not available. It is a vertical cross-counter flow heat exchanger. The tubes are made of 2-1/4 Croloy (ASTM A213, T22). The heat is removed by 60°C-pressurized (4.8MPa) water. The SCHE does not have a safety function.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale	
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 5 will be achieved upon completion of the computer modeling activity described in the TRL rating sheet for TRL 4. In the computer modeling task, the heat exchanger was sized; the heat exchanger pressure drop was evaluated; the structural analysis was performed; and the temperatures and stress levels of the shroud, the insulation, and the insulation cover plates were calculated and used to select the materials for these components.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
The following tests will be performed on a mockup of an actual heat exchanger bundle with shrouds.  1. Perform testing of the SCHE shroud seal to determine measured leakage rates for combinations of different surface finishes, flatness tolerances, (cont.)		GA/SCHE vendor	2 years starting at beginning of preliminary design	2150
<b>DDN(s) Supported:</b> C.14.04.01, C.14.04.05, C.14.04.06, C.14.04.07			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> Dave Carosella, Bob Schleicher				
<b>Date:</b> 12-9-08		<b>Originating Organization:</b> General Atomics		



<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
<p>loads, and differential pressures under typical operating conditions. The shroud seal design consists of a metal bellows spring that compresses a circumferential seal. The testing will also include mechanical testing of the bellow assembly</p> <p>2. Perform tests to characterize inlet flow and temperatures distributions under various operating modes and to determine the need for inlet flow distribution devices. If such devices are determined to be needed, perform tests to evaluate and compare candidate designs.</p> <p>3. Perform tests to investigate the effects of acoustic noise on the large surface area structures of the SCHE. These tests will include the effects of coolant flow through the tube bundle so that the combined effects of acoustic noise and flow induced vibration can be assessed.</p> <p>4. Evaluate the frequency response and dynamic loads of the insulation cover plates and attachments during the flow distribution and acoustics testing.</p> <p>5. Determine the pressure drop flow characteristics of the water-side inlet orifice.</p> <p>Note: SCHE DDNs C.14.04.02, C.14.04.03, and C.14.04.09 will be satisfied by the steam generator technology development program</p>			


<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-8.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Shutdown Cooling Heat Exchanger (SCHE)</b>				
<b>Description:</b> The Shutdown Cooling Heat Exchanger (SCHE) is a multi-tube helical coil heat exchanger. It is similar in design to the evaporator/economizer portion of the FSV steam generator. Its function is to cool the reactor whenever the primary cooling system is not available. It is a vertical cross-counter flow heat exchanger. The tubes are made of 2-1/4 Croloy (ASTM A213, T22). The heat is removed by 60°C-pressurized (4.8MPa) water. The SCHE does not have a safety function.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 6 is achieved upon successful completion of the SCHE design support testing identified in the TRL rating sheet for TRL 5. Achievement of TRL 6 for the SCHE is also dependent on successful completion of the elements of the steam generator design support testing program that is required to satisfy SCHE DDNs C.14.04.02 (vibrational fretting wear and sliding wear of wear protection devices for bare tubes), C14.04.03 (instrument attachment tests), and C14.04.09 (helical coil tube fabrication development).				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Complete final design		GA	2 years	3,000
2. Build a full-size prototype SCHE		SCHE vendor	1 year	6,000
3. Perform flow testing on the full size SCHE to verify thermal/hydraulic and flow induced vibration performance. This test will verify the heat transfer and pressure drop and flow induced vibration characteristics of the tube bundle.		GA/Test Facility	1 year ending 3 years into final design	5,000
<b>DDN(s) Supported:</b> C.14.04.08			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dave Carosella, Bob Schleicher		
<b>Date:</b> 12-09-08	<b>Originating Organization:</b> General Atomics			

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-8.4	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Shutdown Cooling Heat Exchanger (SCHE)</b>				
<b>Description:</b> The Shutdown Cooling Heat Exchanger (SCHE) is a multi-tube helical coil heat exchanger. It is similar in design to the evaporator/economizer portion of the FSV steam generator. Its function is to cool the reactor whenever the primary cooling system is not available. It is a vertical cross-counter flow heat exchanger. The tubes are made of 2-1/4 Croloy (ASTM A213, T22). The heat is removed by 60°C-pressurized (4.8MPa) water. The SCHE does not have a safety function.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Item tested and qualified	
<b>TRL</b>	6	7	8	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved upon successful completion of final design, fabrication of a full-size prototype SCHE, and the heat transfer and flow resistance characteristics testing identified in the TRL rating sheet for TRL 6.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
Test the SCHE at all possible operating conditions including standby mode and transients. These tests are to be performed at design conditions in a helium environment and will verify the final performance characteristics of the SCHE.	INL CTF	2 years with completion 2 years before NGNP startup testing	5,000	
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Dave Carosella, Bob Schleicher		
<b>Date:</b> 12-9-08	<b>Originating Organization:</b> General Atomics			

4/2/2009 3:19 PM

# Revision 0

## RC2-SSC08-SCHE Technology Roadmap



#### **4.8 RC2-SSC-9 Reactor Cavity Cooling System**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>				
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-9.1	<b>Revision:</b> 0
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Cavity Cooling System (RCCS)</b>				
<b>Description:</b> The RCCS protects the concrete structure surrounding the reactor vessel from overheating during all modes of operation and provides an alternative means from removing reactor core decay heat when neither the PCS nor the SCS is available. The RCCS cooling panels transfer heat from the reactor core to a passive outside air system. The RCCS panels also form a part of the barrier that separates the ambient atmosphere from the reactor cavity atmosphere.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of Concept	Component verified at bench scale	Component verified at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
Sufficient conservative material properties data are available to demonstrate feasibility and to perform the required safety analyses. Natural convection heat transfer, buoyancy-driven flow, friction, and pressure loss are sufficiently understood based on experimental studies of basic phenomena. Expanded data is required to refine the design to include all operational environments anticipated.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
1. Conduct testing to determine the mean and variation of emissivity from one panel to the next. 2. Determine emissivity variation over a large surface. 3. Determine the sensitivity of emissivity to various factors including manufacturing processes, operating service conditions and aging.		Advanced Fuel Research, Inc.	Exp. data 1 yr before start of final design. Overall duration of 15 months.	194
<b>DDN(s) Supported:</b> C.16.00.01			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			John Bolin	
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics			

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-9.2	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Cavity Cooling System (RCCS)</b>			
<b>Description:</b> The RCCS protects the concrete structure surrounding the reactor vessel from overheating during all modes of operation and provides an alternative means from removing reactor core decay heat when neither the PCS nor the SCS is available. The RCCS I/O structure is an above-grade structure that provides atmospheric air flow to and from the RCCS cooling panels.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b> 1.4.3	<b>Parent:</b> 1.4	<b>WBS:</b>	
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Component verified at bench scale	Component verified at experimental scale	Subsystem verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
TRL 5 is achieved upon successful completion of the RCCS panel emissivity testing called for in the TRL rating sheet for TRL 4.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
The technical feasibility of the I/O structure concept has been demonstrated by a variety of similar applications; however, the RCCS outlet design is unique to MHR. No experimental or wind effect data exists for the configuration expected to be used that for the NNGP. Consequently, it is necessary to perform scale-model testing to determine pressure profiles inside and in the vicinity of I/O structure for various locations of the I/O structure along the length of the nuclear Island and for various wind directions and velocities.	Oran W. Nicks Low Speed Wind Tunnel, Texas A&M	Exp. data 1 yr before start of final design. Overall duration 21 months.	400
<b>DDN(s) Supported:</b> C16.00.02		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b> John Bolin			
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-9.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Cavity Cooling System (RCCS)</b>				
<b>Description:</b> The RCCS protects the concrete structure surrounding the reactor vessel from overheating during all modes of operation and provides an alternative means from removing reactor core decay heat when neither the PCS nor the SCS is available. The RCCS cooling panels transfer heat from the reactor core to a passive outside air system. The RCCS panels also form a part of the barrier that separates the ambient atmosphere from the reactor cavity atmosphere.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at experimental scale	Subsystem verified at pilot scale	System verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 6 is achieved when the subsystem testing called for in the TRL rating sheet for TRL 5 has been successfully completed. The next step is to test the complete system at less-than-full scale.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
Perform engineering-scale-model testing to determine overall performance of the RCCS under all expected operating conditions. Determine effect of:  1. Temperature, heat flux, Reynolds number on heat transfer, friction factor data for geometrically similar riser tubes.		NSTF in Bldg 310 at Argonne National Lab	Exp. data before end of first year of final design. Overall duration 24 months.	3,450
<b>DDN(s) Supported:</b> N.16.00.07, C.16.00.03, C.16.00.04			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Bolin		
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics			




<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
<p>Actions:</p> <p>2. Riser internal surface conditions on heat transfer and friction factor data for geometrically similar riser tubes.</p> <p>3. Entry region conditions on heat transfer and friction factor data for geometrically similar riser tubes.</p> <p>4. Buoyancy driven mixing in the high aspect ratio cavity between the vessel and RCCS panels.</p>			

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-9.4	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Cavity Cooling System (RCCS)</b>				
<b>Description:</b> The RCCS protects the concrete structure surrounding the reactor vessel from overheating during all modes of operation and provides an alternative means from removing reactor core decay heat when neither the PCS nor the SCS is available. The RCCS cooling panels transfer heat from the reactor core to a passive outside air system. The RCCS panels also form a part of the barrier that separates the ambient atmosphere from the reactor cavity atmosphere.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Subsystem verified at pilot scale	System verified at engineering scale	System tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
TRL 7 is achieved when RCCS system performance has been demonstrated at less-than-full scale in a relevant environment as called for in the TRL rating sheet for TRL 6 (see document RC2-SSC-9.3). The RCCS will achieve TRL of 8 by virtue of pre-commissioning testing at NGNP.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Perform testing of NGNP RCCS to verify design under all expected operating conditions.		As-built NGNP RCCS	Part of startup testing. Overall duration 24 months.	Part of startup testing.
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		John Bolin		
<b>Date:</b> 12-8-08	<b>Originating Organization:</b> General Atomics			

Revision 0

4/21/2009 11:09 AM



#### **4.9 RC2-SSC-10 Steam Generator**

**Steam Generator, 750°C Inlet Temperature, TRL Rating Sheets TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-10.1.1	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Steam Generator – 750°C Gas Inlet Temperature</b>				
<b>Description:</b> The steam generator (SG) is a multi-tube, helical coil, cross-counter flow helium-to-water/steam heat exchanger similar in design to the FSV SG. In this SG, high-temperature helium @7MPa pressure heats feedwater @ 200°C & 19.5 MPa to 540°C steam @ 17.3MPa. The SG comprises two sections: the lower-temperature Economizer/Evaporator/ Superheater (EES) and the higher-temperature Finishing Superheater. The two sections are connected with a vertical tube section that is about 1 meter long. This vertical section, which is exterior to the main helium flow path, contains a bimetallic weld. A detailed description of the SG can be found in GA document 911120 “NGNP Steam Generator Alternative Study” and in the appropriate GA Test Plan.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of Concept	Demonstrated at bench scale	Demonstrated at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>				
GA has assigned a TRL of 4 to the 750°C SG primarily because (1) the FSV reactor experience has demonstrated the basic helical-coil SG thermal and hydraulic design and the SG material selections, and (2) the considerable level of SG design definition already available from the MHTGR Program. The validation of the helium-side heat transfer coefficients is documented in ASME paper 79-WA/NE-1. The FSV SG, although smaller than the NGNP SG was of the same basic configuration. The THTR heat exchanger was of similar design.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )		Actionee	Schedule	Cost (\$K)
Perform SG conceptual design and analysis. Use computer models to 1) Size the SG for design operating conditions @ 100% heat load, 2) Determine the steady state pressure drop, and 3) Perform structural analyses of the various SG components including the tubes and tube supports. Define the DDNs for the NGNP SG and prepare a design support program plan that outlines the testing required to satisfy the DDNs.		GA	About 1.5 years with completion by end of CD	3000
<b>DDN(s) Supported:</b> None			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			Dave Carosella	
<b>Date:</b> 12-10-08	<b>Originating Organization:</b> General Atomics			

<b>TRL Rating Sheet</b>					
<b>Vendor:</b>	GA	<b>Document Number:</b>	RC2-SSC-10.1.2	<b>Revision:</b>	0
<input type="checkbox"/> Area <input checked="" type="checkbox"/> System <input type="checkbox"/> Subsystem/Structure <input type="checkbox"/> Component <input type="checkbox"/> Technology					
<b>Title: Steam Generator – 750°C Gas Inlet Temperature</b>					
<b>Description:</b>					
The steam generator (SG) is a multi-tube, helical coil, cross-counter flow helium-to-water/steam heat exchanger similar in design to the FSV SG. In this SG, high-temperature helium @7MPa pressure heats feedwater @ 200°C & 19.5 MPa to 540°C steam @ 17.3MPa. The SG comprises two sections: the lower-temperature Economizer/Evaporator/ Superheater (EES) and the higher-temperature Finishing Superheater. The two sections are connected with a vertical tube section that is about 1 meter long. This vertical section, which is exterior to the main helium flow path, contains a bimetallic weld. A detailed description of the SG can be found in GA document 911120 "NNGP Steam Generator Alternative Study" and in the appropriate GA Test Plan.					
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS	<input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>	
<b>Technology Readiness Level</b>					
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level		
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at bench scale	Demonstration at experimental scale	Demonstrated at pilot scale		
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>		
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>					
TRL 5 is achieved when the design and analysis activities defined in the TRL rating sheet for TRL 4 have been successfully completed. Specifically, the conceptual design of the NNGP has been developed, including completion of analyses to size the SG, calculate the pressure drop, and verify the structural design. Additionally, the DDNs for the NNGP SG have been defined and a design support program plan that outlines the testing required to satisfy the DDNs has been prepared.					
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>					
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>	
1) Demonstrate the ability to fabricate the helical coiled tubes.		GA/Vendor/ INL	1 year starting last year of PD	1,250	
<b>DDN(s) Supported:</b> M.13.02.01, M.13.02.02, M.13.02.03, M.13.02.04, M.13.02.07, M.13.02.08, M.13.02.10, M.13.02.11, M.13.02.12, M.13.02.14, M.13.02.15			<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b> Dave Carosella					
<b>Date:</b>	12-14-08	<b>Originating Organization:</b> General Atomics			

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
Actions:			
2) Perform mockup tests to establish lead-in lead-out and transition lead expansion and assembly room.	GA/Vendor	1 year Starting 2 <sup>nd</sup> year of PD	600
3) Select and design the SG tube support system and ware protection devices. Perform testing to assure no unacceptable tube ware due to vibration and/or fretting.	GA/Vendor	1 year Starting 2 <sup>nd</sup> year of PD	2,450
4) Perform testing to assure the ability to assemble the SG bundle using the support system.	GA/Vendor		
5) Perform testing to verify the mechanical and thermal characteristics of the vessel insulation and its cover sheet. Tests must be performed at NGNP design operating conditions.	GA/Vendor	1 Year starting last year of PD	700
6) Perform air-flow testing to determine if vortex shedding and flow separation caused by the tube bundle will damage insulation cover sheets and/or flow shrouds. If damage occurs it will be necessary to design and test protection methods for the cover sheets and/or flow shrouds.	GA/Vendor		780
7) Perform testing to verify the mechanical and corrosion properties of alloy 800H under NGNP design conditions	GA/Test Lab/ INL	3 Years starting at start of CD	15,000
8) Perform testing to verify the mechanical and corrosion properties of alloy 2¼Cr - 1Mo under NGNP design conditions	GA/Test Lab/ INL		
9) Perform testing to verify the mechanical properties of the bimetallic weld under NGNP design conditions.	GA/Test Lab/ INL		
10) Perform an airflow test of the steam generator inlet region to determine extent of flow maldistribution. b) Design and test flow control device to eliminate gas side flow maldistribution.	GA/Test Lab/ INL	1 year Starting 2 <sup>nd</sup> Year of PD	\$1,090
11) Perform flow testing to verify the flow/pressure drop characteristics of the orifice on the secondary side	GA/Test Lab		

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-10.1.3	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Steam Generator – 750°C Gas Inlet Temperature</b>			
<b>Description:</b> The steam generator (SG) is a multi-tube, helical coil, cross-counter flow helium-to-water/steam heat exchanger similar in design to the FSV SG. In this SG, high-temperature helium @7MPa pressure heats feedwater @ 200°C & 19.5 MPa to 540°C steam @ 17.3MPa. The SG comprises two sections: the lower-temperature Economizer/Evaporator/ Superheater (EES) and the higher-temperature Finishing Superheater. The two sections are connected with a vertical tube section that is about 1 meter long. This vertical section, which is exterior to the main helium flow path, contains a bimetallic weld. A detailed description of the SG can be found in GA document 911120 “NNGP Steam Generator Alternative Study” and in the appropriate GA Test Plan.			
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at experimental scale	Demonstrated at pilot scale	Demonstrated at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
TRL 6 is achieved upon successful completion of the required design support testing defined in the TRL rating sheet for TRL 5.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Complete final design and fabricate full-size prototype Steam Generator	GA/SG vendor	4 years starting at beginning of FD	TBD
2. Perform flow testing of full-size prototype SG to verify the heat transfer, pressure drop and vibration characteristics of the SG.	GA/SG vendor	2 years with completion one year before NNGP startup	6,000
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dave Carosella	
<b>Date:</b> 12-14-08	<b>Originating Organization:</b> General Atomics		



<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-10.1.4	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Steam Generator – 750°C Gas Inlet Temperature</b>				
<b>Description:</b> The steam generator (SG) is a multi-tube, helical coil, cross-counter flow helium-to-water/steam heat exchanger similar in design to the FSV SG. In this SG, high-temperature helium @7MPa pressure heats feedwater @ 200°C & 19.5 MPa to 540°C steam @ 17.3MPa. The SG comprises two sections: the lower-temperature Economizer/Evaporator/ Superheater (EES) and the higher-temperature Finishing Superheater. The two sections are connected with a vertical tube section that is about 1 meter long. This vertical section, which is exterior to the main helium flow path, contains a bimetallic weld. A detailed description of the SG can be found in GA document 911120 “NNGP Steam Generator Alternative Study” and in the appropriate GA Test Plan.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Demonstrated at pilot scale	Demonstrated at engineering scale	System tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
TRL 7 is achieved upon successful completion of the air-flow testing of a full size SG to verify the heat transfer, pressure drop and vibration characteristics of the steam SG (as defined in the TRL rating sheet for TRL 6.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
Test the steam generator thermal/hydraulic characteristics in the NNGP helium environment under design conditions including steady state and transient operating conditions.	GA/NNGP operator	1.5 years	TBD	
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Dave Carosella		
<b>Date:</b> 12-14-08	<b>Originating Organization:</b> General Atomics			



#### **4.10 RC2-SSC-12 High Temperature Valves**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-12.1	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: High Temperature Isolation Valves and Pressure Relief Valve</b>				
<b>Description:</b> High temperature isolation valves, located in the steam circuit, enable isolation of the steam generator. Isolation valves are also present on the inlet of the branch to the power turbine, and on the inlet to the reboiler used to produce process steam. The Reactor Pressure Vessel is protected by a high temperature pressure actuated relief valve. Helium temperatures are assumed to be 750-800°C and 300-325°C for the hot and cold legs respectively. 241.4 kg/sec of steam is produced at 541°C and 17.25MPa, consistent with the CoGen plant described in the NNGP PCS alternatives report. The plant life is 60 years. It is also assumed that for isolation valves on the steam generator, there will be three (3) valves on the steam side of each hot and cold leg. These valves will be an integral part of the plant protective system actions for steam loop isolation events. (Reference GA Report 911120/0). Isolation and control valves may be 2 way or 3 way, globe, ball or gate type, Relief valves may be spring or pilot operated. In general, valves may be manual, automatic (remote) or actuated. Valves in some locations may require remote service.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of Principal	Component verified at bench scale	Component verified at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
See attached Basis Sheet				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions</b> ( <i>list all</i> )		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
See Action Sheets				
<b>DDN(s) Supported:</b> N.42.02.01, N.42.02.02			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			David T. Carroccia	
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			

### **Additional Basis Sheet(s)**

Basis for rating:

TRL-4 is assigned to the high temperature valves. Although the relief valve is expected to require more development than the steam isolation valves, it is assigned the same level as the steam valves. Steam isolation and control valves are commercially available in the size range needed with ratings that include the pressure and temperature noted above but material properties in the range necessary are not tabulated in the ASME Code Section III Subsection NH. Valves cannot be rated at TRL-5 because a complete specification for the high temperature high pressure high flow valves does not exist at the current time.

The critical characteristics for which these valves must be designed are not defined for the service conditions at NNGP, particularly, the following must be established:

- ASME Section III Code Acceptance of materials
- Allowable Valve Leakage
- Valve response times required
- Acceptable valve open pressure drop
- Accident excursion temperatures
- Accident excursion pressures
- Valve Configuration
- Actuator type
- Application requirements and mounting location

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1) Establish relevant standards and code applicability (ASME Boiler & pressure vessel Section III Class 1, nuclear, piping, NQA-1, ASME OM-1-2007, ASME OM-2008)	GA/URS-WD	1 year	\$300 to \$350 (not including GA Scope)
a) Establish Safety Class	GA		
2) Determine thermal and mechanical properties of valve materials through coupon tests as needed (to fill gaps in the literature) including: <ul style="list-style-type: none"> <li>- Chemistry</li> <li>- Erosion</li> <li>- Room temperature material properties</li> <li>- Endurance limit analysis</li> <li>- Welds, Cladding</li> <li>- Material corrosion</li> <li>- Stress corrosion cracking, fracture toughness</li> <li>- Elevated temperature properties &amp; fatigue data</li> <li>- Irradiation and post irradiation examination</li> <li>- Environmental exposure/embrittlement</li> <li>- Fasteners, and Seals</li> <li>- Helium permeability</li> <li>- Sliding surface friction</li> <li>- Variation in properties following exposure and aging</li> <li>- Actuator torque requirements</li> <li>- Performance characteristics</li> <li>- Lubrication</li> <li>- Remote Service Requirements</li> <li>- Determine applicability of EPRI PPM</li> </ul>	GA/URS-WD		Material Testing included in above cost estimate
3) Establish conditions of service under normal and design basis event conditions	GA		
4) Valve material stress testing	GA/URS-WD		
5) Material durability tests	GA/URS-WD & Valve Suppliers		
6) Determine performance of gaskets, packing material and seals	GA/URS-WD		
Cont'd			

<p>7) Material Selection and Valve Configuration (Body, Bonnet, Seat, Seal, Stem and Packing)</p> <p>8) 3D modeling and analytical simulation including FEA stress analysis, heat transfer analysis and CFD modeling</p> <p>9) Endurance Limit and Creep Analysis</p> <p>10) Identify Maintenance Requirements, ALARA analysis and RAMI characteristics</p> <p>11) Erosion and corrosion accelerated wear testing, Environmental qualification of valve materials, He leak tightness &amp; Weld Methods, Dissimilar Materials and Differential Thermal Expansion</p> <p>12) Interfaces with adjoining structures, piping. Insulation, installation, maintenance access, contamination control</p>	<p>GA/URS-WD</p> <p>GA/URS-WD</p> <p>GA/URS-WD, SME</p> <p>GA/URS-WD,</p> <p>GA/URS-WD</p> <p>GA/URS-WD</p>	<p>1.5year</p>	<p>\$300 to \$600k (not including GA Scope)</p> <p>Simulations, tests and analysis included in above cost estimate</p>
---	---	----------------	--

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-12.2	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: High Temperature Isolation Valves and Pressure Relief Valve</b>			
<b>Description:</b> High temperature isolation valves, located in the steam circuit, enable isolation of the steam generator. Isolation valves are also present on the inlet of the branch to the power turbine, and on the inlet to the reboiler used to produce process steam. The Reactor Pressure Vessel is protected by a high temperature pressure actuated relief valve. Helium temperatures are assumed to be 750-800°C and 300-325°C for the hot and cold legs respectively. 241.4 kg/sec of steam is produced at 541°C and 17.25MPa, consistent with the CoGen plant described in the NNGP PCS alternatives report. The plant life is 60 years. It is also assumed that for isolation valves on the steam generator, there will be three (3) valves on the steam side of each hot and cold leg. These valves will be an integral part of the plant protective system actions for steam loop isolation events. (Reference GA Report 911120/0). Isolation and control valves may be 2 way or 3 way, globe, ball or gate type, Relief valves may be spring or pilot operated. In general, valves may be manual, automatic (remote) or actuated. Valves in some locations may require remote service.			
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Component verified at bench scale	Component verified at experimental scale	Component verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>			
A TRL-5 is achieved upon successful completion of the action items identified in the TRL rating sheet for TRL-4. A complete specification for the high temperature, high pressure, high flow valves exists when TRL-5 is achieved.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1) Physical Test Preparation for Pilot Scale Test Articles which are representative of valve designs	GA/URS-WD	1 year	400 - 450
2) Tests using test apparatus	GA/URS-WD		
3) Determination of applicable NDE methods	GA/URS-WD		
4) Verify 3D (scale) models based on test results	GA/URS-WD		
5) Determine Leak Rate Detection Method Validation	GA/URS-WD		
<b>DDN(s) Supported:</b> N.42.02.01, N.42.02.02		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		David T. Carroccia	
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS		



<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-12.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: High Temperature Isolation Valves and Pressure Relief Valve</b>				
<b>Description:</b> High temperature isolation valves, located in the steam circuit, enable isolation of the steam generator. Isolation valves are also present on the inlet of the branch to the power turbine, and on the inlet to the reboiler used to produce process steam. The Reactor Pressure Vessel is protected by a high temperature pressure actuated relief valve. Helium temperatures are assumed to be 750-800°C and 300-325°C for the hot and cold legs respectively. 241.4 kg/sec of steam is produced at 541°C and 17.25MPa, consistent with the CoGen plant described in the NGNP PCS alternatives report. The plant life is 60 years. It is also assumed that for isolation valves on the steam generator, there will be three (3) valves on the steam side of each hot and cold leg. These valves will be an integral part of the plant protective system actions for steam loop isolation events. (Reference GA Report 911120/0). Isolation and control valves may be 2 way or 3 way, globe, ball or gate type, Relief valves may be spring or pilot operated. In general, valves may be manual, automatic (remote) or actuated. Valves in some locations may require remote service.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
Technology Readiness Level				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at experimental scale	Component verified at pilot scale	Component verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 6 is achieved upon successful completion of the action items identified in the TRL rating sheet for TRL 5.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)	
1) Valve design verification including valve body, bonnet, plug, seal, packing, insulation, ball and seat, stem, bellows, jacket and actuator (as equipped)	GA/URS-WD	1 year	750 - 800	
2) Integrated experimental scale model testing including relief valve and isolation valve (Cont.)				
<b>DDN(s) Supported:</b> N.42.02.01, N.42.02.02		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		David T. Carroccia		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			

<b>Additional Action Sheet(s)</b>			
<b>Actions</b> <i>(list all)</i>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
3) CFD/FEA validation and optimization	GA/URS-WD		Included above
4) Leak detection validation	GA/URS-WD		
5) Validate installation, inspection and maintenance techniques	GA/URS-WD		
6) Assess test plan results and perform risk based analysis on need for next level of testing	GA/URS-WD		

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-12.4	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: High Temperature Isolation Valves and Pressure Relief Valve</b>				
<b>Description:</b> High temperature isolation valves, located in the steam circuit, enable isolation of the steam generator. Isolation valves are also present on the inlet of the branch to the power turbine, and on the inlet to the reboiler used to produce process steam. The Reactor Pressure Vessel is protected by a high temperature pressure actuated relief valve. Helium temperatures are assumed to be 750-800°C and 300-325°C for the hot and cold legs respectively. 241.4 kg/sec of steam is produced at 541°C and 17.25MPa, consistent with the CoGen plant described in the NNGP PCS alternatives report. The plant life is 60 years. It is also assumed that for isolation valves on the steam generator, there will be three (3) valves on the steam side of each hot and cold leg. These valves will be an integral part of the plant protective system actions for steam loop isolation events. (Reference GA Report 911120/0). Isolation and control valves may be 2 way or 3 way, globe, ball or gate type, Relief valves may be spring or pilot operated. In general, valves may be manual, automatic (remote) or actuated. Valves in some locations may require remote service.				
<b>Area:</b>	<input type="checkbox"/> NHSS	<input checked="" type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Component verified at pilot scale	Component verified at engineering scale	Component tested and qualified	
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>	
Basis for Rating <span style="float: right;">(Check box if continued on additional sheets) <input type="checkbox"/></span>				
A TRL of 7 is achieved upon successful completion of the action items identified in the TRL rating sheet for TRL 6. Risk based determination has been made at the previous level whether sufficient need exists to proceed to this level of testing.				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1) Integrated CTF Testing (as part of a larger test effort)		GA/URS-WD /INL	2 years coordinated with other activities at CTF)	750 – 950 Not including GA,INL/BEA scope
2) Stress Analysis Validation by prescribed mechanical loading and strain gage measurements		GA/URS-WD		
3) Temperature and Flow Analysis Validation		GA/URS-WD		
4) In-Service Inspection Techniques Validation		GA/URS-WD		
<b>DDN(s) Supported:</b> N.42.02.01, N.42.02.02		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		David T. Carroccia		
<b>Date:</b> 4-27-09	<b>Originating Organization:</b> Washington Division of URS			



#### **4.11 RC2-SSC-14 Fuel Handling and Storage System**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-14.1	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Fuel Handling and Storage System (FHSS)</b>				
<b>Description:</b> The FHSS is used to refuel the reactor and for all transfers of fuel and reflector elements between the reactor and local storage facilities and between the local storage facilities and the packaging and shipping facility. The system is also used to manipulate special tools for in-service inspection of reactor components. The major fuel handling and storage components (subsystems) include the fuel handling machine (FHM), the fuel transfer cask (FTC), the fuel handling equipment positioner (FHEP), the fuel handling equipment support structure (FHSS), the element hoist and grapple assembly (EHGA) in the local fuel storage facility, and the fuel sealing and inspection facility (FSIF). (Cont.)				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>		<b>WBS:</b>
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of Concept	Components verified at bench scale	Components verified at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
A large experience base exists from designing, building, testing and operating fuel handling equipment for the Peach Bottom and Fort St. Vrain (FSV) reactors. Although the Peach Bottom fuel handling machine was manually operated, important technology was developed in the areas of: (1) electrical power and signal cables for operation in 450°F helium with high gamma background; (2) lubricants for use in the same harsh environment; (3) electronic sensors for use on the grapple head; (4) grapple head floating plate technology for light touch in horizontal and vertical directions; and (5) general purpose manipulator technology adapted for special use in the reactor. (Cont.)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Conduct conceptual design of the FHSS components. The design effort will include a review of the current designs (developed in the early 1990's) and the current state of relevant technologies to ascertain the need for design changes to utilize current technology. Design improvements will be made based on the results of this review.		GA	18 months starting at the beginning of NGNP CD	1,900
<b>DDN(s) Supported:</b> C.21.01.04, C.21.01.07, C.21.01.08			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein		
<b>Date:</b> 11-29-08	<b>Originating Organization:</b> General Atomics			

## Additional Description Sheet(s)

### Description:

In-core fuel handling is performed by the FHM and the FTC working together. The functions of the various major FHSS components are summarized below:

- The FHM is a shielded, gas tight structure containing all the necessary mechanisms required to transfer fuel and reflector elements between the reactor core and the upper plenum
- The FTC is a shielded structure which transfers fuel and reflector elements between the fuel handling machine (inside the upper plenum) , and the FSIF and/or the Local Refueling and Storage Facilities (LRSF)
- The FHSS receives and supports fuel handling equipment over the reactor vessel during refueling
- The FHEP transfers and positions the FHM, FTC, FHSS, and auxiliary service cask between storage locations, reactor vessel and fuel/target processing facilities floor valves
- The EHGA robot is a remotely operated bridge robot in the LRSFs and FSIF which handle core elements, well plugs, and fuel elements
- The FSIF equipment loads spent fuel elements into shipping containers, seals the container lid, and inspects the resulting container integrity.

Operation of the FHSS is a key factor contributing to plant availability. The system must be highly reliable with sufficient redundancy to accommodate upset conditions and equipment failures. The equipment must minimize complexity and be readily maintainable, recognizing that it operates in a radioactive environment. These are all important requirements that require a comprehensive confirmation and endurance test program. The FHSS provides radiation protection to workers and public during refueling operations. The reactor containment is opened for refueling and the refueling equipment must be securely fastened and sealed to the pressure vessel. The equipment is designed to appropriate seismic requirements to maintain integrity with the reactor pressure vessel. Leakage of primary coolant from the reactor is prevented by maintaining the interior pressure slightly below atmospheric. In addition, the equipment is sealed to the reactor with elastomeric seals. In the event of upset conditions, such as an interior water leak, the equipment and seals are designed for the maximum pressure rise (approximately plus 25 psig). Machine controls and fail safe mechanisms are provided for the handling of fuel elements. Mislocating blocks, dropping or damaging blocks, or runaway machinery, etc., are concerns.

### Additional Basis Sheet(s)

**Basis:**

The FSV FHM was designed and built in the late 1960's during the time that programmed machine tools were being developed for numerical control. This machine advanced from the Peach Bottom 1 technology in areas of: (1) computer control of multiple positioning systems in automatic mode or direct operator control in manual operation mode; (2) the use of electric motors, brakes, and position feedback instrumentation in a helium environment; (3) The use of a radiation-hardened television camera and lighting in helium; (4) programming techniques to safely operate the FHM within limits set by hard-wired interlocks and, (5) elementary inventory control, which was greatly enhanced in a 1989 control system upgrade.

The current design for the FHSS has evolved from the FSV technology. Years of experience with the FSV FHM have demonstrated both reliable features of the design and some features which could be improved. The current FHM design is based on the FSV FHM, but includes some mechanisms that differ from the FSV FHM:

- Shorter grapple probe
- Electrically controlled grapple mechanism rather than pneumatic
- Electrically controlled grapple head mechanism rather than pneumatic
- Increased handling mechanism linkage radial displacement
- Viewing system and electronic control system revised to incorporate more current technology
- Telescoping tube guide sleeve is transported and inserted by the FHM rather than an auxiliary service cask
- Vertical travel requirement is greater in order to operate in a deeper core

The FHSS also includes several new automated machines that must operate in concert. The simultaneous operation of these machines is necessary to refuel a reactor module within the allocated time.

The FTC and the EHGA robot are new designs required to operate in a helium environment. These machines incorporate proven technology where applicable. For example, the FTC will use grapple head, telescopic guide tubes, and isolation valve designs similar to those used in the FHM. The FHEP is similar to a commercially available, computer operated gantry crane with position control of the x, y, z, and load rotation axes. The EHGA robot and its end effectors are similar to the gantry robots applied by GA in the U.S. Army chemical weapons demilitarization development program. GA has developed the robotics for the remote handling of munitions in a lethal agent environment. The particular relevant expertise gained and "lessons learned" in the design, use and control of multiple gantry robots, end-effectors, and decontamination compatible hardware is available and applicable to the gantry robots to be used in the LRSFs and the FSIF. The computer control and element accountability system will utilize background data derived from the FSV project, commercial HTGR designs, the GA Demil program and industrial applications of computer controlled equipment. The FSV and Demil projects provide tested data bases for the FHSS computer architecture which include automated serialized accounting of fuel elements and target assemblies.

The baseline TRL assigned to the FHSS is 4 based on (1) the lowest TRL for the subsystems that comprise the FHSS and (2) the need to conduct tests to confirm the performance and environmental compatibility of instrumentation and control components and systems, and to firm up their design prior to overall system development and verification. A TRL of 4 is assigned to both the FHESS and the FSIF for the reasons given below. A TRL of 5 is assigned to the other FHSS subsystems based on the state of the technology as discussed above.

The FHESS with its multiple interfaces (i.e., the reactor isolation valves and neutron control assembly housing seals) is a first-of-a-kind unit. Although design of the FHESS is a routine structural task based on loads, deflections, and stability of the structure, consideration must also be given to the radiation shielding needed to prevent unnecessary personnel radiation exposure. Adequate vendor documentation is expected to be available for the seals and valves to warrant a TRL of 4, but testing is needed to validate the performance of these components.



Little design information is currently available for the FSIF and the equipment will be first-of-a-kind; however, the fuel handling and packaging mechanisms and procedures used in this facility will be based on those employed in FSV and in other HTGRs. Further, as noted above, the relevant expertise gained and "lessons learned" in the design, use, and control of multiple gantry robots, end-effectors, and decontamination compatible hardware is available and applicable to the gantry robots to be used in the FSIF. Thus, an initial TRL of 4 is judged appropriate for this FHSS subsystem.

It is also important to note that the conceptual designs of the current FHSS components were developed in the early 1990's and were based on the technology available at that time. Further, the "technology development" activities defined for the FHSS in the technology development road map (TDRM) and supporting TRL rating sheets are primarily design verification tests. Thus, an important first step in NNGP FHSS technology development will be to review the current designs of the FHSS components and ascertain the extent to which previous design selections should be updated based on new technologies that have become available since the current designs were developed. It is not anticipated that any new technology will be need to be developed for the FHSS components; rather it is a matter of ensuring optimal utilization of currently available technology, particularly in the area of FHSS I&C.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Perform a survey of the supply network for the types of equipment required for the NFSS and select vendors for the various components.	GA	6 months starting upon completion of action 1	350
3. Complete preliminary design of the FHSS	GA, FHSS component vendors	18 months starting at beginning of PD	3000
4. Perform testing as necessary to verify the accuracy and reliability of the instrumentation and control components under a variety of operating conditions and after frequent use. Test the fuel element identification equipment under a range of operating conditions including element motion, velocity, size of identification markings, lighting conditions, etc. Test other instrumentation under various operating speeds and environmental conditions to verify performance characteristics.	FHSS I&C vendor(s)	9 months starting at beginning of FD	900
5. Perform testing to demonstrate proper operation of the FHSS with its four built-in reactor isolation valves and inflatable seals. Test the inflatable seals that seat to the nuclear control assembly housings against offset (non-concentric) housing locations to simulate expected plant construction tolerances. Cycle valve operators and all seals to represent 10 refueling outages and demonstrate all interlocks. All testing will be conducted in ambient air.	FHSS vendor	1 year starting at beginning of FD	600
6. Perform tests of FSIF components to verify the automated packaging, sealing, and inspection processes (including leak-tightness testing capabilities).	FSIF component vendors	1 year starting at beginning of FD	900

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-14.2	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Fuel Handling and Storage System (FHSS)</b>			
<b>Description:</b> The FHSS is used to refuel the reactor and for all transfers of fuel and reflector elements between the reactor and local storage facilities and between the local storage facilities and the packaging and shipping facility. The system is also used to manipulate special tools for in-service inspection of reactor components. The major fuel handling and storage components (subsystems) include the fuel handling machine (FHM), the fuel transfer cask (FTC), the fuel handling equipment positioner (FHEP), the fuel handling equipment support structure (FHSS), the element hoist and grapple assembly (EHGA) in the local fuel storage facility, and the fuel sealing and inspection facility (FSIF). In-core fuel handling is performed by the FHM and the FTC working together. These machines are positioned by the FHEP and are mounted on the FHSS, which is mounted on the reactor vessel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Components verified at bench scale	Components verified at experimental scale	Subsystems verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
A TRL of 5 for the FHSS is achieved upon completion of the required component level testing for the FHSS and the FSIF. The tests on the FHSS seals and valves have qualified the materials used for these components and have verified the functionality and endurance of these components.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Perform speed, accuracy, and extended cyclic endurance and structural testing of the FHEP to verify the design and to ensure the reliability and accuracy of the FHEP to retrieve, transport and place large, heavy machines and structures. The testing shall include measurement of the four-axis acceleration and velocity capabilities of the FHEP under static and dynamic load conditions to acquire the data needed to validate process speed and performance predictions. (Cont.)	GA and FHEP vendor	18 months staring at beginning of FD	1900
<b>DDN(s) Supported:</b> C.21.01.01, C.21.01.02, C.21.01.03, C.21.01.06		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein	
<b>Date:</b> 11-29-08	<b>Originating Organization:</b> General Atomics		

### Additional Basis Sheet(s)

Basis:

Experimental-scale testing of the FSIF components has verified the automated packaging, sealing, and inspection processes to be used in this subsystem. Testing of the FHSS instrumentation and control (I&C) components in air and in helium has demonstrated the performance and environmental compatibility of these components and has demonstrated that the I&C, including software, meets design requirements and is compatible with the fuel handling mechanisms used in the FHSS.

### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
The safety interlocks of the FHEP control system will be validated in the course of these tests.			
2. Perform EHGA robot testing to validate that material handling operations for all fuel element related tasks are done within the cycle time allocation. Predicted recovery tasks will be functionally tested. Environmental endurance testing in both air and helium will be performed.	GA and EHGA vendor	18 months starting at beginning of FD	850
3. Perform full-scale rig test to acquire data for FHM on functional and performance limits in anticipated operating modes and operating conditions: Phase 1: Automated checkout of grapple head Phase 2: Automated checkout of element transfer mechanisms over a full core sector Phase 3: Automated cycle test in 250°F helium	GA and FHM vendor	18 months starting at beginning of FD	1250
4. Use a full-scale test rig and test article to conduct tests in air (Phase 1) and helium (Phase 2) to establish the operability and reliability of the FTC and its components under expected environmental conditions. Key components include the vertical drive system for the hoist grapple, horizontal transfer table drive, and the complete grapple system. Test Phase 3 will be a separate cyclic test of the automated hold-downs and remote connections.	GA and FTC vendor	18 months starting at beginning of FD	1250
5. Complete final design of the FHSS based on the results of all component testing. Issue final procurement specifications for all equipment.	GA	2 years starting 18 months into FD	1500

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-14.3	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Fuel Handling and Storage System (FHSS)</b>			
<b>Description:</b> The FHSS is used to refuel the reactor and for all transfers of fuel and reflector elements between the reactor and local storage facilities and between the local storage facilities and the packaging and shipping facility. The system is also used to manipulate special tools for in-service inspection of reactor components. The major fuel handling and storage components (subsystems) include the fuel handling machine (FHM), the fuel transfer cask (FTC), the fuel handling equipment positioner (FHEP), the fuel handling equipment support structure (FHSS), the element hoist and grapple assembly (EHGA) in the local fuel storage facility, and the fuel sealing and inspection facility (FSIF). In-core fuel handling is performed by the FHM and the FTC working together. These machines are positioned by the FHEP and are mounted on the FHSS, which is mounted on the reactor vessel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Components verified at experimental scale	Subsystems verified at pilot scale	System verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
A TRL of 6 is achieved upon completion of all design verification testing of the FHSS subsystems including the FHM, FTC, FHEP, FHSS, EHGA, and the FSIP and either (1) the results of the tests confirm that the subsystems meet all functional and operational requirements or (2) design modifications have been made to the final design to correct any deficiencies detected during testing.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
Perform an integrated test of the FHSS to verify that all components of the system function together and that system operations can be performed safely and reliably within the allocated time. The testing will involve full-scale fuel handling and control equipment with simulated fuel elements in an environment representative of the operational environment.	GA, component vendors, and testing organization	2.5 years with completion at least 6 months before installation of equipment at NGNP	6000
<b>DDN(s) Supported:</b> C.21.01.05		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein	
<b>Date:</b> 11-29-08	<b>Originating Organization:</b> General Atomics		

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-14.4	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input checked="" type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Fuel Handling and Storage System (FHSS)</b>			
<b>Description:</b> The FHSS is used to refuel the reactor and for all transfers of fuel and reflector elements between the reactor and local storage facilities and between the local storage facilities and the packaging and shipping facility. The system is also used to manipulate special tools for in-service inspection of reactor components. The major fuel handling and storage components (subsystems) include the fuel handling machine (FHM), the fuel transfer cask (FTC), the fuel handling equipment positioner (FHEP), the fuel handling equipment support structure (FHSS), the element hoist and grapple assembly (EHGA) in the local fuel storage facility, and the fuel sealing and inspection facility (FSIF). In-core fuel handling is performed by the FHM and the FTC working together. These machines are positioned by the FHEP and are mounted on the FHSS, which is mounted on the reactor vessel.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Subsystems verified at pilot scale	System verified at engineering scale	System tested and qualified
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>
Basis for Rating (Check box if continued on additional sheets) <input type="checkbox"/>			
A TRL of 7 is achieved when the following conditions are satisfied: (1) The integrated system test with simulated fuel elements in an environment representative of the operating environment, and (2) The results of the integrated system test demonstrate that all of the subsystems function together and that the FHSS is capable of performing all required operations safely and reliably in the allocated time.			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
Conduct the appropriate number and duration of fuel handling operations in the actual operating environment (i.e., in the NGNP) to verify that the system meets reliability requirements.	GA, NGNP operator	During NGNP startup testing	TBD
<b>DDN(s) Supported:</b> None		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		John Saurwein	
<b>Date:</b> 11-29-08	<b>Originating Organization:</b> General Atomics		



#### **4.12 RC2-SSC-15 Primary Circuit and Balance of Plant Instrumentation**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**



<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-15.1	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Primary Circuit and Balance of Plant Instrumentation</b>				
<b>Description:</b> This SSC contains instrumentation equipment associated with the primary circuit and the balance of plant instrumentation, which will be placed in the primary helium circuit to detect leakage of radioactive materials, potentially affecting the public or plant personnel, and other instrumentation to provide defense-in-depth protection of reactor cooling functions. Instrumentation outside the reactor, but within the primary circuit or at particular points near the primary circuit boundary is considered Primary Circuit instrumentation. The Primary Circuit instrumentation provides detection of primary coolant leakage through measurement of pressure, temperature or radiation levels within the Reactor Building or in helium-to-helium heat exchanger piping which penetrates the Reactor Building. (Cont.)				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS
	<input type="checkbox"/> BOP			
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Application Formulated	Proof of Concept	Verified at Bench Scale	
<b>TRL</b>	<b>2</b>	<b>3</b>	<b>4</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
The level 3 technical rating for this SSC is based on experience gained at the Fort St. Vrain nuclear generating station, using similar instrumentation for reactor control and protection. DDNs exist to verify these methods for the later MHR designs. Before a bench-scale rating level can be achieved, calculations to verify the preliminary control/protection requirements for NNGP multi-function plant operation must be completed. (Cont)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. From preliminary Reactor Building design information, select leak detection instrumentation locations in the Reactor Building facilities. Provide bench scale calculations to correlate leak magnitude and pressure/temperature changes in the Reactor Building. (Cont.)		GA	CD 0-12mo	20
<b>DDN(s) Supported:</b> C.31.01.01, C.34.01.02			<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>			Dale Pfremer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics			

### Additional Description Sheet (s)

Description:

Also, it includes moisture monitoring and pressure instrumentation for steam leakage detection, operator information, and as a protection-logic, reactor-trip parameter. Furthermore, this SSC includes plateout instrumentation to monitor and ascertain the level of radioactive plateout within the primary circuit as well. Helium flow-rate measurement is also included. Finally, Balance-of-Plant (BOP) measurements, comprised of steam flow rate, temperature, and pressure instrumentation contained in the steam-electric (BOP) equipment, complete the instrumentation group.

### Additional Basis Sheet(s)

Basis:

This will provide a basis for later design efforts such as determination of helium flow measurement range and accuracy. Also, since available US gas-reactor operating experience is outdated, testing or other means of updating the database is required to achieve the level 4 rating that would precede the conceptual design of some of the instrumentation methods. This includes confirming application of instrumentation used outside the nuclear industry, or confirming application of instrumentation used in other high-temperature reactor development work, such as work in Japan, etc. Industrial proof-of-concept data can also improve and provide new bases for design of more modern instrumentation – for example, application of laser technology to moisture detection devices has come about since FSV. This instrumentation will undergo development and requires the technical rating process for application in the NNGP.

Helium flow rate measuring instrumentation, although not within the reactor design scope, is controlled and monitored through the reactor control and protection interfaces, and is included as part of the isolation valve equipment. Pressure probes, piping and temperature sensors, located within the helium circulators, provide the helium flow rate instrumentation. Because of the integrated nature of this instrumentation, it must be included in the circulator design scope, with operational requirements derived through reactor control and protection requirements. This instrumentation is developed with the circulator design and will require verification of the development effort.

Reactor control/protection systems also use measurements comprised of steam flow rate, temperature, and pressure instrumentation contained in the steam-electric (BOP) equipment to coordinate nuclear control and electric-plant output, as well as to detect impairment of normal reactor heat rejection processes — ultimately using this information to determine if a reactor trip is required. For instance, the steam-turbine-trip parameter will be monitored by the reactor trip decision logic. This instrumentation is well established in nuclear electric plants, and so will not require verification prior to level 7.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Obtain available bench scale data applicable for Primary Circuit radiation detection instrumentation and confirm, by test or analysis, capability to detect leaks through radiological measurements. Determine most likely means of placing such instrumentation in the primary circuit and provide bench-scale test verification of potential mounting schemes.	GA	CD 0-12mo	50
3. Verify bench scale instrumentation supplier data, and confirm that leakage, which could escape into the environment or endanger plant personnel if allowed to exceed specified levels, can be detected well below levels specified in RPS and IPS conceptual design documentation. Provide range and accuracy for instrumentation data base.	GA	CD 0-12mo	50
4. Contact circulator design team and verify incorporation of Helium Mass Flow Measurement in Circulator development effort. The circulator integrated instrumentation may also include safety-related primary helium temperature and pressure measurements.	GA Howden	CD 0-12mo CD 0-12mo	20 20
5. Provide bench-scale calculations for Plateout Probe instrumentation to determine fission product deposition levels. Acquire available plate-out technology information, such as OGL-1 plate-out measurement techniques, etc. Update planning for post-level-4 testing.	GA	CD 0-12mo	20
6. Include Steam Generator Moisture Ingress Detection Sensors in the bench scale verification effort. Survey and select from available commercial moisture monitoring equipment and perform tests to verify application of equipment to moisture detection design. Include new commercial technology such as Cavity Ring-Down Spectroscopy (CRDS) in evaluation. Update planning for post-level-4 testing.	GA Vendor	CD 0-12mo CD 0-12mo	50 20
7. Verify preliminary range, sensor accuracy, response, etc. for reactor control and protection instrumentation located in BOP. Include steam temperature, pressure and flow measurements. Perform bench scale reactor control, transient calculations. Update instrumentation reliability data from available nuclear-electric plant database. Include measurement redundancy, sensor fail-over techniques, signal transmission quality, etc.	GA	CD 0-12mo	50

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-15.2	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Primary Circuit and Balance of Plant Instrumentation</b>				
<b>Description:</b> This SSC contains instrumentation associated with the primary circuit and the balance of plant. Some of the instrumentation will be placed in the primary helium circuit or reactor building to detect leakage of radioactive materials, potentially affecting the public or plant personnel. Balance-of-Plant (BOP) measurements, comprised of steam flow rate, temperature, pressure, etc provide defense-in-depth protection of reactor cooling functions. Instrumentation within the primary circuit or included in the secondary boundary provided by the Reactor Building, is considered Primary Circuit instrumentation. (Cont.)				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS
				<input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at experimental scale	
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
The current level 4 technical rating for this SSC is based on completion of activities required to achieve a level 4 technical rating. These activities provided a bench scale assessment of primary circuit and balance of plant instrumentation for the proposed NNGP design. Available commercial instrumentation and instrumentation used in earlier nuclear plants was reviewed. This provides information to start conceptual design activities. (Cont.)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>	
1. Complete NHSS conceptual instrumentation design and coordinate with interfacing design areas – Reactor Building, BOP, etc. Provide preliminary views of each installed system and operational requirements for radiation detection, pressure, temperature, etc. measurement. Document design issues. (cont)	GA	CD 12-36mo	300	
<b>DDN(s) Supported:</b> C.31.01.01, C.34.01.02		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremer		
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics			

### **Additional Description Sheet(s)**

**Description:**

The instrumentation developed in this SSC provides detection of primary coolant leakage through measurement of pressure, temperature or radiation levels within the Reactor Building or in helium piping which penetrates the Reactor Building. Further it includes moisture monitoring and pressure instrumentation to detect steam in-leakage, provide operator information, and as a protection-logic input to the reactor-trip function. It also includes helium flow rate instrumentation and radioactive plateout monitoring instrumentation.

### **Additional Basis Sheet(s)**

**Basis:**

Achievement of the level 5 rating will require conceptual design selections from the available devices. Critical components within the instrumentation assemblies will be determined and testing at the component level will be performed. Industrial proof-of-concept data, provided by vendors, will also be reviewed to determine if further testing or other means of updating the database is required to achieve the level 5 rating. It is expected that most of this type of testing will involve advanced instrumentation systems, such as the moisture monitoring and plateout probe systems.

Conceptual design activities will also provide a range of plant operations, and analysis, to determine the helium flow rate measuring system requirements. These will be provided to the circulator development team, since pressure probes, piping and temperature sensors, etc located within the helium circulators, provides the helium flow rate instrumentation. Although not within the reactor design scope, helium flow rate is controlled and monitored through the reactor control and protection interfaces. Specification of requirements for this instrumentation is included under this SSC equipment design activities. However, all testing activities will be completed under the circulator development scope.

Reactor control/protection analysis during conceptual design will also provide measurement requirements for steam-electric (BOP) equipment, such as steam flow rate, temperature, and pressure instrumentation. The effort will coordinate nuclear control and BOP electric-plant design requirements. This instrumentation is well established in nuclear electric plants, and so will not require verification testing, other than that provided in BOP development activities.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Determine potential suppliers of Steam Generator Moisture Ingress Detection Sensors, based on selection from available commercial moisture monitoring equipment. Specify experimental scale tests to verify components of equipment for moisture detection design. Refer to uncertainties in industrial proof-of-concept data provided by vendors or other uncertainties requiring updates to the available database. Further testing is required in these cases.	GA	CD 12-24mo	50
	Vendor	CD 12-24mo	50
3. Determine potential suppliers for Plateout Probe instrumentation to determine fission product deposition levels. Determine experimental scale testing to verify NNGP application.	GA	CD 12-24mo	50
	Facility	CD 12-24mo	50
4. Complete testing (2) and (3) above. Verify application of components tested, and document resolution of design issues determined through test results. Resolve by analysis or other means, all design issues which do not require testing. Document results to confirm level 5 technical rating. Provide recommendation for testing at the next technical level.	GA	CD 24-36mo	100

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-15.3	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Primary Circuit and Balance of Plant Instrumentation</b>			
<b>Description:</b> This SSC contains instrumentation associated with the primary circuit and the balance of plant. Some of the instrumentation will be placed in the primary helium circuit or reactor building to detect leakage of radioactive materials, potentially affecting the public or plant personnel. Balance-of-Plant (BOP) measurements, comprised of steam flow rate, temperature, pressure, etc provide defense-in-depth protection of reactor cooling functions. Instrumentation within the primary circuit or included in the secondary boundary provided by the Reactor Building, is considered Primary Circuit instrumentation. (Cont.)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at bench scale	Verified at experimental scale	Verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The current level 5 technical rating for this SSC is based on completion of activities required to achieve a level 5 technical rating. These activities provided component testing of new instrumentation required in NNGP, and analytical assessment supporting design application of the conventional instrumentation contained in the primary circuit and balance of plant. This provides information to start preliminary design activities. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b> <b>Cost (\$K)</b>
1. Complete preliminary final instrumentation design and coordinate with interfacing design areas – Reactor Building, BOP, etc. Provide preliminary views of each installed system to confirm instrumentation installation points and verify operating conditions. Document design issues. (cont)		GA	FD 0-42mo 500
<b>DDN(s) Supported:</b> C.31.01.01, C.34.01.02		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		

### **Additional Description Sheet(s)**

**Description:**

The instrumentation developed in this SSC provides detection of primary coolant leakage through measurement of pressure, temperature or radiation levels within the Reactor Building or in helium piping which penetrates the Reactor Building. It includes moisture monitoring and pressure instrumentation to detect steam in-leakage, provide operator information, and as a protection-logic input to the reactor-trip function. Lastly, it also includes helium flow rate instrumentation and radioactive plateout monitoring instrumentation.

### **Additional Basis Sheet(s)**

**Basis:**

Subsystem testing will be determined by review of vendor development efforts. If subsystem testing is necessary, this type of testing is only expected for advanced instrumentation systems, such as the moisture monitoring and plateout probe systems. No subsystem testing is expected for the conventional instrumentation contained in the primary circuit and balance of plant. Achievement of the level 6 technical rating will be provided by analytical confirmation for this type of instrumentation.

Likewise, coordination with the circulator development team will determine the need for helium flow rate instrumentation testing. If necessary, this testing will be accomplished with other circulator subsystem testing, and will be conducted under the circulator development scope. It is likely that seismic testing of the helium flow rate measurement system will be more convenient if performed at the subsystem level.

This SSC will review nuclear control and electric-plant instrumentation development, but will require no testing to advance to a level 6 technical rating.



<b>Additional Action Sheet(s)</b>			
<b>Actions</b> ( <i>list all</i> )	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Review vendor development of Steam Generator Moisture Ingress Detection Sensors and Plateout Probe instrumentation. Specify necessary subsystem testing, complete tests, and verify results. (No subsystem testing expected.) Advance analytical results to confirm level 6 technical rating.	GA	FD 0-36mo	40
	Vendor	FD 36-42mo	200
	Facility	FD 36-42mo	160
3. Review circulator subsystem testing activities to determine that helium flow measurement system is satisfactory to confirm the level 6 technical rating. Repeat or add testing, including seismic testing, if necessary. Provide supporting analysis. Document results to support verification of reactor flow rate measurement for the safety-related protection system.	GA	FD 0-36mo	10
	Howden	FD 36-42mo	20
4. Review BOP electric-plant instrumentation development to verify accuracy, range, time of response, etc of BOP temperature, pressure, flow rate, etc. instrumentation. Provide supporting analysis and document results to verify reactor control capabilities and confirm ability of PCDIS to accomplish required actions following a reactor trip.	GA	FD 0-42mo	50
	BOP	FD 0-42mo	20

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-15.4	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Primary Circuit and Balance of Plant Instrumentation</b>			
<b>Description:</b> This SSC contains instrumentation associated with the primary circuit and the balance of plant. Some of the instrumentation will be placed in the primary helium circuit or reactor building to detect leakage of radioactive materials, potentially affecting the public or plant personnel. Balance-of-Plant (BOP) measurements, comprised of steam flow rate, temperature, pressure, etc provide defense-in-depth protection of reactor cooling functions. Instrumentation within the primary circuit or included in the secondary boundary provided by the Reactor Building, is considered Primary Circuit instrumentation. (Cont.)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The current level 6 technical rating for this SSC is based on completion of activities required to achieve a level 6 technical rating. These activities determined specific subsystem testing or, as an alternative, provided analytical confirmation of the technical level of the instrumentation. This provided information to complete the final design and perform any necessary system level instrumentation testing. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Complete final design. Issue final P&ID drawings for Primary Circuit and Balance of Plant Instrumentation. Coordinate with interfacing design areas – Reactor Building, BOP, etc. to verify pre-installation acceptance test planning and documentation to be completed. (Cont.)	GA	FD 42-84mo	300
<b>DDN(s) Supported:</b> C.31.01.01, C.34.01.02		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		

### **Additional Description Sheet(s)**

**Description:**

The instrumentation developed in this SSC provides detection of primary coolant leakage through measurement of pressure, temperature or radiation levels within the Reactor Building or in helium piping which penetrates the Reactor Building. It also includes moisture monitoring and pressure instrumentation to detect steam in-leakage, provide operator information, and as a protection-logic input to the reactor-trip function. Finally, it includes helium flow rate instrumentation and radioactive plateout monitoring instrumentation.

### **Additional Basis Sheet(s)**

**Basis:**

Acceptance testing for vendor developed instrumentation and helium flow rate instrumentation will be completed. Acceptance testing will be conducted at vendor facility. Seismic testing will be completed, and instrumentation tested to assure compliance with SSE and OBE requirements. After delivery, tests will be repeated on-site to validate operation and compliance with as-built specifications. System mounting compatibility will also be confirmed. Results will be reviewed and testing will be repeated if equipment modifications are necessary. Advancement to the level 7 technical rating will be supported by analytical results.

Likewise, this SSC requires coordination with the circulator development team will be provided to determine engineering scale helium flow rate instrumentation testing. This testing will be accomplished with other circulator subsystem testing, and will be conducted under the circulator development scope. Seismic testing of helium flow rate measurement system will be completed (or level 6 seismic testing may be repeated, if necessary).

This SSC will monitor BOP instrumentation development testing to assure accuracy, reliability, maintainability, etc. of helium flow measurement and confirm defense-in-depth protection of nuclear/electric-plant reactor cooling capability. BOP will provide pre-installation checkout of instrumentation and documentation to advance to a level 7 technical rating.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Assure updated analysis is provided to define accuracy, reliability, maintainability, etc. of all radiological leak detection instrumentation and for Steam Generator Moisture Ingress Detection Sensors and Plateout Probe instrumentation.	GA	FD 42-60mo	100
3. Fabricate instrumentation and monitor vendor acceptance testing. Complete seismic testing, including repeat of operational testing to assure compliance with SSE and OBE operational requirements. Document to confirm qualification of safety-related protection instrumentation.	GA	FD 60-78mo	100
	Vendors	FD 72-80mo	1,600
4. Deliver instrumentation and repeat vendor acceptance tests on-site to validate operation.	GA	FD 80-84mo	200
	GA	FD 82-84mo	50
5. Verify instrumentation mounting and cable installation capability.			
6. Provide circulator flow measurement test requirements. Combine helium flow rate measurement testing with circulator pre-installation acceptance testing. Provide updated analysis to assure accuracy, reliability, maintainability, etc. of helium flow measurement instrumentation is satisfactory for level 7 technical rating.	GA	FD 42-46mo	40
	Howden	FD 46-78mo	100
7. Complete fabrication of circulator systems. Determine seismic testing which needs to be repeated (if not done previously at level 6) to assure compliance with SSE and OBE operational requirements. Document to confirm qualification of safety-related helium flow rate instrumentation.	GA	FD 72-78mo	50
	Howden	FD 72-78mo	60
8. Review BOP electric-plant instrumentation pre-installation testing. Assure updated analysis is provided to define accuracy, reliability, maintainability, etc. of temperature, pressure, flow rate, etc. instrumentation. Assure seismic testing requirements have been completed. Document for qualification of safety-related protection instrumentation.	GA	FD 60-72mo	50
	BOP	FD 60-72mo	50

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-15.5	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, Primary Circuit and Balance of Plant Instrumentation</b>			
<b>Description:</b> This SSC contains instrumentation associated with the primary circuit and the balance of plant. Some of the instrumentation will be placed in the primary helium circuit or reactor building to detect leakage of radioactive materials, potentially affecting the public or plant personnel. Balance-of-Plant (BOP) measurements, comprised of steam flow rate, temperature, pressure, etc provide defense-in-depth protection of reactor cooling functions. Instrumentation within the primary circuit or included in the secondary boundary provided by the Reactor Building, is considered Primary Circuit instrumentation. (Cont.)			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and Qualified
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The current level 7 technical rating for this SSC is based on completion of activities required to achieve a level 7 technical rating. These activities provided necessary pre-installation system testing of critical instrumentation required in NGNP, or analytical assessment to confirm the technical level of safety-related plant instrumentation. The level 7 effort provided confirmation to install this instrumentation. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (<i>list all</i>)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Install primary circuit and balance of plant instrumentation – coordinate with Reactor Building, Circulator System, BOP, etc. to assure cable separation, instrumentation identification, wiring continuity, etc and provide documentation to validate installation process. (Cont.)	GA Vendors	FD 84-96mo FD 84-96mo	200 1,500
<b>DDN(s) Supported:</b> none		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		

### Additional Description Sheet(s)

**Description:**

The instrumentation developed in this SSC provides detection of primary coolant leakage through measurement of pressure, temperature or radiation levels within the Reactor Building. Furthermore, it includes moisture monitoring and pressure instrumentation to detect steam in-leakage, provide operator information, and as a protection-logic input to the reactor-trip function. It also includes helium flow rate instrumentation and radioactive plateau monitoring instrumentation.

### Additional Basis Sheet(s)

**Basis:**

Instrumentation checkouts to confirm hot startup readiness will be completed to achieve a level 8 technical rating. This includes checkout of primary circuit instrumentation, BOP instrumentation, and helium flow rate instrumentation. Advancement to the level 8 technical rating will complete qualification of safety-related and non-safety instrumentation for the reactor protection and investment protection functions.

Helium flow rate instrumentation checkout will be incorporated in pre-hot start circulator system checking, by pressurization of the vessel to (TBD) and subsequent operation of the circulators.

The advancement to a level 8 technical rating will include validation of instrumentation functions from the control room.

### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
2. Complete pre-hot startup checkout of instrumentation. Perform power-up checks of primary circuit instrumentation. Verify instrumentation checkout from the control room.	GA	FD 84-96mo	100
	Vendors	FD 84-108mo	200
3. Operate circulators and test helium flow rate instrumentation. Verify range of operation and correlate with speed vs. flow from circulator development testing. Verify helium circulator control and flow rate measurements from the control room.	GA	FD 96-108mo	100
4. Monitor BOP electric-plant instrumentation during BOP pre-hot startup readiness testing and verify available temperature, pressure, flow rate, etc. measurements from the control room. Confirm operator information and control functions associated with instrumentation.	GA	FD 96-108mo	100
5. Provide documentation supporting qualification of primary circuit and BOP instrumentation to confirm level 8 technical rating.	GA	FD 96-108mo	200



#### **4.13 RC2-SSC-16 RPS, IPS, and PCDIS**

**TRL Rating Sheets, TRL 4 through 7**

**Technology Development Road Map**



<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-16.1	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, RPS, IPS AND PCDIS</b>			
<b>Description:</b> This SSC contains the primary components of the Reactor Control and Protection systems. This necessarily includes determining and verifying the Plant Control Room layout, the operational and safety interfaces, remote shutdown facilities, plant-wide distribution of control and protection functions, and the overall plant control architecture for effective, reliable plant operation. It includes development of the reactor control and protection algorithms, which require verification at preliminary and latter stages of the design. Since it is quite likely that the plant control architecture and the operator interface will employ modern digital hardware and software. Lastly, it also includes the necessary testing and qualification to assure reliability and safety with this type of equipment.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Proof of concept	Verified at bench scale	Verified at experimental scale
<b>TRL</b>	<b>3</b>	<b>4</b>	<b>5</b>
<b>Basis for Rating</b> (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The initial level 4 technical rating for this SSC relies primarily on work to develop a similar control and protection configuration for the New Production Reactor (NPR) program in the early 90s at General Atomics. This work established the control architecture for the NPR plant using modern digital hardware and software. Conceptual designs were completed for NPR protection and control systems. The NPR work and other MHR control development efforts justify an initial technical rating of 4 because the NPR project completed trade-off studies to define top level requirements for control room layout, plant control architecture, utilization of digital equipment and software for operator interactions, capability for multi-function plant control and safety, etc. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions</b> ( <i>list all</i> )		<b>Actionee</b>	<b>Schedule</b>
1. Complete conceptual design engineering. Determine plant control and protection scheme. Determine preliminary testing. Determine development simulator scope and requirements. Develop models. Document. (Cont.)		GA	CD 0-36mo
<b>DDN(s) Supported:</b> C34.02.02.01, C.34.02.02.02		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		

### Additional Basis Sheet(s)

Basis:

The approach provided by this work will be followed as the basis for starting the NGNP conceptual design effort. During the initial phase of the NGNP conceptual design, development of plant control algorithms, calculations to verify the preliminary control/protection design specifically for NGNP multi-function plant operation, etc. must be completed. This requires development of a real-time simulator, which in-turn supports level 5 testing to verify preliminary operator interaction and control methods. The simulator supports acceptance testing of RPS, IPS, and PCDIS equipment and software, and will be used at a higher technical rating to test the as-built, interconnected Reactor Control and Protection systems equipment. Other testing to complete level 5 readiness will confirm reliability assumptions provided by digital equipment hardware and software manufacturers.

### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
2. Use vendor supplied equipment to perform experimental scale testing of safety, protection, and control failover methods, signal noise tolerance, etc in simulated equipment operating and placement configurations. Test digital equipment robustness, susceptibility to common-mode failure, etc. considering single and multiple failure cases to confirm the reliability design for RPS, IPS and PCDIS equipment, under scenarios of operation, maintenance, etc. If necessary, provide experimental scale verification of the 2-out-of-4 redundancy scheme for safety and protection equipment. Combine test results with conceptual design verification of electric power availability, and other BOP functions critical to Reactor Control and Protection reliability. Document level 5 rating for safety-related digital computer equipment and non-safety protection and control equipment. Provide recommendations for later pilot scale testing.	GA	CD 24-36mo	600
	Vendor 1	CD 24-36mo	500
	Vendor 2	CD 24-36mo	500
	Vendor 3	CD 24-36mo	500
3. Test the preliminary operator interface using the real-time simulator at the experimental scale to evaluate critical aspects of interactive plant operation, control automation strategy, information recovery strategy, etc. Include requirements for operability and safety from NGNP participants in other design areas as well, to confirm the overall conceptual design features of the operator displays. Document necessary plant control interface testing requirements for testing activities in other NGNP design areas needed by the reactor Control and Protection systems at the next technical rating levels (level 6 or level 7). For example, circulator motor control testing will be required to verify assumptions made during conceptual design to develop PCDIS reactor flow control algorithms.	GA	CD 24-36mo	600
	Vendor 4	CD 24-36mo	400
4. Update conceptual design Reactor Control and Protection systems analysis results to confirm preliminary design readiness. Obtain preliminary review of licensability, and document issues.	GA	CD 30-36mo	900

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-16.2	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, RPS, IPS AND PCDIS</b>			
<b>Description:</b> This SSC contains the primary components of the Reactor Control and Protection systems. This necessarily includes determining and verifying the Plant Control Room layout, the operational and safety interfaces, remote shutdown facilities, plant-wide distribution of control and protection functions, and the overall plant control architecture for effective, reliable plant operation. It includes development of the reactor control and protection algorithms, which require verification at preliminary and latter stages of the design. Since it is quite likely that the plant control architecture and the operator interface will employ modern digital hardware and software. Lastly, it includes the necessary testing and qualification to assure reliability and safety with this type of equipment.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>
Technology Readiness Level			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at experimental scale	Verified at pilot scale
<b>TRL</b>	<b>4</b>	<b>5</b>	<b>6</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The level 5 rating for this SSC is based on completion of activities required to achieve a level 5 technical rating. This work included testing of operator interfaces to control plant processes using experimental scale updates of the real-time simulator. Additional experimental scale equipment tests were performed to provide reliability data not included in the original equipment supplier data. Reactor control and protection analysis results confirmed preliminary design readiness. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
Actions ( <i>list all</i> )	Actionee	Schedule	Cost (\$K)
1. Complete preliminary final design engineering. Verify plant control and protection scheme. Verify PCDIS subsystems. Oversee and obtain testing results. Update development simulator requirements for system checkout testing. Finalize development models. Document.	GA	FD 0-42mo	1,300
<b>DDN(s) Supported:</b> C34.02.02.01, C.34.02.02.02, C.31.02.01.01		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		

### **Additional Basis Sheet(s)**

**Basis:**

To advance to a level 6 technical rating, additional testing must be completed to confirm data and control signal transfer rates, and other aspects of the design. Preliminary Design (PD) plant-total instrumentation and control equipment estimates from each of the BOP, NHSS, etc. design areas will be needed to establish test requirements. Vendor supplied equipment will be used. RPS, IPS, and PCDIS data-highway communication capacity, considering the PD data-highway hierarchy within the combined structure of these systems and their interfacing plant systems will be tested. Equipment tests to verify storage, formatting, and on-line retrieval of stored data for use in trend displays, tech spec information displays, safety-console information displays, and other critical operator information displays, will be included. Also, tests to verify the reliability of Reactor Control and Protection equipment operating in locations outside the control room must be included. The level 6 rating will require circulator test data and updates of the control development simulator facility to test the PCDIS reactor flow control algorithms. RPS, IPS and PCDIS acceptance tests (at level 7) will also be based, in part, on these tests.

<b>Additional Action Sheet(s)</b>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
2. Confirm information transfer rates by pilot scale testing of representative digital equipment configurations using vendor supplied hardware and software to drive communication functions. Test preliminary specification of data-highway(s) transmission capacity and information hierarchy. Resolve issues of transfer speed, data loss, synchronization, etc. to confirm readiness to begin RPS, IPS, and PCDIS final design equipment specifications.	GA	FD 24-42mo	200
	Vendor 1	FD 30-42mo	1,400
3. Develop pilot scale facilities for RPS, IPS, and PCDIS plant-distributed control and instrumentation equipment testing, using vendor supplied equipment. Address operating lifetime, on-line maintenance access, and other issues requiring placement specific test data not available from prospective equipment vendors. Where necessary, provide separate pilot scale test configurations for RPS/IPS protection systems and PCDIS control systems to separate safety licensing issues during this testing. Verify channel separation, isolation from non-safety equipment, failed-channel operation, etc. for RPS and IPS to obtain preliminary confirmation of licensability necessary to issue final design procurement specifications for vendor supplied equipment. Issue requests for necessary Reactor Control and Protection testing required in other NGNP design areas, such as communication signal noise environment, temperature/humidity/pressure environment, motion/vibration environment, electrical quality, cooling quality, etc. needed by the Reactor Control and Protection systems to issue the final design specifications. Combine the test results, resolve issues, and document overall results of pilot scale equipment testing to confirm final design readiness.	GA	FD 30-42mo	400
	Vendor 1	FD 12-42mo	1,200
	Vendor 2	FD 12-42mo	500
4. Procure checkout interfaces for development simulator.	GA	FD 30-42mo	200
	Vendor 4	FD 36-42mo	800
5. Recommend testing procedures to obtain data not available from previous circulator development tests in order to confirm or update previous PCDIS design assumptions with respect to circulator flow vs. circulator motor speed over the NGNP operating range. Update control development simulator utilizing test specific representation of circulator motor/speed control. Repeat helium flow control algorithm development tests to assure that helium flow control by means of variable frequency circulator motor speed controllers will not invoke limit-cycling or cause unexpected interaction with commands from the PCDIS. Resolve issues and update PCDIS algorithm design documentation.	GA	FD 12-42mo	900
6. Provide reactor control and protection analysis results to confirm final design readiness.	GA	FD 36-42mo	1,000

<b>TRL Rating Sheet</b>				
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-16.3	<b>Revision:</b> 0		
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component	<input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, RPS, IPS AND PCDIS</b>				
<b>Description:</b> This SSC contains the primary components of the Reactor Control and Protection systems. This necessarily includes determining and verifying the Plant Control Room layout, the operational and safety interfaces, remote shutdown facilities, plant-wide distribution of control and protection functions, and the overall plant control architecture for effective, reliable plant operation. It includes development of the reactor control and protection algorithms, which require verification at preliminary and latter stages of the design. Since it is quite likely that the plant control architecture and the operator interface will employ modern digital hardware and software. Lastly, it includes the necessary testing and qualification to assure reliability and safety with this type of equipment.				
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS	<input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>		<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>				
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level	
Generic Definitions ( <i>abbreviated</i> )	Verified at experimental scale	Verified at pilot scale	Verified at engineering scale	
<b>TRL</b>	<b>5</b>	<b>6</b>	<b>7</b>	
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
The level 6 rating for this SSC is based on completion of activities required to achieve a level 6 technical rating. This work included pilot scale testing of plant-distributed equipment, signal communications, life time under operating conditions, etc. and compliance with safety-related regulatory requirements for channel separation, etc. The PCDIS control design was also updated to include information derived from circulator development testing. (Cont)				
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>				
<b>Actions (list all)</b>		<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Complete final design engineering. Oversee and support procurement of IPS, RPS, and PCDIS equipment. Support and oversee all acceptance testing. Provide development simulator for testing. Validate plant control and protection scheme. Document.  (Cont.)		GA	FD 42-84mo	1,500
<b>DDN(s) Supported:</b> C.31.02.01.01, C.33.01.01.01		<b>Technology Case File:</b>		
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer		
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics			

### Additional Basis Sheet(s)

Basis:

Reactor control and protection analysis results verified software embedded reactor control algorithms and confirmed final design readiness. This provided the basis for the Reactor Control and Protection systems procurement specifications, as well as parallel development of a full-scope training simulator. To advance to a level 7 rating, additional testing must be completed to finalize the operator and hardware interfaces for RPS, IPS, and PCDIS. Software validation acceptance test procedures must be developed and completed, and engineering scale testing must be performed to validate the as-built Reactor Control and Protection systems hardware and software, and to confirm RPS, IPS, and PCDIS installation readiness. The level 7 rating will also require seismic testing of systems before installation can be completed.

### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
2. Procure RPS, IPS and PCDIS equipment.	GA	FD 42-78mo	800
	Vendor 1	FD 60-78mo	30,000
	Vendor 2	FD 60-78mo	16,000
3. Develop on-site engineering scale equipment test configurations, and procedures, to confirm installation checkout capabilities, online and offline maintenance capabilities, etc. using duplicate equipment supplied by vendor. Complete these tests and verify that all adjustments are made by the vendor(s) before delivery.	GA	FD 42-60mo	900
	Vendor 1	FD 48-60mo	1,000
	Vendor 2	FD 48-60mo	800
4. Configure (or duplicate) the control development simulator to provide final engineering scale testing of RPS, IPS and PCDIS equipment. Determine testing to validate software design for combined RPS, IPS and PCDIS operator control and plant information interfaces. Determine plant control and protection systems testing requirements and prepare combined (and separate) RPS, IPS and PCDIS acceptance test procedures to be performed by the vendor(s) and verified before acceptance of equipment. Validate as-built Reactor Control and Protection systems software and equipment. Complete pre-delivery acceptance tests and post-delivery on-site acceptance tests to confirm installation readiness.	GA	FD 60-78mo	500
	Vendor 1	FD 72-84mo	200
5. Complete seismic qualification tests and issue final report to confirm installation readiness.	GA	FD 78-84mo	100
	Vendor 5	FD 78-84mo	3,000
6. Provide final reactor control and protection analysis results to confirm installation readiness and finalize Reactor Control and Protection systems licensing acceptance process.	GA	FD 80-84mo	200

<b>TRL Rating Sheet</b>			
<b>Vendor:</b> GA	<b>Document Number:</b> RC2-SSC-16.4	<b>Revision:</b> 0	
<input type="checkbox"/> Area	<input type="checkbox"/> System	<input type="checkbox"/> Subsystem/Structure	<input checked="" type="checkbox"/> Component <input type="checkbox"/> Technology
<b>Title: Reactor Control and Protection, RPS, IPS AND PCDIS</b>			
<b>Description:</b> This SSC contains the primary components of the Reactor Control and Protection systems. This necessarily includes determining and verifying the Plant Control Room layout, the operational and safety interfaces, remote shutdown facilities, plant-wide distribution of control and protection functions, and the overall plant control architecture for effective, reliable plant operation. It includes development of the reactor control and protection algorithms, which require verification at preliminary and latter stages of the design. Since it is quite likely that the plant control architecture and the operator interface will employ modern digital hardware and software. Lastly, it includes the necessary testing and qualification to assure reliability and safety with this type of equipment.			
<b>Area:</b>	<input checked="" type="checkbox"/> NHSS	<input type="checkbox"/> HTS	<input type="checkbox"/> HPS <input type="checkbox"/> PCS <input type="checkbox"/> BOP
<b>PASSC:</b>	<b>Parent:</b>	<b>WBS:</b>	
<b>Technology Readiness Level</b>			
	Next Lower Rating Level	Current Rating Level	Next Higher Rating Level
Generic Definitions ( <i>abbreviated</i> )	Verified at pilot scale	Verified at engineering scale	Tested and qualified
<b>TRL</b>	<b>6</b>	<b>7</b>	<b>8</b>
Basis for Rating (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
The level 7 rating for this SSC is based on completion of activities required to achieve a level 7 technical rating. This work completed all pre-delivery and post-delivery acceptance testing of RPS, IPS, and PCDIS equipment and validation of the installed software. Final reactor control and protection analysis results confirmed installation readiness and provided the final licensing acceptance process for Plant Control and Protection systems. (Cont.)			
Outline of plan to get from current level to next level. (Check box if continued on additional sheets) <input checked="" type="checkbox"/>			
<b>Actions (list all)</b>	<b>Actionee</b>	<b>Schedule</b>	<b>Cost (\$K)</b>
1. Install Plant Control and Protection systems and complete reconnection checkout procedures for equipment moved from pre-installation checkout locations or which have been reconnected (from the level 7 simulation configuration) for plant operation. (Cont.)	GA Vendor 1 Vendor 2	FD 84-96mo FD 84-96mo FD 84-96mo	1,500 1,000 500
<b>DDN(s) Supported:</b> none		<b>Technology Case File:</b>	
<b>Subject Matter Expert Making Determination:</b>		Dale Pfremmer	
<b>Date:</b> 10/23/08	<b>Originating Organization:</b> General Atomics		



### Additional Basis Sheet(s)

Basis:

To advance to a level 8 rating, the Plant Control and Protection systems must be installed and reconnected (from validation test configurations to operational configurations), using moderate test procedures to validate this process. The level 8 rating will also require flow and equipment operation testing as required by other systems and by other Reactor Control and Protection SSCs. Therefore, other systems must be installed and connected to test the Reactor Control and Protection systems.


### Additional Action Sheet(s)

Actions <i>(list all)</i>	Actionee	Schedule	Cost (\$K)
Verify signal communications, signal scaling and continuity, power-up and power-down features, fire-suppression and other equipment protection features, power failure recovery features, etc. Complete QA check-off procedures to validate final configuration of hardware and software. Complete tests of NHSS, BOP, etc. equipment (dependent on Reactor Control and Protection systems) as allowed within limits of prior-to-hot-startup operational capabilities. Repeat QA and testing for issues requiring resolution. Document final status for hot startup readiness.			
2. Check vessel pressurization equipment and pressurize vessel to (TBD). Operate circulators, and verify helium flow control capabilities. Complete other operation and instrumentation tests, including operator information and procedures, control room supervisory information and procedures, and information storage verification tests; remote shutdown facility tests; BOP and Hydrogen Plant control system checks; safety and protection trip-setpoint tests; maintenance tests; etc. to verify hot-startup readiness. Update the status. Include off-line analysis, from the simulator, comparing expected control and protection test results and actual results, to confirm hot startup readiness. Verify regulatory acceptance of Reactor Control and Protection systems hot startup readiness at level 8.	GA Vendor 1 Vendor 2	FD 96-108mo FD 96-108mo FD 96-108mo	1,100 400 200

4/21/2009 11:08 AM

# Revision 0

## RC2-SSC16- Reactor Control and Protection System Technology Roadmap



## **5 TECHNOLOGY DEVELOPMENT SCHEDULES**

Figure 5-1 provides an overall technology development schedule that shows all of the technology development activities identified in the TDRMs and Test Plans for all of the critical SSC. This schedule was compiled from the schedule information provided in the Test Plans. A second schedule that includes just the testing identified in the Test Plans as potentially being performed in the CTF is provided in Figure 5-2. It is important to note that most, if not all of the tests for which the CTF has been identified as a potential location for the test could be done elsewhere should the CTF not be available. However, assuming that the CTF is built and is available, it would be a logical location for performing the tests identified in Figure 5-2.




Figure 5-1. Overall Schedule for NGNP Technology Development




Figure 5-1. Overall Schedule for NGNP Technology Development (2 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (3 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (4 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (5 of 11)






Figure 5-1. Overall Schedule for NGNP Technology Development (6 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (7 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (8 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (9 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (10 of 11)




Figure 5-1. Overall Schedule for NGNP Technology Development (11 of 11)




Figure 5-2. Schedule for Potential Testing in CTF

## 6 REFERENCES

- [GA TDP 2007] Hanson, D., "NGNP Umbrella Technology Development Plan," GA Report PC-000543, Rev. 0, July 2007
- [GA TDRM 2008] "NGNP Technology Development Road Mapping Report," General Atomics Report PC-000580, December 2008
- [GA 2008] Vollman, R., "NGNP Composites R&D Technical Issues Study," General Atomics Report 911125, Rev. 0, October 2008
- [GA 2009] Vollman, R., "Effect of Reactor Outlet Helium Temperature on the Need for Composites in the NGNP," General Atomics Report 911175, Rev. 0, to be issued
- [INL 2007] "NGNP Engineering White Paper: High Temperature Gas Reactor – Component Test Facility," INL Report INL/EXT-07-13146, Rev. 1, November 2007
- [INL 2008a] Balls, V., D. Duncan, and S. Austad, "The Component Test Facility – A National User Facility for Testing of High Temperature Gas-Cooled Reactor (HTGR) Components and Systems," Paper HTR2008-58250, Proceedings of the 4th International Topical Meeting on High Temperature Reactor Technology HTR2008, September 28-October 1, 2008, Washington, DC USA
- [INL 2008b] "High Temperature Gas-Cooled Reactor (HTGR) Component Test Facility (CTF) – Technical and Functional Requirements," INL Report INL/EXT-08-14150, Rev. 0, April 2008
- [INL 2008c] "Technical Readiness Level Plan," INL Report INL/EXT-08-14251, draft, May 2008
- [INL 2008d] "Technical Program Plan for the Next Generation Nuclear Plant/Advanced Gas Reactor Fuel Development and Qualification Program," INL Report INL/EXT-05-00465, Rev. 2, June 2008
- [PCDSR 2007] "NGNP and Hydrogen Production Preconceptual Design Studies Report," GA Report 911107, Rev. 0, July 2007



[SRM 2009] "Next Generation Nuclear Plant System Requirements Manual," INL Report INL/EXT-07-12999, Rev. 2, March 2009

[TDRM 2009] "Next Generation Nuclear Plant Technology Development Roadmaps: The Technical Path Forward," INL Report INL/EXT-08-15148, January 2009



**GENERAL ATOMICS**

P.O. BOX 85608 SAN DIEGO, CA 92186-5608 (858) 455-3000